



State of Utah

JON M. HUNTSMAN, JR.  
Governor

GARY R. HERBERT  
Lieutenant Governor

Department of Administrative Services

KIMBERLY K. HOOD  
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN  
Director

## ADDENDUM #4

Date: January 12, 2007

To: Contractors

From: S'ean Crawford, Project Manager, DFCM

Reference: West Jordan Third District Court  
Courtroom No. 33 Build-Out  
DFCM Project No. 06073150

Subject: **Addendum No. 4**

Pages	Addendum	2	pages
	<u>Owner Provided Contractor Installed Items</u>	<u>1</u>	<u>page</u>
	<b>Total</b>	<b>3</b>	<b>pages</b>

---

***Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.***

- 4.1 SCHEDULE CHANGES – There are no changes to the schedule per this Addendum. The current schedule is the revised schedule issued with Addendum #2.**
- 4.2 Contractor Questions #6 and #7 - Please find attached the list of Owner provided and Contractor installed items.**
- 4.3 For details D5/AE501, B2/AE502 and B3/AE502: The 2"x2" Steel Post is to be welded to the 3/8" base plate with a 3/16" single fillet weld-all-around.**
- 4.4 All millwork must be delivered to the space and allowed 72 hours for the temperature to stabilize prior to installation.**

- 4.5 Contractor Questions #8 and #9 - Wilkinson Electrical was the sub-contractor responsible for the electrical portion of the original construction. Utah Controls was the sub-contractor to Wilkinson Electrical that installed the work in specification sections 16724 - Access Control Systems, 16725 - Duress Alarm System, 16760 - Intercommunications System, and 16782 - Video Surveillance System.**

**Utah Controls is under contract to maintain the systems.**

**Phone (801) 990-1950**

**Fax (801) 990-1955**

**Mountain Alarm is under contract to monitor the alarm systems and contact the County Sheriff. Bidding Contractors are not to contact Mountain Alarm.**

**The Contractor awarded this project must coordinate installation, programming and the initialization of these systems with the DFCM onsite personnel, Utah Controls and Mountain Alarm.**

- 4.6 Contractor Question #13 – Contractor shall install welded wire fabric in the lightweight concrete. The installation shall conform to the Wire Reinforcement Institute’s Structural Welded Wire Reinforcement Standard Manual of Practice.**

**Fabric shall be 4x4–W2.0x W2.0 and embedded a minimum of 1” from any surface.**

- 4.7 Contractor Question #14 – The EPS foam under the raised concrete platform work shall meet the following minimum requirements;**

**Density: 1.5 – 2.0 pcf.**

**Flame spread: ASTM E 84, 25 or less**

**Smoke Developed: ASTM E 84, 450 or less.**

**End of Addendum #4**

## Schedule of Owner Provided - Contractor Installed Items

**West Jordan Third District Court  
Courtroom No. 33 Build-Out  
DFCM Project No. 06073150**

Symbol Mark	Description	# Required	Provided	Room #	Sheet Ref.
VM-1	Holding Cell Light	6*	7	3201	A2-EL101
One that is required is installed, 2 each of the lights provided are attic stock for the owner.					
VM-2	Holding Cell Entry Light	2	2	3201 - Entries	A2-EL101
Cabinet	Judges Robe Cabinet	2	2	3505 & 3506	C1-AE200A
Not Assigned	Holding Cell Combination Water Closet / Sink - Type 1	3	3	Holding Cells	1-PL107
Not Assigned	HC Holding Cell Combination Water Closet / Sink - Type 2	1	1	HC Holding Cell	1-PL107
Flush Valves	Holding Cell Concealed Water Closet Flush Valves	4	4	Not Shown	Not Shown
Faucet Valves	Holding Cell Concealed Sink Mixing Valves	4	3	Not Shown	Not Shown
Not Assigned	2 x 2 Steel Support Posts - Approx. 30" height		7	3309	Various
	Contractor to verify height and usable location.				
All of the required doors are Owner provided and are on site. The frame for door 3111A shall be contractor provided, all other door frames are Owner provided and are on site.					
Awarded Contractor shall relocate all of the existing millwork attic stock in Courtroom 33 into the adjacent Courtroom shell space.					