



State of Utah

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

Department of Administrative Services

RICHARD K. ELLIS
Executive Director

Division of Facilities Construction and Management

F. KEITH STEPAN
Director

ADDENDUM

Date: 9 November 2006

To: Contractors

From: Jim Russell Project Manager, DFCM

Reference: Provo Fourth District Court
Fire Alarm Upgrade
DFCM Project No. 06107150

Subject: **Addendum No. 1**

Pages	Addendum	1 page
	<u>Engineers Addendum</u>	<u>2 pages</u>
	Total	3 pages

Note: This Addendum shall be included as part of the Contract Documents. Items in this Addendum apply to all drawings and specification sections whether referenced or not involving the portion of the work added, deleted, modified, or otherwise addressed in the Addendum. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

1.1 **SCHEDULE CHANGES** – There are no schedule changes per this addendum.

1.2 **GENERAL**

1.2.1 Protection Consultants Inc. Addendum 1

End of Addendum #1



Date: November 9, 2006

To: Jim Russell
State of Utah DFCM

From: Greg Jones
Protection Consultants, Inc.

Project: Provo Fourth District Court – DFCM 06107150

Subject: Revisions for Addendum 1

Based on conditions observed and discussions during the pre-bid walkthrough held Thursday November 2, 2006 at the Provo City Courts Building, minor revisions to the scope of work for the fire alarm system must be made. Due to the simple nature of the revisions, no revised drawings will be issued. Each change will be described below in sufficient detail to allow the bidders to adjust their price accordingly.

1. Revise the last sentence of fire alarm key note 8 (present on all drawing sheets) to read as follows:

Wiring from fire alarm control relays to elevator control panel by fire alarm contractor. Connections to elevator recall controls by elevator system maintenance contractor. Cost of work performed by elevator system maintenance contractor to be paid by the owner.
2. Revise the last sentence of fire alarm key note 9 (present on all drawing sheets) to read as follows:

Cost of service call (if required) by elevator system maintenance contractor to be paid by owner.
3. Delete key note 14 from schedule of fire alarm key notes (present on all sheets). No interface with building security control panel will be required.
4. Add an addressable control relay at each exit door leading to the building exterior from the northeast (sheet FA-1 drawing coordinate J8) and southeast (sheet FA-1 drawing

coordinate J4) exit stairs. Connect control relay to delayed egress locks on exit doors to allow immediate release of doors under fire alarm conditions.

5. Each courtroom on sheets FA-2, FA-3 and FA-4 (9 courtrooms total) includes two control relays at west exit doors from room to bypass security locks and allow immediate release of doors upon receipt of fire alarm signal at FACP (see key note 6). One control relay is shown at the public exit door of each courtroom and another is shown at the exit door from the judge's bench of each courtroom. The door from each judge's bench is not secure and consequently, the control relays (9 total) shown on the fire alarm drawings for those doors will not be required.