

GENERAL DEMOLITION NOTES



A. CONTRACTOR SHALL PERFORM ALL DEMOLITION AND PREPERATION WORK AS SHOWN ON DRAWINGS AND AS REQUIRED FOR A COMPLETE AND PROPOER JOB. CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID TO VERIFY EXTENT OF REQUIRED DEMOLITION AND PREPERATION WORK. THE CONTRACTOR SHALL REMOVE FROM THE SITE AND DISPOSE OF ALL DEMOLITION ITEMS IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL LAWS.

B. ALL ITEMS NOT INDICATED FOR REMOVAL SHALL REMAIN AND SHALL BE PROTECTED. ANY ITEMS DAMAGED SHALL BE REPAIRED TO MATCH THE ADJACENT SURFACE.

DEMOLITION KEYED NOTES

- 1 EXISTING MASONRY WALL TO BE DEMOLISHED.
- 2 EXISTING STUD WALL TO BE DEMOLISHED.
- 3 REMOVE CASEWORK COMPLETE.
- 4 REMOVE ACCORDIAN DOOR COMPLETE.
- 5 REMOVE CARPET AND RUBBER BASE COMPLETE.
- 6 REMOVE CASEWORK AND SALVAGE TO OWNER.
- 7 REMOVE WINDOW AND FRAME COMPLETE.
- 8 RELOCATE SIGN IF REQUIRED FOR NEW CONSTRUCTION.
- 9 REMOVE GLASS BLOCK COMPLETE.
- 10 REMOVE DOOR AND HARDWARE AND SALVAGE TO OWNER. FRAME TO BE DEMOLISHED.
- 11 REMOVE COUNTER DOOR AND SALVAGE TO OWNER.
- 12 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR TO ROOM 110 & RELOCATE HARDWARE TO ROOM 104. DOOR FRAME TO BE DEMOLISHED.
- 13 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 107. DOOR FRAME TO BE DEMOLISHED.
- 14 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 102. DOOR FRAME TO BE DEMOLISHED.
- 15 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 105. DOOR FRAME TO BE DEMOLISHED.
- 16 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR TO ROOM 104 & RELOCATE HARDWARE TO ROOM 110. DOOR FRAME TO BE DEMOLISHED.
- 17 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 108. DOOR FRAME TO BE DEMOLISHED.
- 18 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 103. DOOR FRAME TO BE DEMOLISHED.
- 19 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 114. DOOR FRAME TO BE DEMOLISHED.
- 20 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 115. DOOR FRAME TO BE DEMOLISHED.
- 21 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 106. DOOR FRAME TO BE DEMOLISHED.
- 22 REMOVE DOOR AND HARDWARE AND RELOCATE DOOR AND HARDWARE TO ROOM 113. DOOR FRAME TO BE DEMOLISHED.

KEY PLAN



HFSArchitects
ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT

STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE


MARK	DATE	DESCRIPTION

DATE:	June 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE

DEMO FLOOR
PLAN

AD101




GENERAL DEMOLITION NOTES

A. CONTRACTOR SHALL PERFORM ALL DEMOLITION AND PREPERATION WORK AS SHOWN ON DRAWINGS AND AS REQUIRED FOR A COMPLETE AND PROPOER JOB. CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID TO VERIFY EXTENT OF REQUIRED DEMOLITION AND PREPERATION WORK. THE CONTRACTOR SHALL REMOVE FROM THE SITE AND DISPOSE OF ALL DEMOLITION ITEMS IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL LAWS.



B. ALL ITEMS NOT INDICATED FOR REMOVAL SHALL REMAIN AND SHALL BE PROTECTED. ANY ITEMS DAMAGED SHALL BE REPAIRED TO MATCH THE ADJACENT SURFACE.

ALTERNATE #1 DEMOLITION LEGEND



REMOVE CARPET AND RUBBER BASE COMPLETE.

KEY PLAN



HFS*Architects*

ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT

STUDENT SERVICES
REMODEL

DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	June 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE

ALTERNATE
DEMO FLOOR
PLAN




GENERAL DEMOLITION NOTES



A. CONTRACTOR SHALL PERFORM ALL DEMOLITION AND PREPERATION WORK AS SHOWN ON DRAWINGS AND AS REQUIRED FOR A COMPLETE AND PROPER JOB. CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID TO VERIFY EXTENT OF REQUIRED DEMOLITION AND PREPERATION WORK. THE CONTRACTOR SHALL REMOVE FROM THE SITE AND DISPOSE OF ALL DEMOLITION ITEMS IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL LAWS.

B. ALL ITEMS NOT INDICATED FOR REMOVAL SHALL REMAIN AND SHALL BE PROTECTED. ANY ITEMS DAMAGED SHALL BE REPAIRED TO MATCH THE ADJACENT SURFACE.

CEILING DEMOLITION LEGEND



KEY PLAN



HFS*Architects*

A RCHITECTURE
I NTERIORS
P LANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT

STUDENT SERVICES REMODEL

DAVIS APPLIED TECHNOLOGY
COLLEGE

[illegible]

DATE: June 2007

AGENCY PROJECT NO:

HFSA PROJECT NO:	0615.02
------------------	---------

CAD DWG FILE NO:	
DRAWN BY:	CAM

DRAWN BY:	SAM
CHECKED BY:	

DESIGNED BY:	BS
--------------	----

DWG TYPE:
ARCHITECTURAL PHASE:

SHEET TITLE

REFLECTED CEILING
DEMOLITION
PLAN

AD111


SHEET 4 OF 4

D


C

B

A



A3 FLOOR PLAN
1/8" = 1'-0"



GENERAL NOTES

- A. ALL DIMENSIONS TAKEN FROM FINISHED FACE AND/OR CENTER LINE OF NEW AND EXISTING WALLS.
- B. IF A CONFLICT OCCURS BETWEEN DRAWINGS, DRAWINGS AND SPECIFICATIONS, SPECIFICATION SECTIONS AND DIVISIONS OR BETWEEN OTHER PARTS OF THESE CONSTRUCTION DOCUMENTS OR THESE DOCUMENTS AND ANY CODE REQUIREMENT, THE CONTRACTOR MAY REQUEST CLARIFICATION DURING THE BIDDING PERIOD. OTHERWISE THE MOST STRINGENT REQUIREMENTS SHALL APPLY AND BE PART OF THE CONTRACT AT NO ADDITIONAL COST TO THE OWNER.
- C. ALL WORK AND MATERIALS SHALL BE IN FULL CONFORMANCE WITH THE LATEST FEDERAL, STATE AND LOCAL CODES LAWS AND ORDINANCES, INCLUDING THEIR MOST RECENT REVISIONS, AMENDMENTS AND INTERPRETATIONS.
- D. THE GENERAL CONTRACTOR SHALL BRING TO THE ATTENTION OF THE ARCHITECT, FOR IMMEDIATE RESOLUTION, ANY NON-CONFORMING CONDITIONS WHICH MAY BE FOUND IN EXISTING FIELD CONDITIONS.
- E. PATCH AND REPAIR ANY DAMAGE TO ANY SURFACE, EQUIPMENT ETC NOT IN THIS SCOPE OF WORK.

FINISH LEGEND

FLOOR / BASE
RM NUM
F T W


WALL

- A. CARPET TILE WITH RUBBER BASE.
1. PAINT NEW & EXISTING GYPSUM BOARD & CMU WALLS

PARTITION LEGEND

- EXISTING STUD WALL TO REMAIN, TYPICAL
- NEW 3/5/8" METAL STUD WALL W/ 5/8" GYPSUM BOARD BOTH SIDES TO 6" ABOVE FINISH CEILING, BRACED TO STRUCTURE ABOVE AT 4'-0" O.C. SEE DETAIL B5/AE501.
- MATCH EXISTING 4" HIGH CMU. TOOTH INTO EXISTING RUNNING BOND PATTERN. ADD #5 REBAR VERTICAL REINFORCING @ 32" O.C. ADD #5 REBAR, HORIZONTAL JOINT REINFORCING @ 32" O.C., TIE BACK INTO EXISTING WALL.
- MATCH EXISTING 8" HIGH CMU. TOOTH INTO EXISTING RUNNING BOND PATTERN. ADD #5 REBAR VERTICAL REINFORCING @ 32" O.C. ADD #5 REBAR, HORIZ. JOINT REINFORCING @ 32" O.C., TIE BACK INTO EXISTING WALL.

KEY PLAN



STUDENT SERVICES REMODEL DAVIS APPLIED TECHNOLOGY COLLEGE

MARK	DATE	DESCRIPTION


DATE:	June 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE

FLOOR PLAN

AE101

SHEET 5 OF



GENERAL NOTES

A. ALL DIMENSIONS TAKEN FROM FINISHED FACE AND/OR CENTER LINE OF NEW AND EXISTING WALLS.

B. IF A CONFLICT OCCURS BETWEEN DRAWINGS, DRAWINGS AND SPECIFICATIONS, SPECIFICATION SECTIONS AND DIVISIONS OR BETWEEN OTHER PARTS OF THESE CONSTRUCTION DOCUMENTS OR THESE DOCUMENTS AND ANY CODE REQUIREMENT, THE CONTRACTOR MAY REQUEST CLARIFICATION DURING THE BIDDING PERIOD. OTHERWISE THE MOST STRINGENT REQUIREMENTS SHALL APPLY AND BE PART OF THE CONTRACT AT NO ADDITIONAL COST TO THE OWNER.



C. ALL WORK AND MATERIALS SHALL BE IN FULL CONFORMANCE WITH THE LATEST FEDERAL, STATE AND LOCAL CODES LAWS AND ORDINANCES, INCLUDING THEIR MOST RECENT REVISIONS, AMENDMENTS AND INTERPRETATIONS.

D. THE GENERAL CONTRACTOR SHALL BRING TO THE ATTENTION OF THE ARCHITECT, FOR IMMEDIATE RESOLUTION, ANY NON-CONFORMING CONDITIONS WHICH MAY BE FOUND IN EXISTING FIELD CONDITIONS.

E. PATCH AND REPAIR ANY DAMAGE TO ANY SURFACE, EQUIPMENT ETC NOT IN THIS SCOPE OF WORK.

FINISH LEGEND		
FLOOR / BASE	ROOM NAME RM NUM F T W	WALL
A. CARPET TILE WITH RUBBER BASE.	1.	PAINT NEW & EXISTING GYPSUM BOARD & CMU WALLS

ALTERNATE #1 FLOOR LEGEND		
	CARPET WITH RUBBER BASE.	



HFSArchitects
ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT


STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION


DATE:	June 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE	
FLOOR PLAN ALTERNATE #1	
AE102	
SHEET	6 OF


D




C1 ROOM 104 INTERIOR ELEVATION
1/4" = 1'-0"




C3 CASEWORK SECT. - HALLWAY 120
1" = 1'-0"





C4 HALLWAY 120 NORTH INTERIOR ELEV.
1/4" = 1'-0"




B1 CASEWORK SECTION - ROOM 107
1" = 1'-0"





B2 ROOM 107 INTERIOR ELEV.
1/4" = 1'-0"



A1 SHELVING SECTION - RM 104
1/2" = 1'-0"



A2 ROOM 102 INTERIOR ELEV.
1/4" = 1'-0"



HFSArchitects
ARCHITECTURE
INTERIORS
PLANNING
1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT

STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	June 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE


INTERIOR
ELEVATIONS

AE401
SHEET 8 OF


D

C


B




A1 BRACING DETAIL
3"=1'-0"




A2 HANGER WIRE DETAIL
FULL SCALE




A3 BRACING DETAIL
NTS




A4 CEILING DETAIL
NTS



B5 WALL DETAIL
3"=1'-0"



A5 BRACING DETAIL
NTS



HFSArchitects
ARCHITECTURE
INTERIORS
PLANNING
1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT

STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	June 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	


SHEET TITLE

CEILING @ MISC.
DETAILS

AE501
SHEET 9 OF

[illegible]

AE602
SHEET 11 OF



MECHANICAL LEGEND											
SYMBOL	ABR.	DESCRIPTION	SYMBOL	ABR.	DESCRIPTION	SYMBOL	ABR.	DESCRIPTION	SYMBOL	ABR.	DESCRIPTION
GENERAL TERMINOLOGY			AIR SIDE			WET SIDE			WET SIDE CONT		
<div><div><div><div><div>A</div><div>ME-101</div></div></div><div>SECTION LETTER DESIGNATION</div></div><div><div><div><div>A2</div></div></div><div>DETAIL NUMBER DESIGNATION CORRESPONDING WITH GRID LOCATION</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>EXISTING AIR DUCT TO BE REMOVED</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>PUMP</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>PITCH DOWN</div></div></div>		
			<div><div><div><div><div></div><div></div></div><div></div></div><div>EXISTING AIR DUCT TO REMAIN</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>UNION</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>ELBOW UP</div></div></div>		
<div><div><div><div><div>AH</div><div>1</div></div></div><div>MECHANICAL EQUIPMENT DESIGNATION</div></div><div><div><div><div>AH</div><div>1</div></div></div><div>EQUIPMENT ITEM DESIGNATION</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>NEW AIR DUCT</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>MANUAL ACTUATOR (BALL, BUTTERFLY, NEEDLE, ETC. VALVES)</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>ELBOW DOWN</div></div></div>		
			<div><div><div><div><div></div><div></div></div><div></div></div><div>RECT. TO RECT. AIR DUCT TAKE-OFF</div></div></div>						<div><div><div><div><div></div><div></div></div><div></div></div><div>TEE UP</div></div></div>		
<div><div><div><div><div>AH</div><div>1</div></div></div><div>MECHANICAL EQUIPMENT DESIGNATION</div></div><div><div><div><div>AH</div><div>1</div></div></div><div>EQUIPMENT ITEM DESIGNATION</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>RECT. TO RND. AIR DUCT TAKE-OFF</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>MANUAL ACTUATOR (GATE, GLOBE, S&D, OS&Y, ETC. VALVES)</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>TEE DOWN</div></div></div>		
			<div><div><div><div><div></div><div></div></div><div></div></div><div>RND. TO RND. AIR DUCT TAKE-OFF</div></div></div>						<div><div><div><div><div></div><div></div></div><div></div></div><div>EXISTING PIPING TO BE REMOVED</div></div></div>		
<div><div><div><div><div>D-1</div><div>CFM</div></div></div><div>REGISTER, GRILL OR DIFFUSER DESIGNATION WITH BALANCING CFM LISTED BELOW</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>RECT. TAKE-OFF AT END OF MAIN</div></div></div>			<div><div><div><div><div>M</div></div></div><div>ELECTRIC MOTOR ACTUATOR</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>EXISTING PIPING TO REMAIN</div></div></div>		
			<div><div><div><div><div></div><div></div></div><div></div></div><div>BURIED OR UNDER FLOOR DUCT</div></div></div>			<div><div><div><div><div>S</div></div></div><div>SOLENOID ACTUATOR</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>NEW PIPING</div></div></div>		
<div><div><div><div><div>R-1</div></div></div><div>GRILLE, OR LOUVER DESIGNATION WHERE BALANCING NOT REQUIRE</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>FLEXIBLE AIR DUCT</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>THREADED OR SWEAT VALVE CONNECTION</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>NATURAL GAS PIPING</div></div></div>		
			<div><div><div><div><div></div><div></div></div><div></div></div><div>LINED DUCT</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>GATE VALVE</div></div></div>					
<div><div><div><div><div></div><div></div></div><div></div></div><div>VANED ELBOW</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>GLOBE VALVE - STRAIGHT PATTERN</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>RADIUS ELBOW</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>GLOBE VALVE - ANGLE PATTERN</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>CONCENTRIC DUCT TRANSITION</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>MOTORIZED 2-WAY CONTROL VALVE</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>ECCENTRIC DUCT TRANSITION</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>MOTORIZED 3-WAY CONTROL VALVE</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>FLEXIBLE AIR DUCT</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>CHECK VALVE</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>VOLUME DAMPER</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>PRV PRESSURE REDUCING VALVE</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>SUPPLY AIR DIFFUSER</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>PRV PRESSURE REDUCING VALVE W/ CHECK</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>RETURN AIR, FRESH AIR, AND TRANSFER AIR</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>CBV CIRCUIT BALANCING VALVE</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>CEILING MOUNTED EXHAUST FAN OR EXHAUST GRILLE</div></div></div>			<div><div><div><div><div></div><div></div></div><div></div></div><div>BV BALL VALVE</div></div></div>								
<div><div><div><div><div></div><div></div></div><div></div></div><div>RETURN OR OUTSIDE AIR DUCT UP</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>SUPPLY DUCT UP</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>EXHAUST AIR INTAKE UP</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>RETURN OR OUTSIDE AIR DUCT DOWN</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>SUPPLY DUCT DOWN</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>EXHAUST DUCT DOWN</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>ROUND DUCT UP</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>LOWER DUCT DOWN</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>FLEXIBLE DUCT CONNECTION</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>LOWER DUCT DOWN</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>FLEXIBLE DUCT CONNECTION</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>PARALLEL BLADE DAMPER</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>OPPOSED BLADE DAMPER</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div></div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>AIRFLOW MEASURING STATION</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>FILTER BANK</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>COIL</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>AP ACCESS PANEL</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>EXISTING EQUIPMENT TO BE REMOVED</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>EXISTING EQUIPMENT TO REMAIN</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>NEW EQUIPMENT</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>FD FIRE DAMPER</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>RD RADIATION TYPE FIRE DAMPER</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>SD SMOKE DAMPER</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>FS FIRE & SMOKE DAMPER</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>T-TSTAT WALL MOUNTED THERMOSTAT</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>S WALL MOUNTED TEMP. SENSOR</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>SA SUPPLY AIR</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>RA RETURN AIR</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>EA EXHAUST AIR</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>OA OUTSIDE AIR</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>MA MIXED AIR</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>FA FRESH AIR</div></div></div>											
<div><div><div><div><div></div><div></div></div><div></div></div><div>RF RELIEF AIR</div></div></div>											

GENERAL NOTES:

G-1 MECHANICAL INFORMATION IS NOT LIMITED TO THE MECHANICAL DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE FOR INFORMATION ON ALL OTHER CONSTRUCTION DOCUMENTS INCLUDING DRAWINGS BY OTHER DISCIPLINES AND SPECIFICATIONS.

A - EACH DRAWING SHEET AND THE SPECIFICATIONS HAVE BEEN PREPARED TO SUPPLEMENT EACH OTHER AND THEY SHALL BE INTERPRETED AS AN INTEGRAL UNIT WITH ITEMS SHOWN AND NOTED ON ONE AND NOT THE OTHER BEING FURNISHED AND INSTALLED AS THOUGH SHOWN AND CALLED OUT IN ALL PLACES. ITEMS IN SPECIFICATIONS OR DRAWINGS LISTED WHICH ARE DIFFERING IN EFFICIENCY OR QUALITY SHALL BE HELD TO THE GREATEST OF: EFFICIENCY, QUALITY OR GOVERNING CODE.

**B - THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR THE
INSTALLATION OF THE SYSTEMS ACCORDING TO THE TRUE INTENT AND
MEANING OF THE CONTRACT DOCUMENTS.**

C - THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT WITH PROPER SERVICE ACCESS AND CLEARANCES ACCORDING TO MANUFACTURERS' RECOMMENDATIONS. THE CONTRACTOR SHALL REVIEW SUPPLIERS BIDDING PACKAGES FOR COMPLETENESS AND COMPLIANCE TO THE SPECIFICATIONS, SCHEDULES, AND DESIGN INTENT (ALL EQUIPMENT AND METHODS). THE CONTRACTOR SHALL REMOVE AND REINSTALL CORRECTLY AT HIS OWN EXPENSE ANY EQUIPMENT NOT IN COMPLIANCE.

D - THE CONTRACTOR SHALL CONSULT MANUFACTURERS
INSTALLATION INSTRUCTIONS FOR SIZES, METHODS, ACCESSORIES,
AND CLEARANCES IN SPACE AVAILABLE PRIOR TO BIDDING PROJECT.

E - ANYTHING NOT CLEAR OR IN CONFLICT WILL BE EXPLAINED BY MAKING APPLICATION TO THE ENGINEER IN WRITING.

G-2 ANY AND ALL ALTERATIONS TO THE SYSTEM SHOWN SHALL BE THE RESPONSIBILITY OF THIS CONTRACTOR. ARCHITECT SHALL BE NOTIFIED IN WRITING PRIOR TO CHANGES.

G-3 CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND LOCATIONS.

G-4 THE WORKING DRAWINGS ARE DIAGRAMMATIC. THEY DO NOT SHOW EVERY OFFSET, BEND, OR ELBOW NECESSARY FOR THE COMPLETE INSTALLATION IN THE SPACE PROVIDED. ALL LOCATIONS FOR MECHANICAL EQUIPMENT SHALL BE FIELD VERIFIED AND COORDINATED WITH ALL DRAWINGS. THE CONTRACTOR SHALL PROVIDE OR COORDINATE WITH THE GENERAL CONTRACTOR PROVISIONS FOR BLOCKOUTS OR CORE DRILLS THROUGH STRUCTURE

G-5 THE INSTRUCTION TO "PROVIDE" ALSO INCLUDES INSTALLATION.

G-6 MECHANICAL CONTRACTOR SHALL PROVIDE AND INSTALL SMOKE AND FIRE DAMPERS AS REQUIRED BY LOCAL CODES AND AUTHORITIES.

G-7 SHEET METAL DUCT SIZES SHOWN ON DRAWINGS ARE FREE AREA DIMENSIONS.

G-8 PROVIDE AND INSTALL BALANCING DAMPERS IN ALL SUPPLY AND EXHAUST AIR BRANCH DUCTS. BALANCE TO CFM SHOWN ON PLAN.

G-9 SEE ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT LOCATION OF DIFFUSERS AND GRILLES.

G-10 PROVIDE TURNING VANES IN ALL ELBOWS OF RECTANGULAR DUCT.

G-11 THE CONTRACTOR SHALL ASSUME ALL RESPONSIBILITY IN HANDLING AND DISPOSING OF REFRIGERANTS, OILS, ETC. ALL SUCH MATERIALS SHALL BE HANDLED, DISPOSED, AND USED IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL LAWS.

G-12 THE MECHANICAL CONTRACTOR SHALL VERIFY MOTOR VOLTAGES WITH THE ELECTRICAL DRAWING BEFORE ORDERING MOTORIZED EQUIPMENT AND CONTROLS.


G-13 C.F.M. LISTED IS ACTUAL AIR.

G-14 SUPPLIERS SHALL REVIEW ALL DRAWINGS AND THE SPECIFICATIONS PRIOR TO SUBMITTING PRICES TO THE CONTRACTOR. ALL QUESTIONS AND DISCREPANCIES SHALL BE BROUGHT TO THE ENGINEERS ATTENTION PRIOR TO BIDDING.

C-15 CONTRACTOR SHALL THOROUGHLY REVIEW AND SIGN SUBMITTALS FOR COMPLETENESS AND COMPLIANCE TO THE SPECIFICATIONS PRIOR TO ENGINEERS REVIEW. SUPPLIERS SHALL HIGHLIGHT OR MARK ALL INFORMATION REQUIRED TO SHOW COMPLIANCE TO THE SPECIFICATIONS. ALL REQUESTED EXCEPTIONS TO THE SPECIFICATIONS, OR SCHEDULES SHALL BE CLEARLY NOTED AND EXPLAINED. SUBMITTAL REVIEW AND ACCEPTANCE IS FOR DESIGN CONCEPT ONLY, AND DOES NOT AT ANY TIME RELIEVE THE CONTRACTOR OF RESPONSIBILITY TO MEET SPECIFICATIONS, CAPACITIES, OR DESIGN INTENT.

G-16 ALL MECHANICAL SHALL BE INSTALLED AND CONFORM TO THE 2006 EDITION OF THE IMC WITH UTAH ANNOTATIONS AND LOCAL AUTHORITY REQUIREMENTS.

G-17 THIS CONTRACTOR SHALL BE RESPONSIBLE FOR THE DRAINING DOWN AND RE-FILLING OF ALL SYSTEMS NECESSARY TO COMPLETE THE WORK OUTLINED BY THIS PROJECT. THIS INCLUDES PROVIDING THE REQUIRED CHEMICAL TREATMENT WHEN RE-FILLING THE SYSTEM.

**HFS***Architects*

A RCHITECTURE
I NTERIORS
P LANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



**STUDENT SERVICES
REMODEL**

**DAVIS APPLIED TECHNOLOGY
COLLEGE**

[illegible]

DATE:	
AGENCY PROJECT NO:	x
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	
CONSTRUCTION DOCUMENTS	
SHEET TITLE	


MECHANICAL GENERAL NOTES AND LEGEND

M001
SHEET OF



MECHANICAL DEMOLITION FLOOR PLAN

SCALE: 1/8" = 1'-0"





SHEET NOTES:

- 1 EXISTING VAV BOX SHALL REMAIN.
- 2 EXISTING MEDIUM PRESSURE DUCT SHALL REMAIN.
- 3 EXISTING LOW PRESSURE DUCT SHALL REMAIN.
- 4 REMOVE EXISTING DIFFUSER OR GRILLE.
- 5 REMOVE EXISTING SECTION OF DUCTWORK AS SHOWN.
- 6 EXISTING THERMOSTAT SHALL BE RE-USED, AND RE-CALIBRATED.
- 7 EXISTING DUCT, DIFFUSERS ETC. THIS AREA SHALL REMAIN.
- 8 EXISTING HOT WATER SUPPLY AND RETURN PIPING SHALL REMAIN.
- 9 REMOVE EXISTING THERMOSTAT.

GENERAL NOTES:

- 1. FIELD VERIFY EXISTING CONDITIONS INCLUDING EXACT LOCATION OF MECHANICAL EQUIPMENT, PIPING, DUCTWORK, ETC.

KEY PLAN



HFSArchitects

ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1354 East 3300 South Suite 200
SALT LAKE CITY, UTAH 84106
(801) 466-4021, FAX 466-8538
EMAIL: excellence@whw-engineering.com

STUDENT SERVICES
REMODEL

DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	
AGENCY PROJECT NO:	x
HFS PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

MECHANICAL
DEMOLITION FLOOR
PLANS


MD101

SHEET OF



MECHANICAL FLOOR PLAN

SCALE: 1/8" = 1'-0"




SHEET NOTES:

- EXISTING VAV BOX SHALL REMAIN.
- EXISTING MEDIUM PRESSURE DUCT SHALL REMAIN.
- EXISTING LOW PRESSURE DUCT SHALL REMAIN.
- PROVIDE NEW CEILING DIFFUSER OR GRILLE. RE-CONNECT TO EXISTING BRANCH OR SOUND BOOT WHERE SHOWN. TRANSITION AS NECESSARY, FIELD VERIFY.
- PROVIDE NEW SUPPLY DUCT AND TIE INTO EXISTING AT THIS APPROXIMATE LOCATION. FIELD VERIFY SIZE AND LOCATION. TRANSITION AS NECESSARY TO CONNECT TO EXISTING.
- EXISTING THERMOSTAT SHALL BE RE-USED, AND RE-CALIBRATED.
- PROVIDE NEW RETURN GRILLE IN NEW LOCATION AS SHOWN.
- PROVIDE NEW VAV BOX. TIE INTO EXISTING MEDIUM PRESSURE DUCTWORK AND EXISTING HOT WATER PIPING. FIELD VERIFY EXACT SIZE AND LOCATION.
- PROVIDE NEW THERMOSTAT. COORDINATE EXACT LOCATION WITH ALL DISCIPLINES.

GENERAL NOTES:

- FIELD VERIFY EXISTING CONDITIONS INCLUDING EXACT LOCATION OF MECHANICAL EQUIPMENT, PIPING, DUCTWORK, ETC.
- PROVIDE NEW SOUND BOOT FOR ALL NEW RETURN GRILLES, IN NEW LOCATIONS. EXISTING SOUND BOOT MAY BE RE-USED WHEN GRILLE IS REPLACED IN THE SAME LOCATION.

KEY PLAN



HFSArchitects

ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1354 East 3300 South Suite 200
SALT LAKE CITY, UTAH 84106
(801) 466-4021, FAX 466-8538
EMAIL: excellence@whw-engineering.com

STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	
AGENCY PROJECT NO:	x
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

MECHANICAL
FLOOR PLAN

ME101

SHEET OF

DIMENSION OF LONGEST SIDE, INCHES	SHEET METAL GAGE (ALL FOUR SIDES)	TRANSVERSE REINFORCING (1)					
		MINIMUM REINFORCING ANGLE SIZE AND MAXIMUM LONGITUDINAL SPACING BETWEEN TRANSVERSE JOINTS &/OR INTERMEDIATE REINFORCING	MIN. H. IN.	AT JOINTS			
				DRIVE SLIP PLAIN S SLIP	HEMMED S SLIP	ALTER'NT BAR SLIP	REIN-FORCED BAR SLIP
UP THRU 12	26	NONE REQUIRED	1	26	26	24	24
13 - 18	24	NONE REQUIRED	1	24	24	24	24
19 - 30	24	1"x1"x1/8" @ 60 IN	1	-	24	24	24
31 - 36	22	1"x1"x1/8" @ 60 IN	1	-	-	22	22

1. TRANSVERSE REINFORCING SIZE IS DETERMINED BY DIMENSION OF SIDE TO WHICH ANGLE IS APPLIED.

D1 DUCT CONSTRUCTION DETAIL


SCALE: NONE

LOW PRESSURE ROUND DUCT CONSTRUCTION SCHEDULE				
DUCT DIAMETER IN INCHES	MAXIMUM 2" W.G. STATIC POSITIVE		MAXIMUM 2" W.G. STATIC NEGATIVE	
	SPIRAL SEAM GAUGE	LONGITUDINAL SEAM GAUGE	SPIRAL SEAM GAUGE	LONGITUDINAL SEAM GAUGE
3 thru 8	28	28	28	24
9 thru 14	28	26	26	24
15 thru 26	26	24	24	22
27 thru 36	24	22	22	20
37 thru 50	22	20	20	18

C1 LOW PRESSURE ROUND DUCT CONSTRUCTION DETAIL


SCALE: NONE

NOTE:
L=1/4 W (4" MINIMUM.)



A1 BRANCH DUCT TAKE-OFF & DAMPER DETAIL

SCALE: NONE




C3 RETURN AIR BOOT DETAIL

SCALE: NONE

NOTE: TAKE-OFFS SHOULD NOT BE INSTALLED CLOSER THAN TWO WIDTHS TO ELBOWS OR INTERSECTIONS

NOTE: AREA OF A x B SHALL BE EQUAL TO 1.5 x AREA BRANCH DUCT




DETAIL

SCALE: NONE


A2 SQUARE-TO-ROUND TAKE-OFF DETAIL

SCALE: NONE




D5 DUCT SUPPORTS

SCALE: NONE




B4 VAV BOX (W/ HEATING COIL) HOT WATER PIPING DETAIL

SCALE: NONE



A5 DUCT LINER DETAIL

SCALE: NONE



HFSArchitects

ARCHITECTURE

INTERIORS

PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1354 East 3300 South Suite 200
SALT LAKE CITY, UTAH 84106
(801) 466-4021, FAX 466-8538
EMAIL: excellence@whw-engineering.com

STUDENT SERVICES REMODEL

DAVIS APPLIED TECHNOLOGY COLLEGE

MARK	DATE	DESCRIPTION

DATE:	
AGENCY PROJECT NO:	x
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

MECHANICAL DETAILS

ME501

SHEET OF




D

C

B

A

REGISTER, LOUVER & GRILLE SCHEDULE							
SYMBOL	TYPE	SERVICE	MAX CFM	NOMINAL SIZE	THROAT SIZE	CEILING TYPE	SCHEDULE NOTES
<div>R-1</div>	CEILING	RETURN	375	12/12	12/12	LAY-IN	1,2,3
<div>R-2</div>	CEILING	RETURN	1200	22/22	22/22	LAY-IN	1,2,3
REGISTER, LOUVER AND DIFFUSER SCHEDULE NOTES:							
1. MAXIMUM NC = 25 @ MAXIMUM CFM NOTED.							
2. SHALL BE PRICE 535 OR EQUAL BY OTHER APPROVED MANUFACTURERS.							
3. FINISH SHALL BE OFF-WHITE BAKED ENAMEL.							

DIFFUSER SCHEDULE								
SYMBOL	TYPE	MAX CFM	FACE SIZE	NCK SIZE	CEILING TYPE	BLOW	PATTERN	SCHEDULE NOTES
<div><div>D-1</div>CFM</div>	CEILING	225	9X9	8"Ø	LAY-IN	4--WAY		1,2,3,4
<div><div>D-2</div>CFM</div>	CEILING	425	12X12	10"Ø	LAY-IN	4--WAY		1,2,3,4
<div><div>D-3</div>CFM</div>	CEILING	650	15X15	12"Ø	LAY-IN	4--WAY		1,2,3,4
1. PROVIDE LAY-IN CEILING AND BORDER / MODULE AS REQUIRED. SEE ARCHITECTURAL CEILING PLANS.								
2. MAXIMUM NC 25 AT CFM LISTED.								
3. TRANSITION AS REQUIRED TO DUCT WORK SHOWN ON PLAN.								
4. DIFFUSER SHALL BE PRICE MODEL SMD OR EQUAL IN SPECIFICATIONS.								

VAV BOX SCHEDULE														
SYMBOL	SERVES	INLET DIA. (INCHES)	COOLING		HEATING						NC LEVEL	MANUF. MODEL #	SCHEDULE NOTES	
			MAX CFM	MIN CFM	COIL EAT	COIL LAT	MAX CFM	FLOW GPM	EWT	(FT) PD				ROWS
<div><div>VAV</div>101</div>	108, 109, 110	8"	440	135	65	100	440	2	180	0.75	2	25	PRICE SDV	1
1. SEE SPECIFICATIONS FOR APPROVED MANUFACTURERS.														



HFS*Architects*

ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1354 East 3300 South Suite 200
SALT LAKE CITY, UTAH 84106
EMAIL: excellence@whw-engineering.com



STUDENT SERVICES
REMODEL

DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:

AGENCY PROJECT NO: x

HFSA PROJECT NO: 0615.02

CAD DWG FILE NO:

DRAWN BY: STAFF

CHECKED BY: SLW

DESIGNED BY: WP

DWG TYPE: MECHANICAL AND PLUMBING


ARCHITECTURAL PHASE:
CONSTRUCTION DOCUMENTS

SHEET TITLE


MECHANICAL
SCHEDULES AND
DETAILS

ME601


SHEET OF




TYPICAL RECESSED FIXTURE MOUNTING DETAIL




TYPICAL FIRESTOP FOR CABLES/CONDUIT THROUGH CONCRETE FLOORING



FIRESTOP FOR METAL CONDUIT THROUGH GYPSUM WALL BOARD



TYPICAL FIRESTOP FOR CABLES/CONDUIT THROUGH CONCRETE WALLS



TYPICAL DISCONNECT CLEARANCE REQUIREMENTS

LIGHTING FIXTURE SCHEDULE				
SYMBOL	DESCRIPTION	LAMPS	APPROVED MANUFACTURERS	CATALOG NUMBER
T-1	LINEAR PENDANT MOUNTED FLUORESCENT LIGHT FIXTURE TO MATCH EXISTING. FIELD VERIFY PRIOR TO ORDERING FOR EXACT CATALOG NUMBER.	3F32 PER 4'	MATCH EXISTING	BUILDING STANDARD
T-2	2'X4\"/>	2F32	COLOMBIA	STB-24-232-G-FSA125-EBB-UNV
T-3	SAME AS T-2 EXCEPT 2'X2\"/>	2F32 ULAMP	X	
			COLOMBIA	X
T-4	10\"/>	100MH	WINONA	P2-LS-M100-277-LK1-SCBA-PG
EX-1	GREEN LED EXIT SIGN TO MATCH BUILDING STANDARD	X	MATCH EXISTING	X

NOTES:
1. ALL FLUORESCENT LIGHTS SHALL HAVE ELECTRONIC PROGRAMMABLE START BALLASTS, 10% TOTAL HARMONIC DISTORTION, UNIVERSAL, ADVANCE AND HOWARD ARE APPROVED MANUFACTURERS. BALLASTS TO HAVE 5 YEAR WARRANTY.
2. ALL FLUORESCENT LAMPS SHALL HAVE 4100° COLOR TEMPERATURE.
3. FIELD VERIFY ALL LIGHTING VOLTAGES PRIOR TO PLACING ANY ORDER.
4. THE WRITTEN CRITERIA OF THE FIXTURE DESCRIPTION TAKES PRECEDENCE OVER THE CATALOG NUMBER.

ELECTRICAL SYMBOL LIST	
SYMBOL	DESCRIPTION
LIGHTING SYMBOLS	
	RECESSED FLUORESCENT FIXTURE
	SURFACE MOUNTED FLUORESCENT FIXTURE
	INDUSTRIAL STRIP LIGHT
	RECESSED FIXTURE
	FIXTURES ON EMERGENCY POWER
	EXIT LIGHT. ARROWS SHOW EXIT DIRECTION
	LIGHTING FIXTURE CALLOUT; NUMBER INDICATES A SUGGESTED QUANTITY - TO BE VERIFIED
	REFERENCE NOTE CALLOUT
	SINGLE POLE TOGGLE SWITCH - 20 AMP
	SINGLE POLE TOGGLE SWITCH - 20 AMP LETTERS INDICATE SWITCH ASSIGNMENT
	THREE WAY TOGGLE SWITCH - 20 AMP
POWER SYMBOLS	
	DUPLEX CONVENIENCE OUTLET - 20 AMP
	FOUR-PLEX CONVENIENCE OUTLET - 20 AMP
	DUPLEX CONVENIENCE OUTLET - 20 AMP GFI, DO NOT PROTECT DOWNSTREAM GFI OUTLETS.
	ARROWS INDICATE HOME RUNS - NUMBER OF CONDUCTORS AS REQUIRED
	FLUSH TELEPHONE/DATA OUTLET
	FLUSH TELEPHONE OUTLET
	FLUSH DATA OUTLET
	FLUSHED FLOOR BOX
	ELECTRICAL PANEL LOCATION
	DUEL TECHNOLOGY WALL MOUNTED OCCUPANCY SENSOR TO CONTROL LIGHTS IN THE ROOM.
	DUEL TECHNOLOGY CEILING MOUNTED OCCUPANCY SENSOR TO CONTROL LIGHTS IN THE ROOM.
	CARD READER
	DOOR STRIKE
GENERAL NOTE SYMBOLS	
WP	INDICATES WEATHER PROOF EQUIPMENT
A	INDICATES DEVICE IS ABOVE COUNTER TOP-42\"/>
WG	INDICATES DEVICES WITH LOW PROFILE WIREGUARD. SUBMIT APPROVAL

- GENERAL NOTES:**
1. IN THE EXISTING SPACES TO BE RENOVATED, THE CONTRACTOR SHALL REMOVE ALL LIGHT FIXTURES, SWITCHES, WIRING, CONDUIT, WIRING DEVICES, FIRE ALARM DEVICES, SPEAKERS, VOLUME CONTROLS, ETC. AS REQUIRED WHETHER OR NOT SHOWN ON THE DRAWINGS.
 2. ALL MATERIALS TO BE REMOVED FROM THE PREMISES SHALL BE RETURNED TO THE OWNER. MATERIALS WHICH THE OWNER DECIDES NOT TO KEEP SHALL BE SALVAGED AND REMOVED FROM THE SITE BY THE CONTRACTOR.
 3. ALL CONCEALED CONDUIT THAT CANNOT BE REMOVED SHALL BE CUT FLUSH WITH THE FINISH SURFACES AND CAPPED OFF AFTER THE WIRING HAS BEEN DISCONNECTED AT THE PANEL AND REMOVED FROM THE CONDUIT.
 4. IN AREAS WHERE CIRCUIT CONTINUITY IS INTERRUPTED, BUT MUST BE MAINTAINED BECAUSE OF THE NATURE OF THE FACILITY, MAKE ALL THE NECESSARY MODIFICATIONS TO THE CIRCUITS IN ORDER TO MAINTAIN THE CIRCUIT INTEGRITY.
 5. THE COLOR OF ALL THE NEW DEVICES AND COVERPLATES SHALL BE COORDINATED WITH ARCHITECT.
 6. REFER TO THE ARCHITECTURAL REFLECTED CEILING PLANS FOR THE EXACT LOCATION OF ALL LIGHTING FIXTURES.
 7. THE COLOR OF THE LIGHT FIXTURES SHALL BE SELECTED BY THE ARCHITECT.
 8. MINIMUM SIZE OF CONDUIT TO BE 3/4\"/>
 9. USE RIGID STEEL SET SCREW TYPE FITTINGS ONLY. DIE CAST FITTINGS SHALL NOT BE USED.
 10. SUPPORT THE LAY-IN TYPE FIXTURES FROM THE CEILING DECK INDEPENDENT OF THE CEILING GRID, AS SHOWN ON THE TYPICAL RECESSED FIXTURE MOUNTING DETAIL.
 11. ALL NEW WORK MUST MEET THE CURRENT ADOPTED NATIONAL ELECTRICAL CODE.
 12. NOT MORE THAN THREE (3) CIRCUITS, SHALL BE INSTALLED IN A 3/4\"/>
 13. THE SIZE OF THE NEUTRAL CONDUCTORS SHALL BE NO. 10 AWG FOR ALL HOME RUNS WITH COMMON NEUTRAL (LIGHTING AND POWER CIRCUITS).
 14. THE MINIMUM SIZE OF THE CONDUCTORS ARE TO BE #12 AWG THIN COPPER, UNLESS INDICATED OTHERWISE ON THE DRAWINGS.
 15. ALL J-BOXES SHALL HAVE MINIMUM DEPTH OF 2-1/8\"/>
 16. ALL METALLIC CONDUITS, JOINTS, FITTINGS, ETC., IN CONTACT WITH THE GROUND SHALL BE SPIRALLY WRAPPED WITH 3M SCOTCHRAPE-51, 20 MIL TAPE OR APPROVED EQUAL). 1/2\"/>
 17. ALL CONDUITS EXPOSED TO THE WEATHER AND IN THE MECHANICAL ROOM SHALL BE GALVANIZED RIGID STEEL, UNLESS OTHERWISE NOTED.
 18. ALL NEW EXPOSED CONDUIT MUST RUN AGAINST THE WALLS OR CEILINGS. DO NOT PENDANT MOUNT ANY CONDUIT FROM THE CEILINGS
 19. ALL THE HOMERUNS MUST BE ACCESSIBLE. DO NOT CARRY A HOMERUN FROM ONE DEVICE TO ANOTHER WHICH IS TIED TO A SEPARATE HOMERUN INSIDE THE WALL. MARK ON ALL THE J-BOXES THE CIRCUIT NAMES AND NUMBERS. USE NO. 10 THIN CONDUCTORS FOR HOMERUNS OVER 100 FEET, NO. 8 THIN OVER 200 FEET, NO. 6 THIN OVER 300 FEET AND NO. 4 THIN OVER 400 FEET LENGTH
 20. COORDINATE WITH THE OWNER AND ARCHITECT FOR THE EXACT LOCATION OF THE OUTLETS.
 21. LIGHT SWITCHES INSTALLED ADJACENT TO EACH OTHER, SHALL BE GANGED TOGETHER WITH ONE PIECE COVERPLATE.
 22. USE EPOXY ANCHORS TO SUPPORT THE ELECTRICAL EQUIPMENT. EXPANSION ANCHOR BOLTS ARE NOT ACCEPTED.
 23. AT THE END OF THE JOB, PROVIDE BLANK COVER PLATES TO MATCH THE OTHER COVER PLATES FOR ALL J-BOXES WHERE DEVICES HAVE NOT YET BEEN INSTALLED.
 24. SEAL AROUND ALL CONDUIT PENETRATIONS THROUGH WALLS AND CEILINGS WITH FIRE RATED MATERIAL. 3M IS AN APPROVED MANUFACTURER.
 25. ALL MATERIALS USED IN THIS INSTALLATION SHALL BE U.L. APPROVED AND NEW.
 26. ALL ELECTRICAL WIRING MUST BE IN CONDUIT (ROMEX NOT PERMITTED).
 27. NO CONDUITS SHALL RUN IN DUCT WORK.
 28. PRIOR TO SUBMITTING A BID THE ELECTRICAL CONTRACTOR SHALL INSPECT THE SITE AND INCLUDE IN HIS BID PACKAGE ALL CHARGES DUE TO EXISTING CONDITIONS. SHOP DRAWINGS ARE REQUIRED. ALL LABOR, MATERIAL AND WORKMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF 1 YEAR FROM THE DATE OF ACCEPTANCE BY THE TENANT. REPLACE OR REPAIR ALL DEFECTS DURING THE GUARANTEED PERIOD.
 29. THE ELECTRICAL CONTRACTOR SHALL TERMINATE THE ELECTRICAL CONNECTIONS TO ALL THE EQUIPMENT BY PROVIDING THE NECESSARY MALE/FEMALE CONNECTOR, RECEPTACLE, PLUG, ETC.
 30. ALL DUPLEX OUTLETS AND SWITCHES SHALL BE 20 AMP., 120 VOLT SPEC GRADE, HUBBELL AND PASS & SEYMOUR AND LEVITON ARE APPROVED MANUFACTURERS
 31. ELECTRICAL CONTRACTOR SHALL VERIFY ALL ELECTRICAL LOADS (VOLTAGE, PHASE, CONNECTION REQUIREMENT, ETC.) OF EQUIPMENT FURNISHED UNDER OTHER DIVISIONS WITH APPROVED SHOP DRAWINGS. REFER TO BEGINNING ROUGH-IN.
 32. THE CONTRACTOR SHALL INFORM THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES FOUND BETWEEN THE INTENDED FUNCTION OF EQUIPMENT AND EQUIPMENT SPECIFIED IN THE CONTRACT DOCUMENTS A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO ISSUANCE OF THE FINAL ADDENDUM. FAILURE TO REPORT ANY DISCREPANCY (CATALOG NUMBERS, DISCONTINUED ITEMS, ETC.) DOES NOT RELIEVE THE CONTRACTOR FROM PROVIDING EQUIPMENT WHICH SHALL CONFORM TO AND FULFILL THE INTENT OF THE CONTRACT DOCUMENTS. NOR SHALL IT BE USED AS A CONDITION TO OBTAIN ADDITIONAL FUNDS FROM THE OWNER AFTER THE CONTRACT IS AWARDED. THE CONTRACTOR SHALL REQUEST ALL CLARIFICATIONS OF CONTRACT DOCUMENT REQUIREMENTS IN WRITING TO THE ARCHITECT/ENGINEER A MINIMUM OF FIVE WORKING DAYS PRIOR TO ISSUANCE OF THE FINAL ADDENDUM.




HFS Architects

ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE


MARK	DATE	DESCRIPTION

DATE:	JUN 01, 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE	SYMB LIST, GENERAL NOTES, AND FIXTURE SCHEDULE
-------------	---

E0.01

SHEET OF



PARTIAL FIRST FLOOR DEMOLITION PLAN - ELECTRICAL
1/8" = 1'-0"

REFERENCE NOTES:

- ◇ EXISTING DEVICES TO REMAIN. PROTECT DEVICES AND KEEP CIRCUIT INTEGRITY.
- ◇ THE EXISTING PUSH BUTTONS FOR THE EMERGENCY PAGING SYSTEM WILL BE RELOCATED BY THE OWNER. THE ELECTRICAL CONTRACTOR IS TO COORDINATE WITH THE OWNER AND PROVIDE J-BOXES AND CONDUITS.



DEMOLITION NOTES:

- IN THE EXISTING SPACE TO BE RENOVATED, THE CONTRACTOR SHALL REMOVE ALL LIGHT FIXTURES, SWITCHES, WIRING, WIRING DEVICES, CONDUITS, FIRE ALARM DEVICES, SPEAKERS, VOLUME CONTROLS, ETC. AS REQUIRED WHETHER OR NOT SHOWN ON THE DRAWINGS.
- ALL MATERIALS THAT ARE TO BE REMOVED FROM THE PREMISES SHALL BE RETURNED TO THE OWNER. MATERIALS WHICH THE OWNER DECIDES NOT TO KEEP SHALL BE SALVAGED AND REMOVED FROM THE SITE BY THE CONTRACTOR.
- ALL CONCEALED CONDUITS THAT CANNOT BE REMOVED SHALL BE CUT FLUSH WITH THE FINISHED SURFACES AND CAPPED OFF AFTER THE WIRING HAS BEEN DISCONNECTED AT THE PANEL AND REMOVED FROM THE CONDUIT.
- IN AREAS WHERE CIRCUIT CONTINUITY IS INTERRUPTED, BUT MUST BE MAINTAINED BECAUSE OF THE NATURE OF THE FACILITY, MAKE ALL THE NECESSARY MODIFICATIONS TO THE CIRCUITS IN ORDER TO MAINTAIN THE CIRCUITS INTEGRITY.

HFSArchitects
ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT




STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	JUN 01, 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE	PARTIAL FIRST FLOOR DEMOLITON PLAN - ELECTRICAL
-------------	---

E1.11



PARTIAL FIRST FLOOR PLAN- POWER
1/8"=1'-0"


REFERENCE NOTES: POWER

- 1 FURNISH AND INSTALL A 4"x4"x2-1/8" J-BOX IN THE APPROXIMATE LOCATION SHOWN FOR VOICE/DATA. RUN A 3/4" CONDUIT WITH A PULL-STRING FROM THE J-BOX TO THE NEAREST ACCESSIBLE CEILING SPACE ON THIS FLOOR. COORDINATE WITH THE OWNER/ARCHITECT FOR EXACT LOCATION PRIOR TO ROUGH-IN.
- 2 PROVIDE SURFACE MOUNTED WINMOLD WITH DUPLEX OUTLETS AND J-BOXES FOR VOICE DATA OUTLETS IN THE APPROXIMATE LOCATIONS SHOWN. TIE THE DUPLEX OUTLETS TO THE INDICATED CIRCUITS. RUN CONDUIT WITH PULL STRING (SIZE AND NUMBER OF CONDUIT AS SHOWN) FROM THE WINMOLD TO THE NEAREST ACCESSIBLE CEILING SPACE ON THIS FLOOR FOR VOICE/DATA CABLING. COORDINATE WITH THE ARCHITECT/ OWNER FOR PATH OF CONDUIT. THE WINMOLD SHALL BE 4" WIDE PLASTIC WITH A DIVIDER IN BETWEEN POWER AND LOW VOLTAGE CABLING. WALKER AND HUBBLE ARE THE APPROVED MANUFACTURERS WIRE MOLD IS TO BE EQUAL TO: WALKER 5400TB BASE- 5400C COVER- 5400 SERIES RACEWAY WITH ALL FITTINGS NECESSARY FOR A COMPLETE INSTALLATION.
- 3 REPLACE THE EXISTING PLASTIC COVER PLATE FOR THE FLOOR BOXES AND FLOOR J-BOXES IN THE AREA WITH NEW BRASS COVER. MAKE ANY MODIFICATIONS NECESSARY TO INSTALL THE NEW COVER PLATE. FIELD VERIFY FOR THE NUMBER OF FLOOR BOXES.
- 4 RUN CONDUITS THROUGH MILLWORK FOR ALL DEVICES INDICATED IN THE MILLWORK. COORDINATE THIS WORK WITH THE GENERAL CONTRACTOR. SEE ALSO, ARCHITECTURAL CABINET ELEVATIONS FOR MORE DETAILS.
- 5 PROVIDE 1" CONDUIT FROM THE CEILING TO COMPUTER KIOSK. ALSO TIE THE KIOSK TO THE INDICATED CIRCUIT. COORDINATE WITH THE ARCHITECT FOR EXACT LOCATION OF THE KIOSK.
- 6 TIE EACH HOMERUN TO A DEDICATED 120 VOLT, 20 AMP CIRCUIT ON THE SAME FLOOR. PROVIDE CONDUITS, CONDUCTORS, ETC. FOR A COMPLETE INSTALLATION. PROVIDE ADDITIONAL BREAKERS AS REQUIRED. FIELD VERIFY FOR AVAILABLE PANEL SPACE.
- 7 DO NOT RUN SURFACE MOUNTED CONDUIT IF POSSIBLE. COORDINATE WITH THE ARCHITECT/ ENGINEER PRIOR TO RUNNING ANY SURFACE MOUNTED CONDUIT.
- 8 FURNISH AND INSTALL NEW FIRE ALARM DEVICE IN THE APPROXIMATE LOCATION SHOWN. TIE THE NEW DEVICE TO THE EXISTING FIRE ALARM CONTROL PANEL. THE NEW DEVICE SHALL BE THE SAME AS AND COMPATIBLE WITH THE EXISTING SYSTEM. TEST AND CERTIFY THE SYSTEM TO MEET THE LOCAL AHI.
- 9 FURNISH AND INSTALL ALL NEW CEILING MOUNTED RECESSED SPEAKERS IN THE APPROXIMATE LOCATIONS SHOWN. THE NEW SPEAKER SHALL BE THE SAME AS THE EXISTING ONES. TIE THE SPEAKERS TO THE EXISTING SOUND SYSTEM. FIELD VERIFY. PROVIDE CONDUIT, CONDUCTORS, ETC. FOR A COMPLETE INSTALLATION.



HFS Architects
ARCHITECTURE
INTERIORS
PLANNING
1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	JUN 01, 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE PARTIAL FIRST FLOOR PLAN-POWER

E2.11



PARTIAL FIRST FLOOR PLAN- LIGHTING
1/8"=1'-0"

REFERENCE NOTES: LIGHTING

- 1. TIE ALL FIXTURES INDICATED WITH A LOWER CASE LETTER 'E' TO ITS CORRESPONDING SWITCH(ES). PROVIDE CONDUITS, CONDUCTORS, ETC. FOR A COMPLETE INSTALLATION.
- 2. EMERGENCY LIGHT FIXTURES INDICATED WITH THE LETTER 'E' SHALL BE PROVIDED WITH A SEPARATE BALLAST FOR THE CENTER LAMP. ONE LAMP WITH 1100 LUMENS IN THE LIGHT FIXTURE SHALL BE TIED TO THE EMERGENCY SYSTEM AND TURN ON WHEN THE COMMERCIAL POWER FAILS REGARDLESS OF THE POSITION OF THE CONTROL SWITCH. PROVIDE CONDUITS, CONDUCTORS, RELAY, ETC. FOR A COMPLETE INSTALLATION.
- 3. TIE EXIT SIGNS TO AN UNSWITCHED EMERGENCY LIGHTING CIRCUIT. PROVIDE CONDUITS, CONDUCTORS, RELAY BALLASTS, ETC. FOR A COMPLETE INSTALLATION.
- 4. LIGHT FIXTURES INDICATED WITH THE LETTERS 'NL' (NIGHT LIGHT) SHALL BE PROVIDED WITH A SEPARATE BALLAST FOR ONE OF THE LAMPS. THAT LAMP SHALL STAY ON AT ALL TIMES. PROVIDE CONDUITS, CONDUCTORS, ETC. FOR A COMPLETE INSTALLATION.
- 5. FURNISH AND INSTALL A CEILING/ WALL MOUNTED MOTION SENSOR TO CONTROL THE LIGHT FIXTURES IN THE ROOM. SET THE TIME DELAY FOR 30 MINUTES. WATT STOPPER & SENSOR SWITCH ARE THE APPROVED MANUFACTURES.
- 6. TIE EACH HOMERUN SHOWN TO THE NEAREST 277 VOLT, 20 AMP DEDICATED CIRCUIT. FIELD VERIFY. PROVIDE CONDUIT, CONDUCTORS, BREAKER, ETC FOR A COMPLETE INSTALLATION.
- 7. TIE THE EMERGENCY LIGHT FIXTURES TO THE NEAREST EMERGENCY LIGHTING CIRCUIT WITH AVAILABLE AMPACITY. RUN THE EMERGENCY LIGHTING CIRCUIT IN A SEPARATE RACEWAY. PROVIDE CONDUIT, CONDUCTORS, J-BOX, ETC FOR A COMPLETE INSTALLATION.

HFSArchitects

ARCHITECTURE
INTERIORS
PLANNING

1484 South State Street
Salt Lake City, Utah 84115
801-596-0691/F: 596-0693
www.hfsa.com

CONSULTANT



STUDENT SERVICES
REMODEL
DAVIS APPLIED TECHNOLOGY
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	May 25, 2007
AGENCY PROJECT NO:	
HFSA PROJECT NO:	0615.02
CAD DWG FILE NO:	
DRAWN BY:	
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	

SHEET TITLE PARTIAL FLOOR PLAN- LIGHTING

E9.11