



# Culinary Remodel

## Davis Applied Technology College


[illegible]



GENERAL NOTES

- A. ALL DIMENSIONS TAKEN FROM FINISHED FACE AND/OR CENTER LINE OF NEW AND EXISTING WALLS.
- B. IF A CONFLICT OCCURS BETWEEN DRAWINGS, DRAWINGS AND SPECIFICATIONS, SPECIFICATION SECTIONS AND DIVISIONS OR BETWEEN OTHER PARTS OF THESE CONSTRUCTION DOCUMENTS OR THESE DOCUMENTS AND ANY CODE REQUIREMENT, THE CONTRACTOR MAY REQUEST CLARIFICATION DURING THE BIDDING PERIOD. OTHERWISE THE MOST STRINGENT REQUIREMENTS SHALL APPLY AND BE PART OF THE CONTRACT AT NO ADDITIONAL COST TO THE OWNER.
- C. ALL WORK AND MATERIALS SHALL BE IN FULL CONFORMANCE WITH THE LATEST FEDERAL, STATE AND LOCAL CODES LAWS AND ORDINANCES. INCLUDING THEIR MOST RECENT REVISIONS, AMENDMENTS AND INTERPRETATIONS.
- D. THE GENERAL CONTRACTOR SHALL BRING TO THE ATTENTION OF THE ARCHITECT, FOR IMMEDIATE RESOLUTION, ANY NON-CONFORMING CONDITIONS WHICH MAY BE FOUND IN EXISTING FIELD CONDITIONS.
- E. PATCH AND REPAIR ANY DAMAGE TO ANY SURFACE, EQUIPMENT ETC NOT IN THIS SCOPE OF WORK.

ROOF PLAN LEGEND



**HFS Architects**  
ARCHITECTURE  
INTERIORS  
PLANNING  
1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

C

B

A

CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY  
COLLEGE


MARK	DATE	DESCRIPTION

DATE:	DECEMBER 21 , 2006
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

ROOF &  
SITE PLAN

**AS101**

SHEET 2 OF



GENERAL DEMOLITION NOTES

A. CONTRACTOR SHALL PERFORM ALL DEMOLITION AND PREPERATION WORK AS SHOWN ON DRAWINGS AND AS REQUIRED FOR A COMPLETE AND PROPER JOB. CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID TO VERIFY EXTENT OF REQUIRED DEMOLITION AND PREPERATION WORK. THE CONTRACTOR SHALL REMOVE FROM THE SITE AND DISPOSE OF ALL DEMOLITION ITEMS IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL LAWS.

B. ALL ITEMS NOT INDICATED FOR REMOVAL SHALL REMAIN AND SHALL BE PROTECTED. ANY ITEMS DAMAGED SHALL BE REPAIRED TO MATCH THE ADJACENT SURFACE.


DEMOLITION KEYED NOTES

- 1 REMOVE MASONRY WALL COMPLETE.
- 2 REMOVE DOOR AND FRAME AND RELOCATE TO DOOR #102C.
- 3 REMOVE EXTERIOR WINDOW SYSTEM, SALVAGE AND REINSTALL, SEE SHEET AE101 FOR LOCATION.
- 4 RELOCATE THERMOSTAT AND DEDICATION PLAQUE. SEE SHEET AE101 FOR NEW LOCATION OF PLAQUE.
- 5 REMOVE 3'-0" AND 5'-0" HIGH CONCRETE EXTERIOR WALL COMPLETE.
- 6 REMOVE MASONRY WALL AND GLASS BLOCK COMPLETE.
- 7 REMOVE DOOR AND FRAME AND RELOCATE TO DOOR #102D.
- 8 REMOVE OPERABLE PARTITION WALL COMPLETE.
- 9 REMOVE OPERABLE PARTITION CEILING TRACK COMPLETE.



DEMOLITION LEGEND

- REMOVE CARPET AND BASE.
- REMOVE LANDSCAPING, CONCRETE SIDEWALK AND CURB, RESURFACE FOR NEW CONCRETE FOOTINGS AND SLAB, SEE STRUCTURAL.
- REMOVE CONCRETE FLOOR, 5-1/2" MIN. WIDE X 1-1/2" MIN. DEEP FOR PREPARATION OF SLIDING WALL FRONT DOOR SILL TRACK AND STACK AREA. SEE DETAIL C2/AE601.

KEY PLAN



A3 DEMOLITION PLAN  
1/8" = 1'-0"



**HFS**Architects  
ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY  
COLLEGE


MARK	DATE	DESCRIPTION

DATE:	DECEMBER 21 , 2006
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

DEMOLITION  
PLAN

AD101





GENERAL DEMOLITION NOTES

A. CONTRACTOR SHALL PERFORM ALL DEMOLITION AND PREPERATION WORK AS SHOWN ON DRAWINGS AND AS REQUIRED FOR A COMPLETE AND PROPER JOB. CONTRACTOR SHALL VISIT THE SITE PRIOR TO BID TO VERIFY EXTENT OF REQUIRED DEMOLITION AND PREPERATION WORK. THE CONTRACTOR SHALL REMOVE FROM THE SITE AND DISPOSE OF ALL DEMOLITION ITEMS IN ACCORDANCE WITH ALL APPLICABLE STATE AND FEDERAL LAWS.


B. ALL ITEMS NOT INDICATED FOR REMOVAL SHALL REMAIN AND SHALL BE PROTECTED. ANY ITEMS DAMAGED SHALL BE REPAIRED TO MATCH THE ADJACENT SURFACE.

- DEMOLITION KEYED NOTES
- 1 REMOVE MASONRY WALL COMPLETE.
  - 2 REMOVE DOOR AND FRAME AND RELOCATE TO DOOR #102C.
  - 3 REMOVE EXTERIOR WINDOW SYSTEM, SALVAGE AND REINSTALL, SEE SHEET AE101 FOR LOCATION.
  - 4 RELOCATE THERMOSTAT AND DEDICATION PLAQUE. SEE SHEET AE101 FOR NEW LOCATION OF PLAQUE.
  - 5 REMOVE 3'-0" AND 5'-0" HIGH CONCRETE EXTERIOR WALL COMPLETE.
  - 6 REMOVE MASONRY WALL AND GLASS BLOCK COMPLETE.
  - 7 REMOVE DOOR AND FRAME AND RELOCATE TO DOOR #102D.
  - 8 REMOVE OPERABLE PARTITION WALL COMPLETE.
  - 9 REMOVE OPERABLE PARTITION CEILING TRACK COMPLETE.

CEILING DEMOLITION LEGEND

- REMOVE EXISTING SUSPENDED CEILING GRID AND 2x4" ACOUSTICAL LAY-IN PANELS.
- REMOVE EXISTING LAY-IN CEILING PANELS, GRID TO REMAIN.
- REMOVE AND RELOCATE LIGHT FIXTURE, SEE ELECTRICAL.

KEY PLAN



**HFS**Architects  
ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY COLLEGE

MARK	DATE	DESCRIPTION

DATE: DECEMBER 21 , 2006

AGENCY PROJECT NO: 06134220

HFSA PROJECT NO: 0615.01

CAD DWG FILE NO:

DRAWN BY: SAM

CHECKED BY:

DESIGNED BY: BS

DWG TYPE:

ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS


SHEET TITLE

REFLECTED CEILING  
DEMOLITIONI PLAN

AD111

SHEET 4 OF





**GENERAL NOTES**

A. ALL DIMENSIONS TAKEN FROM FINISHED FACE AND/OR CENTER LINE OF NEW AND EXISTING WALLS.

B. IF A CONFLICT OCCURS BETWEEN DRAWINGS, DRAWINGS AND SPECIFICATIONS, SPECIFICATION SECTIONS AND DIVISIONS OR BETWEEN OTHER PARTS OF THESE CONSTRUCTION DOCUMENTS OR THESE DOCUMENTS AND ANY CODE REQUIREMENT, THE CONTRACTOR MAY REQUEST CLARIFICATION DURING THE BIDDING PERIOD. OTHERWISE THE MOST STRINGENT REQUIREMENTS SHALL APPLY AND BE PART OF THE CONTRACT AT NO ADDITIONAL COST TO THE OWNER.

C. ALL WORK AND MATERIALS SHALL BE IN FULL CONFORMANCE WITH THE LATEST FEDERAL, STATE AND LOCAL CODES LAWS AND ORDINANCES. INCLUDING THEIR MOST RECENT REVISIONS, AMENDMENTS AND INTERPRETATIONS.



D. THE GENERAL CONTRACTOR SHALL BRING TO THE ATTENTION OF THE ARCHITECT, FOR IMMEDIATE RESOLUTION, ANY NON-CONFORMING CONDITIONS WHICH MAY BE FOUND IN EXISTING FIELD CONDITIONS.

E. PATCH AND REPAIR ANY DAMAGE TO ANY SURFACE, EQUIPMENT ETC NOT IN THIS SCOPE OF WORK.

FINISH LEGEND		
FLOOR / BASE	ROOM NAME	WALL
	ITEM NUM F T W	
A. CARPET WITH RUBBER BASE.		1. PAINT NEW & EXISTING GYPSUM BOARD WALLS
B. 12 X 12 PORCELAIN PAYER TILE W / PORCELAIN PAYER TILE BASE.		

PARTITION LEGEND		
	EXISTING STUD WALL TO REMAIN, TYPICAL	
	NEW 3-5/8" METAL STUD WALL W/ 5/8" GYPSUM BOARD BOTH SIDES TO 6" ABOVE FINISH CEILING, BRACED TO STRUCTURE ABOVE AT 4'-0" O.C.	
	RELOCATED STOREFRONT WINDOW SYSTEM.	

CARPET LEGEND		
	PORCELAIN PAVERS	
	ACCENT BORDER CARPET TO MATCH EXISTING CARPET AND WIDTH	



**HFSArchitects**

ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

**CULINARY REMODEL**

DAVIS APPLIED TECHNOLOGY COLLEGE


MARK	DATE	DESCRIPTION

DATE:	DECEMBER 21 , 2006
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

**FLOOR PLAN**

**AE101**

SHEET 5 OF



CEILING PLAN LEGEND

NEW INDIRECT FLUORESCENT PENDANT LIGHT FIXTURE, SEE ELECTRICAL DRAWINGS

EXISTING INDIRECT FLUORESCENT PENDANT LIGHT FIXTURE, RETAIN AND PROTECT

EXISTING 2'x4' LIGHT FIXTURE, RETAIN AND PROTECT

NEW SUPPLY GRILLE, SEE MECHANICAL DRAWINGS

EXISTING SUPPLY GRILLE, RETAIN AND PROTECT

NEW RETURN AIR GRILLE, SEE MECHANICAL DRAWINGS

EXISTING RETURN AIR GRILLE, RETAIN AND PROTECT

A.

NEW FOIL BACKED 2 X 2 CEILING PANELS AND NEW GRID, MATCH EXISTING. SEE A4, A5, B5, C4, & C5 / AE502 FOR CEILING DETAILS.

B.

NEW FOIL BACKED 2 X 2 CEILING PANELS, MATCH EXISTING, EXISTING GRID TO REMAIN

E.

EXISTING CEILING GRID AND PANELS, RETAIN AND PROTECT.

KEY PLAN

HFSArchitects

ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY COLLEGE

MARK	DATE	DESCRIPTION

DATE: DECEMBER 21 , 2006

AGENCY PROJECT NO: 06134220

HFSA PROJECT NO: 0615.01

CAD DWG FILE NO:

DRAWN BY: SAM

CHECKED BY:

DESIGNED BY: BS

DWG TYPE:


ARCHITECTURAL PHASE: CONSTRUCTION DOCUMENTS

SHEET TITLE


REFLECTED CEILING PLAN

AE111


SHEET 6 OF




C1 WALL DETAILS  
3/4" = 1'-0"




A1 WALL SECTION  
1/2" = 1'-0"



C3 KITCHEN SECTION  
1/4" = 1'-0"



A3 KITCHEN SECTION  
1/4" = 1'-0"



**HFSArchitects**  
ARCHITECTURE  
INTERIORS  
PLANNING  
1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

CULINARY REMODEL  
DAVIS APPLIED TECHNOLOGY  
COLLEGE



MARK	DATE	DESCRIPTION

DATE:	DECEMBER 21, 2006
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	SAM
CHECKED BY:	
DESIGNED BY:	BS
DWG TYPE:	
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	


SECTIONS

**AE301**  
SHEET 7 OF






C1 WINDOW TYPES 1/4" = 1'-0" C3 HEAD DETAIL 1-1/2" = 1'-0" C4 PARTIAL ELEVATION 1/4" = 1'-0" C5 CEILING EDGE AT STOREFRONT 3" = 1'-0"




B1 FRAME TYPES 1/4" = 1'-0" B4 ADJ. SHELVING SECTION 1/2" = 1'-0" B5 ADJ. SHELVING ELEVATION 1/2" = 1'-0"



A1 DOOR TYPES 1/4" = 1'-0" A3 DOOR SCHEDULE

DOOR SCHEDULE													
DOOR NO.	ROOM NAME	DOOR						FRAME					
		DOOR SIZE			TYPE	MAT.	FINISH	TYPE	MAT.	FINISH	DETAILS		
		W	H	T							HEAD	JAMB	SILL
100	LIBRARY	3'-0" (PR)	7'-0"	--	D	HM	--	EXST.	EXST.	EXST.	EXST.	EXST.	--
102A	DINING	17'-7" F.V.	9'-5" F.V.	--	A	--	--	--	--	--	C1/AE601	D5/AE502, D2/AE601	C2/AE601
102B	DINING	9'-0" F.V.	9'-5" F.V.	--	A	--	--	--	--	--	C1/AE601	D5/AE502, D2/AE601	C2/AE601
102C	DINING	EXIST.	EXIST.	EXIST.	B	EXIST.	EXIST.	EXIST.	EXIST.	EXIST.	--	--	--
102D	DINING	EXIST.	EXIST.	EXIST.	B	EXIST.	EXIST.	EXIST.	EXIST.	EXIST.	--	--	--
102E	DINING	15'-11" F.V.	9'-8" F.V.	--	A	--	--	--	--	--	D1/AE601	D4/AE502	C2/AE601
102F	DINING	13'-11" F.V.	9'-8" F.V.	--	A	--	--	--	--	--	D1/AE601	D4/AE502	C2/AE601
103	OFFICE	3'-0"	7'-0"	13/4"	C	SCWD	STAIN	2	HM	PAINT	D2/AE501	D4/AE501	--
104A	TRAINING KITCHEN	3'-0"	7'-0"	13/4"	C	SCWD	STAIN	1	HM	PAINT	D2/AE501	D4/AE501	--
104B	TRAINING KITCHEN	3'-0"	7'-0"	13/4"	C	SCWD	STAIN	1	HM	PAINT	D2/AE501	D4/AE501	--
104C	TRAINING KITCHEN	3'-0"	7'-0"	13/4"	C	SCWD	STAIN	1	HM	PAINT	D2/AE501	D4/AE501	--

A3 DOOR SCHEDULE



**HFSArchitects**  
ARCHITECTURE  
INTERIORS  
PLANNING  
1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

CULINARY REMODEL  
DAVIS APPLIED TECHNOLOGY COLLEGE

MARK	DATE	DESCRIPTION

DATE: DECEMBER 21, 2006  
AGENCY PROJECT NO: 06134220  
HFSA PROJECT NO: 0615.01  
CAD DWG FILE NO:  
DRAWN BY: SAM  
CHECKED BY:  
DESIGNED BY: BS  
DWG TYPE:  
ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS

DETAILS  
& INTERIOR  
ELEVATIONS


**AE501**  
SHEET 8 OF

D


C

B


A




D4 SLIDING MALL FRONT JAMB  
3"= 1'-0"




D5 JAMB DETAIL @ 90 ° CORNER  
3"= 1'-0"




C4 SEISMIC CEILING  
3"= 1'-0"




C5 BRACING DETAIL  
3"= 1'-0"




B3 HEAD DETAIL AT STACK  
SCALE: 1" = 1'-0"




B4 HANGER WIRE DETAIL  
FULL SCALE




B5 CEILING ANCHOR SYSTEM  
SCALE: 3"= 1'-0"




A3 SLIDING PANEL @ WINDOW  
SCALE: 3"= 1'-0"



A4 BRACING DETAIL  
NTS



A5 BRACING DETAIL  
SCALE: 3"= 1'-0"



**HFSArchitects**  
ARCHITECTURE  
INTERIORS  
PLANNING  
1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT


CULINARY REMODEL  
DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION


DATE: DECEMBER 21, 2006  
AGENCY PROJECT NO: 06134220  
HFSA PROJECT NO: 0615.01  
CAD DWG FILE NO:  
DRAWN BY: SAM  
CHECKED BY:  
DESIGNED BY: BS  
DWG TYPE:  
ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS  
SHEET TITLE

DETAILS


AE502  
SHEET 8 OF




D1 SLIDING MALL FRONT HEAD  
3\"/>




D2 SLIDING MALL FRONT DETAIL  
3\"/>




C1 SLIDING MALL FRONT HEAD  
1\"/>




C2 SLIDING MALL FRONT SILL DETAIL  
3\"/>




B1 COLUMN DETAIL  
1 - 1/2\"/>




B2 SLIDING MALL FRONT HEAD TRACK  
3\"/>




A1 COLUMN DETAIL  
1 - 1/2\"/>




A2 WINDOW HEAD / (JAMB SIM)  
3\"/>



C3 BUILDING ELEVATION (SOUTH)  
1/4\"/>



A3 BUILDING ELEVATION (EAST)  
1/4\"/>



**HFSArchitects**  
ARCHITECTURE  
INTERIORS  
PLANNING  
1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

CULINARY REMODEL  
DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION


DATE: DECEMBER 21, 2006  
AGENCY PROJECT NO: 06134220  
HFSA PROJECT NO: 0615.01  
CAD DWG FILE NO:  
DRAWN BY: SAM  
CHECKED BY:  
DESIGNED BY: BS  
DWG TYPE:  
ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS  
SHEET TITLE

ELEVATIONS  
& DETAILS

**AE601**  
SHEET 9 OF



[illegible]




NEW & EXISTING ROOF FRAMING PLAN SCALE: 1/8" = 1'-0"

KEYNOTES:

- A. HSS 3 1/2" x 1 1/2" x 1/4" @ 2'-6" O.C., SEE DETAIL A2/SE501 FOR STACK END SPACING
- B. L4x3x5/16", SEE DETAIL A2/SE101

NOTES:

1. (3) ROWS BRIDGING @ 14K1 JOIST
2. (5) ROWS BRIDGING @ 20K JOIST




KEYNOTES:

1. STEEL ROOF JOIST (TYP.)
2. 4x3x5/16" ANGLE (LLV)
3. 2x2x1/4" ANGLE BRACE FROM ANGLE BEARING TO BOTTOM CHORD PANEL POINT (NOT REQD IF ANGLE BEARS AT TOP CHORD PANEL POINT)
4. L3x3x1/4 FROM 1'-0" TO 3'-0" SPAN
5. L6x4x5/16 FROM 3'-0" TO 10'-0" SPAN.

NOTE:

- A. USE THIS DETAIL AT OPENINGS 12" OR GREATER. OPENINGS LESS THAN 12" SHALL BE REINFORCED WITH 16 GAUGE PLATE, 10" LARGER THAN OPENING IN ALL DIRECTIONS & FASTENED TO DECK @ 8" o.c.
- B. IF ROOF TOP UNITS ARE NOT SHOWN ON THE FRAMING PLAN, CONTRACTOR IS TO COORDINATE WEIGHTS AND LOCATIONS WITH JOIST SUPPLIER.

FOLDING PARTITION SUPPORT NO SCALE




NEW & EXISTING FOOTING & FOUNDATION PLAN SCALE: 1/8" = 1'-0"

CONCRETE PIER SCHEDULE

MARK	WIDTH	LENGTH	VERTICAL REINF.	TIE SETS	NOTES
CP-1	14"	16"	(4) #6	#3 @ 3' O.C.	TYPE 'A'

1. VERTICAL BARS SHALL TERMINATE IN A STANDARD 90 DEGREE HOOK UNLESS APPROVED OTHERWISE BY THE STRUCTURAL ENGINEER.
2. VERTICAL REINFORCING SHALL SPLICE AT FLOOR LEVELS ONLY. TYP., U.N.O.
3. WHEN USED, THE MAXIMUM OFFSET FOR INCLINED BARS SHALL BE 3 INCHES. THE MAXIMUM SLOPE FOR INCLINED BARS SHALL BE 1:6.
4. PROVIDE DOWELS WITH STANDARD HOOKS TO THE STRUCTURE BELOW TO MATCH THE VERTICAL REINFORCING IN THE COLUMN ABOVE. TYP., U.N.O.
5. PROVIDE A MINIMUM OF TWO SETS OF TIES IN THE TOP FIVE INCHES OF EVERY COLUMN. TYP., U.N.O. PROVIDE TIE SETS AT ONE-HALF THE SPACING SHOWN IN THE SCHEDULE FOR A MINIMUM OF 1/6 THE CLEAR SPAN. THE MAXIMUM CROSS SECTIONAL DIMENSION OF THE COLUMN, OR 18 INCHES. TOP AND BOTTOM, TYP., U.N.O.
6. COLD JOINTS SHALL OCCUR AT FLOOR LEVELS ONLY. TYP., U.N.O.
7. PROVIDE CHAMFERS AT ALL CORNERS OF ALL COLUMNS. TYP., U.N.O.
8. PENETRATIONS THROUGH CONCRETE COLUMNS IS NOT ALLOWED. TYP., U.N.O.



ROOF DECKS

1. SEE GENERAL NOTES: "STEEL DECK" FOR ADDITIONAL INFORMATION.
2. CONNECTIONS: WELD DECK TO SUPPORTING FRAMING MEMBERS WITH EITHER AN E60 OR E70 ELECTRODE WITH PUDDLE WELDS HAVING A FUSION AREA NOT LESS THAN 3/4" EFFECTIVE DIAMETER AS FOLLOWS:
- A. @ EACH FLUTE & TWO AT PANEL LAPS (ONE EACH SIDE OF SEAM).
- B. 6" O.C. @ ALL SUPPORTS PARALLEL TO DECK CORRUGATIONS
- C. FASTEN SIDE LAPS BY 1.5" TOP SEAM WELDS AT 18" o.c. CRIMP SIDE SEAMS BEFORE WELDING SIDE LAPS OR USE VERCOS PUNCHLOK SYSTEM W/ CONNECTIONS @ 12" o.c. MAX. ENGAGE ALL LAYERS OF THE DECK MATERIAL. WELDS SHALL PENETRATE ALL LAYERS OF DECK AND HAVE PROPER FUSION TO THE SUPPORTING MEMBERS.
3. ROOF DECK: TYPE HSB-36 OR PLB-36, 20 GAUGE, GALVANIZED G60, 36" WIDE, 1.5" DEEP, HAVING MINIMUM I = 0.216 IN<sup>4</sup> AND S = 0.235 IN<sup>3</sup> AND S = 0.248 IN<sup>3</sup>. DECK MUST MATCH (E) STEEL DECK TO FIT.
4. ALL ROOF DECKING TO BE THREE SPANS MINIMUM.

FOOTING SCHEDULE

MARK	WIDTH	LENGTH	THICK	BOTTOM REINFORCING	TOP REINFORCING	NOTES
F-1	2'-0"	CONT.	12"	(3) #5 CONTINUOUS	NONE	
F-2	3'-6"	3'-6"	12"	(4) #5 x 3'-0" E.W.	NONE	


C.W. = CROSSWISE E.W. = EACH WAY L.W. = LENGTHWISE

1. ALL FOOTINGS ARE MARK F-1, U.N.O.
2. BEAR FOOTINGS ON PROPERLY PREPARED MATERIAL.
3. BEAR EXTERIOR FOOTINGS BELOW THE EFFECTS OF FROST.
4. CENTER FOOTINGS BELOW THE WALL AND/OR COLUMN ABOVE, TYPICAL UNO.
5. PROVIDE 24 BEVELED KEYWAYS IN CONTINUOUS WALL FOOTINGS. UNO
6. PROVIDE 3" CLEAR CONCRETE COVER AT BOTTOM REINF., UNO.
7. PROVIDE DOWELS WITH STANDARD HOOK FROM FOOTINGS TO ANY REINFORCED ELEMENT ABOVE. DOWEL SIZE TO MATCH VERTICAL REINFORCING IN ELEMENT ABOVE. UNO
8. ANY INCREASE IN THE SIZE OF FOOTINGS FOR CONSTRUCTION CONVENIENCE, MAY REQUIRE ADDITIONAL REINFORCING. COORDINATE WITH THE EOR
9. ALL FOOTINGS TO BEAR ON ENGINEERED FILL. SEE SOILS REPORT.

CONCRETE WALL SCHEDULE

MARK	THICKNESS	VERTICAL REINF.	HORIZONTAL REINF.	NOTES
CW-1	8"	#4 @ 12" O.C.	#4 @ 12" O.C.	(2) #5 TOP & BOTTOM, TYPE 'A'

1. ALL WALLS ARE MARK CW-1, U.N.O.
2. CONTRACTOR TO VERIFY ALL WALL THICKNESSES W/ ARCHITECT.
3. PROVIDE CORNER BARS AT ALL CORNERS AND INTERSECTING WALLS, SEE DETAIL D2/SE501
4. WHEN A SINGLE CURTAIN OF REINFORCING IS SPECIFIED, PLACE THE VERTICAL REINFORCING IN THE CENTER OF THE WALL, TYPICAL, U.N.O.
5. WHEN A DOUBLE CURTAIN OF REINFORCING IS SPECIFIED, PLACE EACH CURTAIN OF STEEL AT THE FACE OF THE WALL WITH MINIMUM COVER AS SPECIFIED IN THE GENERAL NOTES. PLACE THE VERTICAL REINFORCING CLOSEST TO THE FORMS, TYPICAL, U.N.O.
6. PROVIDE DOWELS WITH STANDARD HOOKS TO THE STRUCTURE BELOW WITH SIZE AND SPACING TO ATTACH THE VERTICAL REINFORCING IN THE WALL ABOVE.
7. SPLICE VERTICAL REINFORCING AT FLOOR LEVELS ONLY, TYPICAL, U.N.O.
8. SPLICES IN HORIZONTAL REINFORCING IN ONE CURTAIN SHALL BE STAGGERED FROM SPLICES IN THE OPPOSITE CURTAIN A MINIMUM OF FOUR FEET.




# HFSArchitects

ARCHITECTURE  
INTERIORS  
PLANNING


1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT



Structural  
Engineering

442 North Main Street, Suite 200  
Bountiful, Utah 84010  
e-mail: cliff.cole@wcaeng.com  
(801) 298-1118, Office 298-1122 Fax



## CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION

DATE:

AGENCY PROJECT NO: 06134220

HFSA PROJECT NO: 0615.01

CAD DWG FILE NO:

DRAWN BY: NT

CHECKED BY: KW

DESIGNED BY: KW

DWG TYPE:

ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS



SHEET TITLE

FOOTING & FOUNDATION PLAN  
&  
ROOF FRAMING PLAN

# SE101


SHEET OF





**HFSA**Architects  
ARCHITECTURE  
INTERIORS  
PLANNING  
1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT  
**WCA**  
Structural  
Engineering inc.  
442 North Main Street, Suite 200  
Bountiful, Utah 84010  
e-mail: cliff.cole@wcaeng.com  
(801) 298-1118, Office 298-1122 Fax



CULINARY REMODEL


DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION


DATE:  
AGENCY PROJECT NO: 06134220  
HFSA PROJECT NO: 0615.01  
CAD DWG FILE NO:  
DRAWN BY: NT  
CHECKED BY: KW  
DESIGNED BY: KW  
DWG TYPE:  
ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS

SHEET TITLE  
ELEVATIONS  
**SE201**  
SHEET OF







**D1** TYPICAL HOOKS & BENDS  
NO SCALE




**D2** CONCRETE OR MASONRY WALL CORNER REINF.  
NO SCALE




**D3** SLAB ON GRADE JOINT  
NO SCALE




**D4** DETAIL  
NO SCALE




**D5** EXISTING CONNECTION  
NO SCALE




**C1** EXISTING CONNECTION @ CORNERS  
NO SCALE




**C2** DETAIL  
NO SCALE




**C3** DETAIL  
NO SCALE




**C4** DETAIL  
NO SCALE




**C5** DETAIL  
NO SCALE




**B1** DETAIL  
NO SCALE





**B2** DETAIL  
NO SCALE




**B3** DETAIL  
NO SCALE




**B4** DETAIL  
NO SCALE




**A5** SECTION THRU CURTAIN WALL  
NO SCALE




**A1** FOLDING PARTITION SUPPORT  
NO SCALE




**A2** FOLDING PARTITION SUPPORT  
NO SCALE



**A3** DETAIL  
NO SCALE



**A4** DETAIL  
NO SCALE




**HFS Architects**  
ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT

**WCA**  
Structural  
Engineering Inc.

442 North Main Street, Suite 200  
Bountiful, Utah 84010  
e-mail: cliff.cole@wcaeng.com  
(801) 298-1118, Office 298-1122 Fax



**CULINARY REMODEL**

DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION

DATE:

AGENCY PROJECT NO: 06134220

HFSa PROJECT NO: 0615.01

CAD DWG FILE NO:

DRAWN BY: NT

CHECKED BY: KW

DESIGNED BY: KW

DWG TYPE:


ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS

SHEET TITLE

**DETAILS**


**SE501**  
SHEET OF





# MECHANICAL DEMOLITION FLOOR PLAN

SCALE: 1/8" = 1'-0"




## SHEET NOTES:

- 1 REMOVE EXISTING DIFFUSER, DUCTWORK, AND ACCESSORIES AS SHOWN.
- 2 CAP EXISTING DUCT BRANCH.
- 3 REMOVE EXISTING THERMOSTAT AND ASSOCIATED CONTROLS, WIRING, ETC. UPDATE BMS.
- 4 EXISTING VAV BOX AND ASSOCIATED PIPING, DUCT, AND CONTROLS TO BE REMOVED.
- 5 REMOVE EXISTING PIPING BRANCH BACK TO MAIN AND CAP.

## GENERAL NOTES:

1. FIELD VERIFY EXISTING CONDITIONS INCLUDING EXACT LOCATION OF MECHANICAL EQUIPMENT, PIPING, DUCTWORK, ETC.

## KEY PLAN



**HFSArchitects**

ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT



**WHW**  
**ENGINEERING INC.**  
PROFESSIONAL MECHANICAL ENGINEERING  
1354 East 3300 South Suite 200  
SALT LAKE CITY, UTAH 84106  
(801) 466-4021, FAX 466-8538  
EMAIL: excellence@whw-engineering.com

## CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION


DATE:	
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

## MECHANICAL DEMOLITION FLOOR PLANS

**MD101**


SHEET OF





MECHANICAL FLOOR PLAN

SCALE: 1/8" = 1'-0"




SHEET NOTES:

- CONNECT NEW 1-1/2" GAS PIPE TO EXISTING 4" GAS LINE ABOVE KITCHEN. ROUTE TIGHT TO STRUCTURE TO MINIMIZE CONFLICT WITH EXISTING AND NEW DUCTWORK. FIELD VERIFY EXACT LOCATION TO TIE IN. TOTAL NEW LOAD ON REG: 400MBH ESTIMATED TOTAL LOAD ON EXISTING REGULATOR: 4,712,950 DESIGN PRESSURE: 4 OZ LONGEST LENGTH TO REGULATOR:160'
- EXTEND EXISTING FIRE SPRINKLER SYSTEM INTO NEW AREA. PROVIDE NEW HEADS TO MATCH EXISTING. PROVIDE SHOP DRAWINGS STAMPED BY NICET CERTIFIED DESIGNER.
- TIE NEW PRIMARY AND SECONDARY ROOF DRAINS INTO EXISTING ROOF DRAINS. FIELD VERIFY EXACT LOCATION FOR TIE IN.
- PROVIDE NEW THERMOSTAT FOR NEW ROOFTOP. VERIFY EXACT LOCATION OF THERMOSTAT WITH OWNER / USER. TIE INTO EXISTING BMS, UPDATE GRAPHICS, ETC.
- FIELD VERIFY EXACT ROUTING OF DUCTWORK TO ENSURE BEST ROUTING.
- PROVIDE NEW DIFFUSERS AND CONNECT TO EXISTING DUCTWORK. TRANSITION AS NECESSARY TO CONNECT TO EXISTING.
- RECONNECT EXISTING MAIN SUPPLY TRUNK TO NEW SUPPLY FROM NEW RTU SERVING THE DINNING AREA.
- EXISTING SUPPLY AND RETURN DUCTWORK FROM EXISTING AIR HANDLERS ABOVE SHALL REMAIN.
- PROVIDE NEW CEILING RETURN GRILLES OPEN TO CEILING PLENUM FOR RETURN TO EXISTING SYSTEM.

GENERAL NOTES:

- FIELD VERIFY EXISTING CONDITIONS INCLUDING EXACT LOCATION OF MECHANICAL EQUIPMENT, PIPING, DUCTWORK, ETC.

KEY PLAN



HFSArchitects

ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT



**WHW**  
ENGINEERING INC.  
PROFESSIONAL MECHANICAL ENGINEERING  
1354 East 3300 South Suite 200  
SALT LAKE CITY, UTAH 84106  
(801)466-4021, FAX 466-8538  
EMAIL: excellence@whw-engineering.com

CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY  
COLLEGE


MARK	DATE	DESCRIPTION

DATE:	
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	


MECHANICAL  
FLOOR PLAN


ME101

SHEET OF



- SHEET NOTES:**
- 1 SEE DETAIL A1 SHEET ME601 FOR GAS LINE CONNECTION TO UNIT. PATCH SEAL PENETRATION THRU ROOF.
  - 2 MAINTAIN MINIMUM 10' CLEARANCE BETWEEN ROOF TOP UNITS AND EDGE OF ROOF.
  - 3 FOLLOW MANUFACTURERS INSTALLATION INSTRUCTIONS AND CLEARANCE REQUIREMENTS FOR ROOF TOP UNITS.
  - 4 ADD NEW PRIMARY AND SECONDARY ROOF DRAINS TO SERVE NEW ROOF AREA. TIE EXISTING PIPING BELOW. SEE SHEET ME101 FOR CONTINUATION.
  - 5 VERIFY FLUES ARE INSTALLED A MINIMUM OF 25' FROM MAIN AIR HANDLER FRESH AIR INTAKE AND MAKE-UP AIR UNIT INTAKE. PROVIDE FLUE EXTENSION FOR FLUE TO DISCHARGE A MINIMUM 7' ABOVE THE ROOF.





**HFSArchitects**


ARCHITECTURE

INTERIORS

PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0693/F: 596-0693  
www.hfsa.com

CONSULTANT



**WHW**  
ENGINEERING INC.  
PROFESSIONAL MECHANICAL ENGINEERING

1354 East 3300 South Suite 200  
SALT LAKE CITY, UTAH 84106  
(801)466-4021, FAX 466-8538  
EMAIL: excellence@whw-engineering.com

CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY COLLEGE

MARK	DATE	DESCRIPTION

DATE:

AGENCY PROJECT NO: 06134220

HFS PROJECT NO: 0615.01

CAD DWG FILE NO:

DRAWN BY: STAFF

CHECKED BY: SLW

DESIGNED BY: WP

DWG TYPE: MECHANICAL AND PLUMBING

ARCHITECTURAL PHASE: CONSTRUCTION DOCUMENTS

SHEET TITLE

MECHANICAL ROOF PLAN

ME102

SHEET OF

DIMENSION OF LONGEST SIDE, INCHES	SHEET METAL GAGE (ALL FOUR SIDES)	MINIMUM REINFORCING ANGLE SIZE AND MAXIMUM LONGITUDINAL SPACING BETWEEN TRANSVERSE JOINTS &/OR INTERMEDIATE REINFORCING	TRANSVERSE REINFORCING (1)			
			AT JOINTS			
			MIN. H. IN.	DRIVE SLIP PLAIN S SLIP	HEMMED S SLIP	ALTERN'T BAR SLIP REIN-FORCED BAR SLIP
UP THRU 12	26	NONE REQUIRED	1	26	26	24
13 - 18	24	NONE REQUIRED	1	24	24	24
19 - 30	24	1"x1"x1/8" @ 60 IN	1	-	24	24
31 - 36	22	1"x1"x1/8" @ 60 IN	1	-	-	22

1. TRANSVERSE REINFORCING SIZE IS DETERMINED BY DIMENSION OF SIDE TO WHICH ANGLE IS APPLIED.

### D1 DUCT CONSTRUCTION DETAIL


SCALE: NONE

LOW PRESSURE ROUND DUCT CONSTRUCTION SCHEDULE				
DUCT DIAMETER IN INCHES	MAXIMUM 2" W.G. STATIC POSITIVE		MAXIMUM 2" W.G. STATIC NEGATIVE	
	SPIRAL SEAM GAUGE	LONGITUDINAL SEAM GAUGE	SPIRAL SEAM GAUGE	LONGITUDINAL SEAM GAUGE
3 thru 8	28	28	28	24
9 thru 14	28	26	26	24
15 thru 26	26	24	24	22
27 thru 36	24	22	22	20
37 thru 50	22	20	20	18

### C1 LOW PRESSURE ROUND DUCT CONSTRUCTION DETAIL


SCALE: NONE

NOTE:  
L=1/4 W (4" MINIMUM.)




### A1 BRANCH DUCT TAKE-OFF & DAMPER DETAIL

SCALE: NONE




### D3 ROOFTOP UNIT DETAIL

SCALE: NONE




### D5 DUCT SUPPORTS

SCALE: NONE



### C3 RETURN AIR BOOT DETAIL

SCALE: NONE




### C5 ROOF DRAIN DETAIL

SCALE: NONE


NOTE: TAKE-OFFS SHOULD NOT BE INSTALLED CLOSER THAN TWO WIDTHS TO ELBOWS OR INTERSECTIONS

NOTE: AREA OF A x B SHALL BE EQUAL TO 1.5 x AREA BRANCH DUCT




### A2 SQUARE-TO-ROUND TAKE-OFF DETAIL

SCALE: NONE



### A5 DUCT LINER DETAIL

SCALE: NONE



**HFSArchitects**

ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT



**WHW**  
ENGINEERING INC.  
PROFESSIONAL MECHANICAL ENGINEERING  
1354 East 3300 South Suite 200  
SALT LAKE CITY, UTAH 84106  
(801) 466-4021, FAX 466-8538  
EMAIL: excellence@whw-engineering.com

## CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS
SHEET TITLE	

## MECHANICAL DETAILS

**ME501**

SHEET OF




D

C

B

A



**A1** GAS LINE CONNECTION DETAIL  
SCALE: NONE

REGISTER, LOUVER & GRILLE SCHEDULE

SYMBOL	TYPE	SERVICE	MAX CFM	NOMINAL SIZE	THROAT SIZE	CEILING TYPE	SCHEDULE NOTES
<div>R-1</div>	CEILING	RETURN	375	12/12	12/12	LAY-IN	1,2,3,4
<div>R-2</div>	CEILING	RETURN	1200	22/22	22/22	LAY-IN	1,2,3,4
<div>R-3</div>	CEILING	RETURN	1200	22/22	16"Ø	LAY-IN	1,2,3,4
REGISTER, LOUVER AND DIFFUSER SCHEDULE NOTES:							
1. MAXIMUM NC = 25 @ MAXIMUM CFM NOTED.							
2. SHALL BE PRICE 535 OR EQUAL BY OTHER APPROVED MANUFACTURERS.							
3. SEE SPECIFICATIONS FOR APPROVED MANUFACTURERS.							
4. FINISH SHALL BE OFF-WHITE BAKED ENAMEL.							

DIFFUSER SCHEDULE


SYMBOL	TYPE	MAX CFM	FACE SIZE	NCK SIZE	CEILING TYPE	BLOW	PATTERN	SCHEDULE NOTES
<div>D-1 CFM</div>	CEILING	380	12X12	10"Ø	LAY-IN	4--WAY		1,2,3
<div>D-2 CFM</div>	CEILING	650	15X15	14"Ø	LAY-IN	4--WAY		1,2,3
1. PROVIDE LAY-IN CEILING AND BORDER / MODULE AS REQUIRED. SEE ARCHITECTURAL CEILING PLANS.								
2. MAXIMUM NC 25 AT CFM LISTED.								
3. TRANSITION AS REQUIRED TO DUCT WORK SHOWN ON PLAN								

PLUMBING FIXTURE SCHEDULE

SYMBOL	FIXTURE	INDIVIDUAL LINE SIZES					REMARKS
		TRAP	WASTE	VENT	COLD WATER	HOT WATER	
<div>PRD-1</div>	PRIMARY ROOF DRAIN	-	3"	-	-	-	
<div>SRD-1</div>	SECONDARY ROOF DRAIN	-	3"	-	-	-	

ROOFTOP AIR CONDITIONER SCHEDULE (GAS HEAT)

SYMBOL	MANUFACTURER & MODEL NUMBER	SA CFM	OSA CFM	E.S.P. IN W.G.	HEATING	COOLING			ELECTRICAL						EER/ SEER	OPER. WT. (LBS)	SCHEDULE NOTES
					TOT. MIN. INPUT MBH	AMB. AIR (DB)	AMB. AIR (WB)	MIN. TOTAL MBH	V - Ø - Hz	COMPRESSOR #	COMPRESSOR TOTAL RLA	COMPRESSOR TOTAL LRA	MCA	MOCP			
<div>RT 1</div>	CARRIER 48TM005	1600	320	0.7	150	95	67	50	460/3/60	1	8.3	45	15.2	20	*/10.0	700	1,2,3,4,6,7,8
<div>RT 2</div>	CARRIER 48TM014	4800	960	0.8	250	95	67	147	460/3/60	2	9	75	28.7	35	9.5/*	1300	1,2,4,5,6,7,8
1. E.S. P. DOES NOT INCLUDE LOSSES THROUGH ACCESSORIES.																	
2. RATED MINIMUM INPUT AT SEA LEVEL.																	
3. PROVIDE ONE 15 AMP, 120 VOLT, DUPLEX GFCI SERVICE OUTLET. MCA AND MOCP LISTED INCLUDE CONVIENCE OUTLET LOAD.																	
4. BELT DRIVE UNIT, R-22.																	
5. PROVIDE POWER EXHAUSTER.																	
6. PROVIDE WITH PROGRAMMABLE THERMOSTAT.																	
7. PROVIDE WITH ECONOMIZER.																	
8. PROVIDE WITH 2 STAGE GAS HEAT. CAPACITY SHOWN IS FOR HIGH HEAT.																	



**HFS**Architects

ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT



**WHW**  
ENGINEERING INC.  
PROFESSIONAL MECHANICAL ENGINEERING  
1354 East 3300 South Suite 200  
SALT LAKE CITY, UTAH 84106  
(801)466-4021, FAX 466-8538  
EMAIL: excellence@whw-engineering.com

CULINARY REMODEL

DAVIS APPLIED TECHNOLOGY  
COLLEGE

MARK	DATE	DESCRIPTION

DATE:	
AGENCY PROJECT NO:	06134220
HFSA PROJECT NO:	0615.01
CAD DWG FILE NO:	
DRAWN BY:	STAFF
CHECKED BY:	SLW
DESIGNED BY:	WP
DWG TYPE:	MECHANICAL AND PLUMBING
ARCHITECTURAL PHASE:	CONSTRUCTION DOCUMENTS





SHEET TITLE



























MECHANICAL  
SCHEDULES AND  
DETAILS

**ME601**

SHEET OF





ELECTRICAL SYMBOL LIST	
SYMBOL	DESCRIPTION
<b>LIGHTING SYMBOLS</b>	
	RECESSED FLUORESCENT FIXTURE
	SURFACE MOUNTED FLUORESCENT FIXTURE
	INDUSTRIAL STRIP LIGHT
	RECESSED FIXTURE
	WALL MOUNTED FIXTURE
	SURFACE FIXTURE
	EXIT LIGHT. ARROWS SHOW EXIT DIRECTION
	LIGHTING FIXTURE CALLOUT. NUMBER INDICATES A SUGGESTED QUANTITY- TO BE VERIFIED
	REFERENCE NOTE CALLOUT
	SINGLE POLE TOGGLE SWITCH - 20 AMP
	SINGLE POLE TOGGLE SWITCH - 20 AMP LETTERS INDICATE SWITCH ASSIGNMENT
	THREE WAY TOGGLE SWITCH - 20 AMP
	LOW PROFILE SLIDE DIMMER-SUITABLE FOR THE LOAD.
	4 HOUR SPRING WOUND TIMER SWITCH TO CONTROL THE LIGHT FIXTURE - 277 VOLT
<b>POWER SYMBOLS</b>	
	DUPLEX CONVENIENCE OUTLET - 20 AMP
	DUPLEX CONVENIENCE OUTLET - 20 AMP GFI. DO NOT PROTECT DOWNSTREAM GFI OUTLETS.
	DUPLEX CONVENIENCE OUTLET - 20 AMP ELECTRIC WATER COOLER
	DUPLEX OUTLET WITH CHILD PROOF COVER - 20 AMP
	SINGLE 20A OUTLET W/LOCKING MECHANISM. GFI PROTECTED.
	SPECIAL PURPOSE SINGLE PHASE OUTLET
	SPECIAL PURPOSE THREE PHASE OUTLET
	ARROWS INDICATE HOME RUNS - NUMBER OF CONDUCTORS AS REQUIRED
	FUSED DISCONNECT SWITCH - SIZE AS REQUIRED
	FLUSH TELEPHONE/DATA OUTLET
	FLUSH TELEPHONE OUTLET
	FLUSH DATA OUTLET
<b>SPECIAL SYSTEMS SYMBOLS</b>	
	FIRE ALARM MANUAL PULL STATION
	FIRE ALARM HORN WITH STROBE HIGH DECIBEL



LIGHTING FIXTURE SCHEDULE			
SYMBOL	DESCRIPTION	LAMPS	APPROVED MANUFACTURERS CATALOG NUMBER
(T-1)	LINEAR PENDENT MOUNTED FLUORESCENT LIGHT FIXTURE TO MATCH EXISTING. FIELD VERIFY PRIOR TO ORDERING FOR EXACT CATALOG NUMBER.	X	BUILDING STANDARD
		X	
(T-2)	6" APERTURE DOWN LIGHT	20F32	COLUMBIA LIGHTOLIER LIGHTOLIER CFTD832HEB-S1FD802H-B24
	EXISTING EXIT SIGNS TO BE RELOCATED.	EXISTING	X
(EX-1)		X	

NOTES:

1. ALL FLUORESCENT LIGHTS SHALL HAVE ELECTRONIC PROGRAMMABLE START BALLAST'S, 10% TOTAL HARMONIC DISTORTION UNIVERSAL, ADVANCE AND HOWARD ARE APPROVED MANUFACTURERS. BALLAST'S TO HAVE 5 YEAR WARRANTY.
2. ALL FLUORESCENT LAMPS SHALL HAVE 4100° COLOR TEMPERATURE.
3. FIELD VERIFY ALL LIGHTING VOLTAGES PRIOR TO PLACING ANY ORDER.
4. THE WRITTEN CRITERIA OF THE FIXTURE DESCRIPTION TAKES PRECEDENCE OVER THE CATALOG NUMBER.

**GENERAL NOTES:**

1. IN THE EXISTING SPACES TO BE RENOVATED, THE CONTRACTOR SHALL REMOVE ALL LIGHT FIXTURES, SWITCHES, WIRING, CONDUIT, WIRING DEVICES, FIRE ALARM DEVICES, SPEAKERS, VOLUME CONTROLS, ETC. AS REQUIRED WHETHER OR NOT SHOWN ON THE DRAWINGS.
2. ALL MATERIALS TO BE REMOVED FROM THE PREMISES SHALL BE RETURNED TO THE OWNER. MATERIALS WHICH THE OWNER DECIDES NOT TO KEEP SHALL BE SALVAGED AND REMOVED FROM THE SITE BY THE CONTRACTOR.
3. ALL CONCEALED CONDUIT THAT CANNOT BE REMOVED SHALL BE CUT FLUSH WITH THE FINISH SURFACES AND CAPPED OFF AFTER THE WIRING HAS BEEN DISCONNECTED AT THE PANEL AND REMOVED FROM THE CONDUIT.
4. IN AREAS WHERE CIRCUIT CONTINUITY IS INTERRUPTED, BUT MUST BE MAINTAINED BECAUSE OF THE NATURE OF THE FACILITY, MAKE ALL THE NECESSARY MODIFICATIONS TO THE CIRCUITS IN ORDER TO MAINTAIN THE CIRCUIT INTEGRITY.
5. THE COLOR OF ALL THE NEW DEVICES AND COVERPLATES SHALL BE COORDINATED WITH ARCHITECT.
6. REFER TO THE ARCHITECTURAL REFLECTED CEILING PLANS FOR THE EXACT LOCATION OF ALL LIGHTING FIXTURES.
7. THE COLOR OF THE LIGHT FIXTURES SHALL BE SELECTED BY THE ARCHITECT.
8. MINIMUM SIZE OF CONDUIT TO BE 3/4" 1/2" CONDUIT MAY BE USED FOR CONDUIT CABLES, ALUMINUM CONDUITS SHALL NOT BE USED.
9. USE RIGID STEEL SET SCREW TYPE FITTINGS ONLY. DIE CAST FITTINGS SHALL NOT BE USED.
10. SUPPORT THE LAY-IN TYPE FIXTURES FROM THE CEILING DUCK INDEPENDENT OF THE CEILING DUCK, AS SHOWN ON THE TYPICAL RECESSED FIXTURE MOUNTING DETAIL.
11. ALL NEW WORK MUST MEET THE CURRENT ADOPTED NATIONAL ELECTRICAL CODE.
12. NOT MORE THAN THREE (3) CIRCUITS, SHALL BE INSTALLED IN A 3/4" CONDUIT.
13. THE SIZE OF THE NEUTRAL CONDUCTORS SHALL BE NO. 10 AWG FOR ALL HOME RUNS WITH COMMON NEUTRAL (LIGHTING AND POWER CIRCUITS).
14. THE MINIMUM SIZE OF THE CONDUCTORS ARE TO BE #12 AWG THHN COPPER, UNLESS INDICATED OTHERWISE ON THE DRAWINGS.
15. ALL J-BOXES SHALL HAVE MINIMUM DEPTH OF 2-1/8" UNLESS OTHERWISE SPECIFIED. SECURE ALL J-BOXES AS SHOWN IN THE DETAILS. FURNISH AND INSTALL PROPER MUD RINGS.
16. ALL METALLIC CONDUITS, JOINTS, FITTINGS, ETC., IN CONTACT WITH THE GROUND SHALL BE SERIALLY WRAPPED WITH 3M SCOTCH-PAF-51, 20 MIL TAPE (OR APPROVED EQUAL). 1/2" OVERLAP IS REQUIRED.
17. ALL CONDUITS EXPOSED TO THE WEATHER AND IN THE MECHANICAL ROOM SHALL BE GALVANIZED RIGID STEEL, UNLESS OTHERWISE NOTED.
18. ALL NEW EXPOSED CONDUIT MUST RUN AGAINST THE WALLS OR CEILINGS. DO NOT PENDANT MOUNT ANY CONDUIT FROM THE CEILING.
19. ALL THE HOMERUNS MUST BE ACCESSIBLE. DO NOT CARRY A HOMERUN FROM ONE DEVICE TO ANOTHER WHICH IS TIED TO A SEPARATE HOMERUN INSIDE THE WALL. MARK ON ALL THE J-BOXES THE CIRCUIT NAMES AND NUMBERS. USE NO. 10 THIN CONDUCTORS FOR HOMERUNS OVER 400 FEET, NO. 8 THIN OVER 200 FEET, NO. 6 THIN OVER 300 FEET AND NO. 4 THIN OVER 400 FEET LENGTH.
20. COORDINATE WITH THE OWNER AND ARCHITECT FOR THE EXACT LOCATION OF THE OUTLETS.
21. LIGHT SWITCHES INSTALLED ADJACENT TO EACH OTHER, SHALL BE GANGED TOGETHER WITH ONE PICE COVERPLATE.
22. USE EPOXY ANCHORS TO SUPPORT THE ELECTRICAL EQUIPMENT. EXPANSION ANCHOR BOLTS ARE NOT ACCEPTED.
23. AT THE END OF THE JOB, PROVIDE BLANK COVER PLATES TO MATCH THE OTHER COVER PLATES FOR ALL J-BOXES WHERE DEVICES HAVE NOT YET BEEN INSTALLED.
24. SEAL AROUND ALL CONDUIT PENETRATIONS THROUGH WALLS AND CEILINGS WITH FIRE RATED MATERIAL. 3M IS AN APPROVED MANUFACTURER.
25. ALL MATERIALS USED IN THIS INSTALLATION SHALL BE U.L. APPROVED AND NEW.
26. ALL ELECTRICAL WIRING MUST BE IN CONDUIT (BOMEX NOT PERMITTED).
27. NO CONDUITS SHALL RUN IN DUCT WORK.
28. PRIOR TO SUBMITTING A BID THE ELECTRICAL CONTRACTOR SHALL INSPECT THE SITE AND INCLUDE IN HIS BID PACKAGE ALL CHARGES DUE TO EXISTING CONDITIONS. SHOP DRAWINGS ARE REQUIRED. ALL LABOR, MATERIAL AND WORKMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF 1 YEAR FROM THE DATE OF ACCEPTANCE BY THE TENANT. REPLACE OR REPAIR ALL DEFECTS DURING THE GUARANTEED PERIOD.
29. THE ELECTRICAL CONTRACTOR SHALL TERMINATE THE ELECTRICAL CONNECTIONS TO ALL THE EQUIPMENT BY PROVIDING THE NECESSARY MALE/FEMALE CONNECTOR, RECEPTACLE, PLUG, ETC.
30. ALL DUPLEX OUTLETS AND SWITCHES SHALL BE 20 AMP, 120 VOLT SPC GRADE. HUBBELL AND PASS & SEYMOUR AND LEVITON ARE APPROVED MANUFACTURERS.
31. ELECTRICAL CONTRACTOR SHALL VERIFY ALL ELECTRICAL LOADS (VOLTAGE, PHASE, CONNECTION REQUIREMENT, ETC.) OF EQUIPMENT FURNISHED UNDER OTHER DIVISIONS WITH APPROVED SHOP DRAWINGS. REFER TO BEGINNING RUGH-IN.
32. THE CONTRACTOR SHALL INFORM THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES FOUND BETWEEN THE INTENDED FUNCTION OF EQUIPMENT AND EQUIPMENT SPECIFIED IN THE CONTRACT DOCUMENTS. A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO ISSUANCE OF THE FINAL ADDENDUM. FAILURE TO REPORT ANY DISCREPANCY (CATALOG NUMBERS, DISCONTINUED ITEMS, ETC.) DOES NOT RELIEVE THE CONTRACTOR FROM PROVIDING EQUIPMENT WHICH SHALL CONFORM TO AND FULFILL THE INTENT OF THE CONTRACT DOCUMENTS. NOR SHALL IT BE USED AS A CONDITION TO OBTAIN ADDITIONAL FUNDS FROM THE OWNER AFTER THE CONTRACT IS AWARDED. THE CONTRACTOR SHALL SUBMIT ALL CLARIFICATIONS OF CONTRACT DOCUMENT REQUIREMENTS IN WRITING TO THE ARCHITECT/ENGINEER A MINIMUM OF FIVE WORKING DAYS PRIOR TO ISSUANCE OF THE FINAL ADDENDUM.

		
<h1 style="margin: 0;">HFS Architects</h1> <p style="margin: 0;"><b>ARCHITECTURE</b> <b>INTERIORS</b> <b>PLANNING</b></p>		
<p style="margin: 0;">1484 South State Street Salt Lake City, Utah 84115 801-596-0691/F: 596-0693 <a href="http://www.hfsa.com">www.hfsa.com</a></p>		
CONSULTANT		
 <p style="margin: 0; font-size: small;">1220 NORTH 300 WEST SALT LAKE CITY, UTAH 84101 (801) 406-3222 (801) 414-3332 fax</p>		
		
<h2 style="margin: 0;">CULINARY REMODEL</h2>		
<h3 style="margin: 0;">DAVIS APPLIED TECHNOLOGY COLLEGE</h3>		
MARK	DATE	DESCRIPTION
DATE:		21 DECEMBER 2006
AGENCY PROJECT NO:		06134220
HPSA PROJECT NO:		0615.01
CAD DWG FILE NO:		
DRAWN BY:		
CHECKED BY:		MA
DESIGNED BY:		JTB
DWG TYPE:		
ARCHITECTURAL PHASE: <b>CONSTRUCTION DOCUMENTS</b>		
SHEET TITLE		
<h1 style="margin: 0;">E0.01</h1>		
SHEET		OF





- REFERENCE NOTES:**
- 1 FURNISH AND INSTALL A 4"x4"x2-1/8" J-BOX IN THE APPROXIMATE LOCATION SHOWN FOR VOICE/DATA. RUN A 1" CONDUIT WITH A PULL STRING FROM THE J-BOX TO THE NEAREST ACCESSIBLE CEILING SPACE ON THIS FLOOR. COORDINATE WITH THE OWNER/ARCHITECT FOR EXACT LOCATION PRIOR TO ROUGH-IN.
  - 2 TIE EACH HOMERUN SHOWN TO A 120 VOLT, 20 AMP DEDICATED CIRCUIT IN THE ELECTRICAL ROOM. COORDINATE WITH THE OWNER FOR PROPER PANEL. PROVIDE CONDUITS, CONDUCTORS, CIRCUIT BREAKERS, ETC. FOR A COMPLETE INSTALLATION.
  - 3 FURNISH AND INSTALL NEW FIRE ALARM DEVICE IN THE APPROXIMATE LOCATION SHOWN. TIE THE NEW DEVICE TO THE EXISTING FIRE ALARM CONTROL PANEL. THE NEW DEVICE SHALL BE THE SAME AS AND BE COMPATIBLE WITH THE EXISTING SYSTEM. TEST AND CERTIFY THE SYSTEM TO MEET THE LOCAL AHS.
  - 4 FURNISH AND INSTALL A NEW FIRE ALARM PULL STATION IN THE APPROXIMATE LOCATION SHOWN AND TIE TO THE EXISTING FIRE ALARM CONTROL PANEL. PROVIDE CONDUITS, CONDUCTORS, ETC. FOR A COMPLETE WORKING INSTALLATION. COORDINATE WITH THE ARCHITECT FOR THE EXACT LOCATION.
  - 5 FURNISH AND INSTALL A 20 AMP, 460 VOLT, 3 POLE CIRCUIT BREAKER IN THE EXISTING PANEL "HKP" TO FEED THE NEW ROOF TOP UNIT. THE NEW BREAKER SHALL HAVE THE SAME AIC RATING AS THE REST OF THE BREAKERS. MAKE ANY MODIFICATIONS NECESSARY TO INSTALL THE NEW BREAKER(S) IN THE EXISTING PANEL. PROVIDE A 30 AMP WEATHER PROOF DISCONNECT SWITCH WITH 20 AMP FUSES ON THE ROOF FOR THE NEW ROOF TOP UNIT. REFER TO THE MECHANICAL DRAWINGS FOR THE EXACT LOCATION OF THE ROOF TOP UNIT. COORDINATE WITH BUILDING MANAGEMENT.
  - 6 FURNISH AND INSTALL A 35 AMP, 460 VOLT, 3 POLE CIRCUIT BREAKER IN THE EXISTING PANEL "HKP" TO FEED THE NEW ROOF TOP UNIT. THE NEW BREAKER SHALL HAVE THE SAME AIC RATING AS THE REST OF THE BREAKERS. MAKE ANY MODIFICATIONS NECESSARY TO INSTALL THE NEW BREAKER(S) IN THE EXISTING PANEL. PROVIDE A 60 AMP WEATHER PROOF DISCONNECT SWITCH WITH 35 AMP FUSES ON THE ROOF FOR THE NEW ROOF TOP UNIT. REFER TO THE MECHANICAL DRAWINGS FOR THE EXACT LOCATION OF THE ROOF TOP UNIT. COORDINATE WITH BUILDING MANAGEMENT.
  - 7 FURNISH AND INSTALL NEW DUCT DETECTOR WITH SAMPLING TUBE IN SUPPLY AND RETURN DUCT. THE NEW DUCT DETECTORS SHALL BE BY THE SAME MANUFACTURES AND BE COMPATIBLE WITH THE EXISTING SYSTEM. TIE THE DUCT DETECTORS TO THE FIRE ALARM CONTROL PANEL FOR MONITORING. ALSO, TIE THE ROOF TOP UNITS TO THE FIRE ALARM CONTROL PANEL FOR SHUT DOWN. COORDINATE THIS WORK WITH THE MECHANICAL SUB CONTRACTOR.
  - 8 FURNISH AND INSTALL NEW CEILING MOUNTED RECESSED SPEAKERS IN THE APPROXIMATE LOCATIONS SHOWN. THE NEW SPEAKER SHALL BE THE SAME AS THE EXISTING ONES. TIE THE SPEAKER TO THE EXISTING SOUND SYSTEM. FIELD VERIFY. PROVIDE CONDUIT, CONDUCTORS, ETC. FOR A COMPLETE INSTALLATION.



**HFSArchitects**  
ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT



1200 ROUTE 200 WEST  
SALT LAKE CITY, UTAH 84143  
(801) 466-2222  
(801) 474-2222 Ext.



LICENSED PROFESSIONAL ENGINEER  
NO. 334543-2202  
MANSOUR AGHDAS  
STATE OF UTAH

**CULINARY REMODEL**

**DAVIS APPLIED TECHNOLOGY  
COLLEGE**

MARK	DATE	DESCRIPTION

DATE: 21 DECEMBER 2006

AGENCY PROJECT NO: 06134220

HFSA PROJECT NO: 0615.01

CAD DWG FILE NO:

DRAWN BY:

CHECKED BY: MA

DESIGNED BY: JTB

DWG TYPE:


ARCHITECTURAL PHASE:  
CONSTRUCTION DOCUMENTS

SHEET TITLE

**E2.11**

SHEET OF





- REFERENCE NOTES:**
- 1 THE LIGHT FIXTURES INDICATED WITH A LOWER CASE LETTER TO ITS CORRESPONDING LIGHT SWITCHES. PROVIDE CONDUIT, CONDUCTORS, ETC. FOR A COMPLETE INSTALLATION.
  - 2 THE EMERGENCY LIGHT FIXTURES INDICATED WITH LETTER 'E' AND ALL EXIT SIGNS TO THE EMERGENCY POWER SYSTEM IN THE ELECTRICAL ROOM SO THAT ONE LAMP IN THE LIGHT FIXTURE TURN "ON" IN CASE OF POWER FAILURE REGARDLESS THE POSITION OF THE CONTROL SWITCH. PROVIDE CONDUIT, CONDUCTORS, RELAY (EQUAL TO BODINE GTD) BALLASTS ETC. FOR A COMPLETE INSTALLATION.
  - 3 RELOCATE EXISTING EXIT SIGN AND ASSOCIATED WIRING TO NEW LOCATION. CLEAN AND REPAIR THE EXIT SIGNS AS NEEDED FOR A COMPLETE WORKING SYSTEM.
  - 4 RELOCATE THE EXISTING 12' LIGHT FIXTURE SECTION TO OFFICE 118. CLEAN THE LIGHT FIXTURE AFTER INSTALLATION. REPAIR THE FIXTURE AS NECESSARY FOR A WORKING INSTALLATION. FURNISH AND INSTALL NEW T-1 LIGHT FIXTURES IN THE LOCATION SHOWN TO MATCH UP WITH THE EXISTING LAYOUT. COORDINATE WITH THE ARCHITECT ENGINEER.
  - 5 TIE TO THE NEAREST 277 VOLT LIGHTING CIRCUIT WITH AVAILABLE AMPACITY. PROVIDE CONDUITS, CONDUCTORS, RELAY, ETC. FOR A COMPLETE INSTALLATION.
  - 6 FURNISH AND INSTALL NEW MOTION SENSOR TO CONTROL THE LIGHT FIXTURES IN THE ROOM. THE NEW MOTION SENSOR SHALL BE THE SAME AS THE EXISTING ONES. MODIFY THE EXISTING LIGHTING CIRCUIT TO ACCOMMODATE THE NEW SWITCHING. FIELD VERIFY.
  - 7 COORDINATE WITH THE OWNER AND RELOCATE THE EXISTING SECURITY SYSTEM DEVICES AND THE ASSOCIATED CIRCUITS. FIELD VERIFY.



**HFS Architects**  
ARCHITECTURE  
INTERIORS  
PLANNING

1484 South State Street  
Salt Lake City, Utah 84115  
801-596-0691/F: 596-0693  
www.hfsa.com

CONSULTANT



1200 ROUTE 200 WEST  
SALT LAKE CITY, UTAH 84146 (801)466-2222 (801)474-2522 Inc.



LICENSED PROFESSIONAL ENGINEER  
NO. 334543-2202  
MANSOUR AGHDAS  
STATE OF UTAH

**CULINARY REMODEL**

**DAVIS APPLIED TECHNOLOGY COLLEGE**

MARK	DATE	DESCRIPTION

DATE: 21 DECEMBER 2006

AGENCY PROJECT NO: 08134220

HFSA PROJECT NO: 0815.01

CAD DWG FILE NO:

DRAWN BY:

CHECKED BY: MA

DESIGNED BY: JTB

DWG TYPE:

ARCHITECTURAL PHASE: CONSTRUCTION DOCUMENTS

SHEET TITLE

**E9.11**

SHEET OF