



State of Utah—Department of Administrative Services

DIVISION OF FACILITIES CONSTRUCTION
AND MANAGEMENT

4110 State Office Building/Salt Lake City, Utah 84114/538-3018

REDWOOD ROAD ABC STORE - REMODEL AND EXPANSION
DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH
DFCM PROJECT NO. 06233030

MAY 2007

CONSTRUCTION DRAWINGS

PROJECT INFORMATION

OWNER:	STATE OF UTAH DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT 4110 STATE OFFICE BUILDING SALT LAKE CITY, UTAH 84114	ARCHITECT:	FRANK N MURDOCK JR ARCHITECT + ASSOCIATES 975 EAST 100 SOUTH SALT LAKE CITY, UTAH 84102
PROPOSED USE	PROPOSED ADDRESS		
STATE LIQUOR STORE	3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH		
SITE INFORMATION (NOT FOR MATERIAL TAKE OFF USE)	PARKING INFORMATION		
TOTAL SITE:	33,836 SQ FT ±	CUSTOMER & EMPLOYEE PARKING: 42 PARKING STALLS	
BUILDING FOOTPRINT:	8,410 SQ FT	1 STALL / 200 SQ FT OF GROSS AREA	
HARD SURFACE AREA:	36,722 SQ FT		
LANDSCAPING AREA:	9,338 SQ FT		

SITE DRAWINGS

SEE SHEET AS101 FOR GENERAL SITE DEMOLITION PLAN AND NEW SITE PLAN
SEE SHEET AS102 FOR SITE GRADING AND STORM SEWER INFORMATION
SEE SHEET AS103 FOR SITE UTILITY INFORMATION
SEE SHEET AS501 FOR SITE DETAIL INFORMATION

SITE PLAN LEGEND

■	CATCH BASIN	T.O.G	TOP OF GRATE	—X—X—	FENCE
⊗	STORM DRAIN MAN HOLE	I.E.	INVERT ELEVATION	—	FENCE
◆	POWER POLE	T.O.SW	TOP OS SIDEWALK	—	2 - 4" PVC PIPE SLEEVE
⌵	WATER VALVE	T.O.PV	TOP OF PAVEMENT	—	EXISTING GRADE CONTOUR
□	ELECTRIC BOX	T.O.C.	TOP OF CONCRETE	4434	
⊙	FIRE HYDRANT	—	OVERHEAD POWER LINE	③	NEW GRADE CONTOUR
•	LIGHT POST	—SS—	SANITARY SEWER	—	CENTER LINE OF ROAD
□	STREET LIGHT BOX	—W—	WATER LINE	—	
■	GAS METER	—T—	TELEPHONE LINE	—	
■	TELEPHONE BOX	—G—	GAS LINE	—	
PL	PROPERTY LINE	---C---	CABLE T.V.	—	
L	LANDSCAPE AREA	—	PARKING STALLS	—	
SW	SIDEWALK			—	
⊙	SANITARY SEWER MAN HOLE			—	

GENERAL NOTES

- REFER TO SITE DEVELOPMENT, LANDSCAPE, MECHANICAL AND ELECTRICAL DRAWINGS FOR DIMENSIONS AND ADDITIONAL SITE INFORMATION.
- CONTRACTOR TO VERIFY ALL EXISTING SITE CONDITIONS. NOTIFY ARCHITECT OF ANY DISCREPANCIES TO THE CONTRACT DOCUMENTS.
- PROVIDE POSITIVE DRAINAGE AWAY FROM BUILDING AT ALL POINTS.
- CONTRACTOR SHALL NOT PARK, STORE EQUIPMENT, OR USE THE EXISTING ROAD FOR ANY PURPOSE OTHER THAN ACCESS TO THE PROJECT SITE. CONTRACTOR SHALL NOT DISTURB OR USE ANY AREA OUTSIDE CONTRACT LIMIT LINE TO PARK OR STORE EQUIPMENT. UNLESS OTHERWISE NOTED, THE PROPERTY LINE SHALL FORM THE BOUNDARY OF THE CONTRACT LIMIT LINE.
- CONTRACTOR WILL MAINTAIN AND PROTECT ALL EXISTING UTILITIES DURING CONSTRUCTION.
- ALL CUTTING, PATCHING, EXCAVATION AND BACKFILL DONE IN STREET SHALL BE DONE IN ACCORDANCE WITH UTAH DEPARTMENT OF TRANSPORTATION SPECIFICATIONS.
- PROVIDE PIPE SLEEVES WHERE SPRINKLER LINES PASS UNDER ASPHALT PAVEMENT, SIDEWALKS OR RETAINING WALLS.
- PROTECT ANY EXISTING STORM DRAINS FROM MUD AND DEBRIS DURING CONSTRUCTION.
- REPAIR OR REPLACE ANY DAMAGE TO EXISTING PROPERTY, PAVEMENT, STRUCTURES, ETC. CAUSED BY WORK UNDER THIS CONTRACT WHICH ARE NOT SCHEDULE TO BE REMOVED.
- MAINTAIN EXISTING UTILITIES IN FULL OPERATION. SHUT DOWN OF EXISTING UTILITIES IS TO BE KEPT TO A MINIMUM. 72 HOUR NOTICE IS TO BE GIVEN TO THE OWNER PRIOR TO ANY UTILITY SHUT DOWN.
- THE STAGING AREA FOR THIS PROJECT IS LIMITED. STAGING IS TO BE KEPT WITHIN THE PROPERTY LINES. ACCESS TO THE ADJOINING PROPERTIES IS TO BE MAINTAINED DURING CONSTRUCTION. THE AREA OF CONSTRUCTION IS TO BE FENCED AT ALL TIMES.
- MAINTAIN AND PROTECT EXISTING LANDSCAPING NOT SCHEDULED FOR REMOVAL. REPLACE ANY LANDSCAPING DAMAGES DURING CONSTRUCTION.



REFERENCE NOTES
DEMOLITION SITE PLAN

- REMOVE AND PROPERLY DISPOSE OF EXISTING CONCRETE CURBS AND GUTTERS.
- REMOVE AND PROPERLY DISPOSE OF EXISTING CONCRETE SIDEWALK.
- REMOVE AND PROPERLY DISPOSE OF EXISTING LANDSCAPING INCLUDING ALL TREES AND SHRUBS WITHIN THE NEW CONSTRUCTION AREA.
- REMOVE AND PROPERLY DISPOSE OF EXISTING CONCRETE PAD AND CURBS AT SISSOR LIFT. MAINTAIN EXISTING LIFT IN OPERATION UNTIL NEW LIFT IS OPERATIONAL.
- NOT USED
- RELOCATE EXISTING NATURAL GAS LINE AND METER AS DIRECTED BY SERVICE PROVIDER. COORDINATE THE REMOVAL AND RELOCATION OF METER WITH THE UTILITY PROVIDER.
- REMOVE EXISTING DUMPSTER ENCLOSURE.
- MAINTAIN AND PROTECT EXISTING FENCE.
- MAINTAIN AND PROTECT EXISTING CURBS, GUTTERS AND ASPHALT. REPLACE ANY EXISTING CURBS, GUTTERS OR ASPHALT DAMAGED BY NEW CONSTRUCTION.
- MAINTAIN AND PROTECT EXISTING LANDSCAPING AND SPRINKLING SYSTEMS. REPLACE ANY LANDSCAPING OR SPRINKLING SYSTEMS DAMAGED BY NEW CONSTRUCTION.
- SEE SHEET AS-102 FOR RELOCATION OR ABANDONMENT OF EXISTING UTILITY SERVICES. REPLACE ANY ASPHALT, CONCRETE, LANDSCAPING OR SPRINKLING SYSTEMS DAMAGED BY NEW CONSTRUCTION.

REFERENCE NOTES
SITE PLAN

- MAINTAIN AND PROTECT EXISTING SITE ELEMENTS TO REMAIN INCLUDING EXISTING RETAINING WALLS, FENCES, STORM DRAIN BASIN AND CURBS AND GUTTERS.
- NEW CONCRETE CURB AND GUTTER. SEE DETAIL 6/AS501
- NEW 4" THICK CONCRETE SIDEWALK. SEE DETAILS 11, 12 AND 13 SHEET AS501 ALIGN WITH EDGES AND ELEVATIONS OF EXISTING SIDEWALKS WHERE NEW AND EXISTING SIDEWALKS MEET. JOINTS AS NOTED BELOW TYPICAL UNLESS NOTED OTHERWISE
CONTROL JOINT IN CONCRETE SIDEWALK:
@ 5'-0" O.C. - SEE DETAIL 12/AS501.
EXPANSION JOINT IN CONCRETE SIDEWALK
@ 20'-0" O.C. - SEE DETAIL 13/AS501.
- NEW ASPHALT CONCRETE PAVING. SEE DETAIL 10/AS501 FOR PAVEMENT SECTION. SEE SOILS REPORT FOR DEPTH OF FILL AND COMPACTION REQUIREMENTS IN THIS AREA.
- NEW DRY SUMP CATCH BASIN SEE DETAIL 1/AS102
- NEW PARKING STRIPING SEE DETAIL 3/AS501
- NEW CONCRETE SPLASH BLOCK.
- NEW 8" THICK CONCRETE APRON. SEE 5/AS501. CONCRETE AT APRONS AND DRIVES (INCLUDING SIDEWALK AT DRIVE) TO BE MINIMUM 8" THICK.
- APPROXIMATE LOCATION OF CONSTRUCTION FENCE. EXACT LOCATION TO BE COORDINATED WITH OWNER.
- REMOVE LANDSCAPING. INSTALL NEW 4' WIDE CONCRETE SIDEWALK, MAX. SLOPE 1:20
- REMOVE LANDSCAPING AND SECTION OF EXISTING CONCRETE CURB. INSTALL NEW 4' WIDE CONCRETE RAMP, MAX. SLOPE 1:12 IN 6'-0".
- PAINT 4" WIDE STRIPING (2 COATS) TO DESIGNATE WALKWAY.
- REMOVE LANDSCAPING AND SECTION OF EXISTING CONCRETE CURB. INSTALL NEW 4' WIDE CONCRETE SIDEWALK, MAX. SLOPE 1:20.

REDWOOD ROAD





ABC STORE - REDWOOD RD - EXISTING SITE

SCALE: 1" = 20'
0 10' 25' 50'

DEMOLITION AND SITE CLEARING

IT IS THE INTENT OF THIS PROJECT TO REMOVE AND PROPERLY DISPOSE OF ALL EXISTING IMPROVEMENTS NOTED TO BE REMOVED. SAW CUT EXISTING ASPHALT IN AREAS NOTED TO BE REMOVED. THE AREAS OF THE SITE SCHEDULED FOR NEW CONSTRUCTION SHOULD THEN BE GRUBBED IN ACCORDANCE WITH THE REQUIREMENTS OF THE SOILS REPORT AND PREPARED FOR NEW CONSTRUCTION.

REDWOOD ROAD




ABC STORE ADDITION - REDWOOD RD - SITE PLAN

SCALE: 1" = 20'
0 10' 25' 50'

73 PARKING STALLS

REDWOOD ROAD ABC STORE - REMODEL AND EXPANSION

DEPT OF ALCOHOLIC BEVERAGE CONTROL
3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH



REVISION # DATE:

DFCM PROJECT NO.:
062330303
CONST DOC
FILE NAME: ABCR-AS101
PLOT SCALE: 1:240
DRAWN BY: STAFF
CHECKED BY: FNM
DATE: MAY 2007

AS
101

OWNER: STATE OF UTAH
DIVISION OF FACILITIES
CONSTRUCTION AND MANAGEMENT
4110 STATE OFFICE BUILDING
SALT LAKE CITY, UTAH 84114

ARCHITECT: FRANK N MURDOCK JR
ARCHITECT + ASSOCIATES
975 EAST 100 SOUTH
SALT LAKE CITY, UTAH 84102


<u>PROPOSED USE</u>		<u>PROPOSED ADDRESS</u>	
STATE LIQUOR STORE		3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH	
<u>SITE INFORMATION (NOT FOR MATERIAL TAKE OFF USE)</u>		<u>PARKING INFORMATION</u>	
TOTAL SITE:	33,836 SQ FT ±	CUSTOMER & EMPLOYEE PARKING: 42 PARKING STALLS 1 STALL / 200 SQ FT OF GROSS AREA	
BUILDING FOOTPRINT:	8,410 SQ FT	15%	
HARD SURFACE AREA:	36,722 SQ FT	67%	
LANDSCAPING AREA:	9,336 SQ FT	18%	

SEE SHEET AS101 FOR GENERAL SITE DEMOLITION PLAN AND NEW SITE PLAN
SEE SHEET AS102 FOR SITE GRADING AND STORM SEWER INFORMATION
SEE SHEET AS103 FOR SITE UTILITY INFORMATION
SEE SHEET AS501 FOR SITE DETAIL INFORMATION

—	CATCH BASIN	T.O.G	TOP OF GRATE	—X—X—	FENCE
◆	STORM DRAIN MAN HOLE	I.E.	INVERT ELEVATION	—	FENCE
◆	POWER POLE	T.O.SW	TOP OS SIDEWALK	=====	2 - 4" PVC PIPE SLEEVE
X	WATER VALVE	T.O.PV	TOP OF PAVEMENT	=====	EXISTING GRADE CONTOUR
⊠	ELECTRIC BOX	T.O.C.	TOP OF CONCRETE	4434	
⊠	FIRE HYDRANT	—————	OVERHEAD POWER LINE		
⊠	LIGHT POST	— — — — —	UNDERGROUND POWER LINE	(31)	NEW GRADE CONTOUR
⊠	STREET LIGHT BOX	— SS —	SANITARY SEWER	— C&L —	CENTER LINE OF ROAD
⊠	GAS METER	— W —	WATER LINE		
■	TELEPHONE BOX	— T —	TELEPHONE LINE	(A) (B)	SIGN TYPES - SEE 2/ASS01
PL	PROPERTY LINE	— G —	GAS LINE		
L	LANDSCAPE AREA	- - - - -	CABLE T.V.		
SW	SIDEWALK	—————	PARKING STALLS		
⊠	SANITARY SEWER MAN HOLE				

NEW CONCRETE PAVING
AND SIDEWALKS

1. REFER TO SITE DEVELOPMENT, LANDSCAPE, MECHANICAL AND ELECTRICAL DRAWINGS FOR DIMENSIONS AND ADDITIONAL SITE INFORMATION.
2. CONTRACTOR TO VERIFY ALL EXISTING SITE CONDITIONS. NOTIFY ARCHITECT OF ANY DISCREPANCIES TO THE CONTRACT DOCUMENTS.
3. PROVIDE POSITIVE DRAINAGE AWAY FROM BUILDING AT ALL POINTS.
4. CONTRACTOR SHALL NOT PARK, STORE EQUIPMENT, OR USE THE EXISTING ROAD FOR ANY PURPOSE OTHER THAN ACCESS TO THE PROJECT SITE. CONTRACTOR SHALL NOT DISTURB OR USE ANY AREA OUTSIDE CONTRACT LIMIT LINE TO PARK OR STORE EQUIPMENT. UNLESS OTHERWISE NOTED, THE PROPERTY LINE SHALL FORM THE BOUNDARY OF THE CONTRACT LIMIT LINE.
5. CONTRACTOR WILL MAINTAIN AND PROTECT ALL EXISTING UTILITIES DURING CONSTRUCTION.
6. ALL CUTTING, PATCHING, EXCAVATION AND BACKFILL DONE IN STREET SHALL BE DONE IN ACCORDANCE WITH UTAH DEPARTMENT OF TRANSPORTATION SPECIFICATIONS.
7. PROVIDE PIPE SLEEVES WHERE SPRINKLER LINES PASS UNDER ASPHALT PAVEMENT, SIDEWALKS OR RETAINING WALLS.
8. PROTECT ANY EXISTING STORM DRAINS FROM MUD AND DEBRIS DURING CONSTRUCTION.
9. REPAIR OR REPLACE ANY DAMAGE TO EXISTING PROPERTY, PAVEMENT, STRUCTURES, ETC. CAUSED BY WORK UNDER THIS CONTRACT WHICH ARE NOT SCHEDULED TO BE REMOVED.
10. MAINTAIN EXISTING UTILITIES IN FULL OPERATION. SHUT DOWN OF EXISTING UTILITIES IS TO BE KEPT TO A MINIMUM. 72 HOUR NOTICE IS TO BE GIVEN TO THE OWNER PRIOR TO ANY UTILITY SHUT DOWN.
11. THE STAGING AREA FOR THIS PROJECT IS LIMITED. STAGING IS TO BE KEPT WITHIN THE PROPERTY LINES. ACCESS TO THE ADJOINING PROPERTIES IS TO BE MAINTAINED DURING CONSTRUCTION. THE AREA OF CONSTRUCTION IS TO BE FENCED AT ALL TIMES.
12. MAINTAIN AND PROTECT EXISTING LANDSCAPING NOT SCHEDULED FOR REMOVAL. REPLACE ANY LANDSCAPING DAMAGES DURING CONSTRUCTION.



NOTE: DRY SUMP MUST BE INSTALLED IN AN AREA WITH SOIL OF GOOD PERCOLATION. COORDINATE DEPTH OF DRY SUMP w/ SOIL CONDITIONS AND FREE DRAINING SOIL STRATA.



1
AS102

DRY SUMP SECTION

SCALE: 3/4" = 1'-0"

A CONTRACTOR IS TO LOCATE EXISTING WATER LINES AND PROVIDE NEW FIRE SPRINKLER AND CULINARY WATER RISERS IN APPROXIMATE LOCATIONS INDICATED. EXTEND NEW FIRE SPRINKLING LINE OVERHEAD TO PROVIDE SERVICE TO EXISTING FIRE SPRINKLING SYSTEM.
TERMINATE EXISTING SERVICE TO EXISTING FIRE SPRINKLER RISER AND ABANDON EXISTING UNDERGROUND SERVICE IN PLACE.

B CONTRACTOR IS TO LOCATE EXISTING NATURAL GAS SERVICE LINE AND PROVIDE NEW GAS SERVICE AND METER IN APPROXIMATE LOCATION INDICATED. EXTEND NEW GAS SERVICE LINE TO PROVIDE SERVICE TO NEW AND EXISTING MECHANICAL EQUIPMENT.
TERMINATE EXISTING SERVICE TO EXISTING METER AND ABANDON EXISTING UNDERGROUND SERVICE IN PLACE.
COORDINATE NEW SERVICE AND INSTALLATION WITH NATURAL GAS SERVICE PROVIDER.



ABC STORE ADDITION - REDWOOD RD - SITE GRADING PLAN

SCALE: 1" = 20'


0 10' 25' 50'

73 PARKING STALLS

REDWOOD ROAD ABC STORE - REMODEL AND EXPANSION

SITE GRADING AND UTILITY PLANS


FRANK N. MURDOCK JR. ■ Architect & Associates
775 East 100 South Suite 100, Salt Lake City, Utah 84102 TEL: (801) 532-4441 FAX (801) 532-4220




REVISION # DATE:

FCM PROJECT NO.:
06233030
CONST DOC
FILE NAME: ABCR-AS102
PLOT SCALE: 1:240
DRAWN BY: STAFF
CHECKED BY: FNM
DATE: JUNE 2007


AS
102




25 CONCRETE EDGE DETAIL
AS501 SCALE: 1" = 1'-0"




24 CONCRETE MOW STRIP DETAIL
AS501 SCALE: NOT TO SCALE




23 PIPE RAIL ANCHORING DETAIL
AS501 SCALE: NOT TO SCALE



22 DRY SUMP CATCH BASIN
AS501 SCALE: NOT TO SCALE




21 STAIR NOSING SECTION
AS501 SCALE: NOT TO SCALE




20 HANDRAIL MOUNTING DETAIL
AS501 SCALE: NOT TO SCALE


16 NOT USED
AS501 SCALE: NOT TO SCALE




17 CONCRETE CURB DETAIL
AS501 SCALE: NOT TO SCALE




18 DOCK BUMPER SECTION
AS501 SCALE: NOT TO SCALE




19 DOCK BUMPER ELEVATION
AS501 SCALE: NOT TO SCALE




14 BOLLARD DETAIL
AS501 SCALE: 3/4" = 1'-0"




13 EXPANSION JOINT DETAIL (EJ)
AS501 SCALE: 1-1/2" = 1'-0"




12 CONTROL JOINT DETAIL (CJ)
AS501 SCALE: 1-1/2" = 1'-0"




11 CONCRETE SIDEWALK DETAIL
AS501 SCALE: 1" = 1'-0"




5 CONCRETE/ASPHALT EDGE
AS501 SCALE: NOT TO SCALE




6 CURB AND GUTTER DETAIL
AS501 SCALE: NOT TO SCALE




7 CONCRETE CURB DETAIL
AS501 SCALE: 1" = 1'-0"




8 CONCRETE WATERWAY DETAIL
AS501 SCALE: NOT TO SCALE




9 CURB TO SIDEWALK DETAIL
AS501 SCALE: 1-1/2" = 1'-0"




10 PAVEMENT SECTIONS
AS501 SCALE: 3" = 1'-0"



4 EXTERIOR SIGNAGE SUPPORT
AS501 SCALE: 3/4" = 1'-0"






3 PAVEMENT MARKINGS
AS501 SCALE: NOT TO SCALE



2 EXTERIOR TRAFFIC SIGNAGE
AS501 SCALE: NOT TO SCALE

1 NOT USED
AS501 SCALE: NONE

1. PROVIDE SIGNAGE ABOVE ENTRY DOORS STATING "THESE DOORS TO REMAIN UNLOCKED DURING BUSINESS HOURS".
2. PROVIDE SIGNAGE DESIGNATING "PUBLIC RESTROOMS" AT LOCATION TO BE DETERMINED BY ARCHITECT.
3. CONTRACTOR TO PROVIDE AND INSTALL 25 L.F. OF CHAIR RAIL (INPRO CORP., NORTHERN HARDWOODS CR2 OR EQUAL) IN LOCATIONS AND AT HEIGHTS TO BE DETERMINED BY THE ARCHITECT.



REFLECTED CEILING PLAN LEGEND

4' WALL MOUNTED LIGHTING FIXTURE

2' SURFACE MOUNTED LIGHTING FIXTURE

SECURITY LIGHT

2' X 4' FLUORESCENT LIGHTING FIXTURE

RECESSED LIGHTING FIXTURE

8' SUSPENDED LIGHTING FIXTURE

UNIT HEATER

TRACK LIGHT

8' SUSPENDED INDIRECT LIGHTING FIXTURE

WALL MOUNTED LIGHTING FIXTURE

2'X4' SUSPENDED ACOUSTICAL CEILING
PROVIDE SEISMIC BRACING - SEE 1/A102

METAL SOFFIT PANEL

RETURN REGISTER

SUPPLY DIFFUSER

EXHAUST FAN

GYPSUM BOARD SOFFIT

(E.S.) PAINTED EXPOSED STRUCTURE HEIGHT MAY VARY

(MSP) METAL SOFFIT PANEL

(AC) 2'X2' SUSPENDED ACOUSTICAL CEILING

(GB) GYPSUM BOARD CEILING


(SUSGB) SUSPENDED GYPSUM BOARD CEILING






(FMSP) EXTERIOR GYPSUM SOFFET BOARD CEILING UNDER PREFINISHED METAL SOFFET PANEL








(SSS) SYNTHETIC STUCCO SOFFET

(0'-0") CEILING OR SOFFIT HEIGHT (HEIGHT MEASURED FROM FINISHED FLOOR ELEV.: 0'-0")

NOTE: CEILING TO INSTALLED PER SECTION 1621 OT THE 2006 IBC
OR BRACED PER 1997 UBC STANDARDS, SECTION 25-2.












NOTE: OWNER TO PROVIDE AND INSTALL ALL SOAP DISPENSERS, SANITARY NAPKIN DISPOSAL UNIT, PAPER TOWEL DISPENSER AND WASTE UNITS AND TOILET PAPER DISPENSERS.

WALL TYPE
1 BRACE TO ROOF DECK @ 4' O.C.
3 5/8" STUD PARTITION WALL:
PAINTED 5/8" GYP. BD. BOTH SIDES OF 3 5/8" METAL STUDS @ 16" ON CENTER, FROM FLOOR TO ROOF DECK OR TO 6" ABOVE CEILING WHERE CEILING OCCURS. PROVIDE DIAGONAL BRACING TO ROOF DECK @ 4' O.C. WHERE CEILING OCCURS. GYP. BD. @ WALL TO STOP @ GYP. BD. CEILING WHERE OCCURS. PROVIDE TILE WANSKOT AS SHOWN ON PLANS. INSTALL WATER-RESISTANT GYP. BD. @ ALL TOILET ROOMS. PROVIDE PROTECTIVE PARTICLE BOARD WANSKOT AS SHOWN ON FLOOR PLANS, DETAIL 3/A104.

DASHED LINE REPRESENTS PARTICLE BOARD WANSKOT, SEE DETAIL 3/A104.






WEST EXTERIOR ELEVATION

SCALE: 1/8" = 1'-0"

SOUTH EXTERIOR ELEVATION

SCALE: 1/8" = 1'-0"




EAST EXTERIOR ELEVATION

SCALE: 1/8" = 1'-0"

NORTH EXTERIOR ELEVATION

SCALE: 1/8" = 1'-0"




EAST WEST BUILDING SECTION

SCALE: 1/4" = 1'-0"

REDWOOD ROAD ABC STORE - REMODEL AND EXPANSION

DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH


FRANK N MURDOCK JR. ■ Architect & Associates
975 East 100 South Suite 100, Salt Lake City, Utah 84102 TEL: (801) 532-4441 FAX: (801) 532-4220




REVISION # DATE:

DFCM PROJECT NO.:
06233030
CONST DOC
FILE NAME: ABCR-A201
PLOT SCALE: 1:36
DRAWN BY: STAFF
CHECKED BY: FNM
DATE: MAY 2007


A
201



3 WALL SECTION @ EXPANSION JOINT
SCALE: 3/4" = 1'-0"



2 WALL SECTION @ EXPANSION JOINT
SCALE: 3/4" = 1'-0"




1 WALL SECTION @ SCISSOR LIFT
SCALE: 3/4" = 1'-0"

REDWOOD ROAD ABC - REMODEL AND EXPANSION
DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH

WALL SECTIONS AND DETAILS


FRANK N MURDOCK JR ■ Architect & Associates
975 East 100 South, Suite 100, Salt Lake City, Utah 84102 TEL: (801) 332-4441 FAX: (801) 532-4220



REVISION # DATE:


DFCM PROJECT NO.: 06233030
CONSTR DOC
FILE NAME: ABCR-A301
PLOT SCALE: 1:16
DRAWN BY: STAFF
CHECKED BY: FRM
DATE: MAY 2007

**A
301**





FRANK N MURDOCK JR ■ Architect & Associates

975 East 100 South Suite 100, Salt Lake City, Utah 84102 TEL: (801) 532-4441 FAX (801) 532-4220




A
302





REDWOOD ROAD ABC - REMODEL AND EXPANSION

DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH




REVISION # DATE:

DFCM PROJECT NO.:
06233030
CONSTR DOC
FILE NAME: ABCR-A303
PLOT SCALE: 1:16
DRAWN BY: STAFF
CHECKED BY: FNM
DATE: MAY 2007


A
303

WALL SECTIONS AND DETAILS


FRANK N. MURDOCK JR. ■ Architect & Associates
975 East 100 South, Suite 100, Salt Lake City, Utah 84102
TEL: (801) 332-4441 FAX: (801) 532-4220




25 HM Door Head/Transom Sill
SCALE: NOT TO SCALE




24 Storefront Door Head/Transom Sill
SCALE: NOT TO SCALE




23 Storefront Window Sill
SCALE: NOT TO SCALE




22 Storefront Window Sill
SCALE: NOT TO SCALE




21 Storefront Window Head
SCALE: NOT TO SCALE




16 Hollow Metal Window Jamb
SCALE: NOT TO SCALE




17 Hollow Metal Door Jamb
SCALE: NOT TO SCALE




18 Impact Door Jamb/head sim
SCALE: NOT TO SCALE




19 Overhead Door Jamb
SCALE: NOT TO SCALE



20 Hollow Metal or Wood Door (Interior)
SCALE: NOT TO SCALE



15 Storefront Window Mullion
SCALE: NOT TO SCALE




14 Storefront Window Sill
SCALE: NOT TO SCALE




13 Storefront Window Jamb
SCALE: NOT TO SCALE




12 Storefront Window Jamb
SCALE: NOT TO SCALE




11 Storefront Window Jamb
SCALE: NOT TO SCALE




6 Thickset Tile Base
SCALE: NOT TO SCALE




7 Storefront Window Sill
SCALE: NOT TO SCALE




8 Storefront Window Jamb
SCALE: NOT TO SCALE




9 Storefront Window Head
SCALE: NOT TO SCALE




10 Storefront Window Jamb
SCALE: NOT TO SCALE




5 Marble Threshold
SCALE: NOT TO SCALE




4 Door Threshold
SCALE: NOT TO SCALE



3 Concrete to Tile Transition
SCALE: NONE



2 Tile to Floor Mat Detail
SCALE: NONE




1 Door Threshold (entry mat)
SCALE: NOT TO SCALE

NOT USED


NOT USED

NOT USED

NOT USED




13 STAIR NOSING DETAIL
SCALE: 3" = 1'-0"




NOTE:
1. INSTALLATION MUST WITHSTAND 250 LB. FORCE IN ANY DIRECTION.

8 GRAB BAR DETAIL
SCALE: 3" = 1'-0"




NOTES:
1. FOR FIRE EXTINGUISHERS IN THE WORKROOM, A RED BACKGROUND MUST BE PROVIDED WHICH EXTENDS SIX INCHES ON THE SIDES AND BELOW THE FIRE EXTINGUISHERS OR CABINETS. THE RED BACKGROUND MUST BE EXTENDED ABOVE THE FIRE EXTINGUISHER TO A HEIGHT OF 12 FEET ABOVE THE FINISHED FLOOR OR TO THE CEILING IF THE ROOM IS LESS THAN 12 FEET IN HEIGHT.
2. LOCATE SAFETY EQUIPMENT AT THE HEIGHT RECOMMENDED BY OSHA AND ON THE MOST ACCESSIBLE FACE.


3 FIRE EXTINGUISHER IDENTIFICATION
SCALE: NONE




12 UPPER CABINET SECTION
SCALE: NOT TO SCALE




9 LOCKER ROOM BENCH
SCALE: 3" = 1'-0"



2 CONCRETE REVEAL
SCALE: NONE



11 SINK CABINET SECTION
SCALE: NOT TO SCALE




10 BASE CABINET SECTION
SCALE: NOT TO SCALE

NOT USED

REDWOOD ROAD ABC STORE - REMODEL AND EXPANSION

DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
3381 SOUTH REDWOOD ROAD, WEST VALLEY CITY, UTAH

FRANK N MURDOCK JR ■ Architect & Associates
1715 East 100 South Suite 100 Salt Lake City, Utah 84107 TEL: (801) 532-4441 FAX: (801) 532-4220



REVISION # DATE:

DFCM PROJECT NO.:
06233030
CONSTR. DOC.
FILE NAME: ABCR-A502
PLOT SCALE: 3/12
DRAWN BY: STAFF
CHECKED BY: FRANK
DATE: MAY 2007

A
502

X:\Project Files\2020\06box.DWG RedwoodDrawings\8001.dwg, 3/6/22, 6/6/2007 8:25:34 AM

STRUCTURAL NOTES

STRUCTURAL DESIGN LOADS

ROOF:		
DEAD LOAD:	DL = 25 PSF	
GROUND SNOW LOAD:	Pg = 30 PSF	
FLAT ROOF SNOW LOAD:	Pf = 43 PSF	
SNOW EXPOSURE FACTOR:	Ce = 1.0	
SNOW IMPORTANCE FACTOR:	I = 1.0	
THERMAL FACTOR:	Ct = 1.0	
WIND LOAD:		
BASIC WIND SPEED:	V = 90 MPH (3 SEC GUST)	
IMPORTANCE FACTOR:	I = 1.0	
WIND EXPOSURE:	C = "c"	
COMPONENT AND CLADDING PRESSURE:	P = 25 PSF	
SEISMIC:		
USE GROUP:	I	
SPECTRAL RESPONSE COEF:	SDS = 1.081, SD1 = 0.639	
SITE CLASS:	D	
BASIC SEISMIC-FORCE-RESISTING SYSTEM:		
SPECIAL REINFORCED MASONRY SHEAR WALLS	R=5, OMEGA=2.5, Cd=3.5, Cw=0.116	
SOILS:		
NET ALLOWABLE SOIL PRESSURE = 1500 PSF		
TO BE FIELD VERIFIED		

GENERAL

- ALL DESIGN, CONSTRUCTION, AND INSPECTION SHALL BE IN CONFORMANCE WITH THE 2006 INTERNATIONAL BUILDING CODE.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AT THE SITE.
- ALL OMISSIONS OR CONFLICTS BETWEEN THE VARIOUS ELEMENTS OF THE WORKING DRAWINGS AND/OR SPECIFICATIONS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AND/OR STRUCTURAL ENGINEER BEFORE PROCEEDING WITH ANY WORK INVOLVED.
- DRAWINGS INDICATE THE FINISHED PRODUCT. THEY DO NOT INDICATE A METHOD OF CONSTRUCTION. CONTRACTOR SHALL TAKE ALL PRECAUTIONS NECESSARY TO PROTECT THE STRUCTURE DURING CONSTRUCTION. SUCH PRECAUTIONS SHALL INCLUDE, BUT NOT BE LIMITED TO, BRACING, SHORING FOR CONSTRUCTION EQUIPMENT, ETC.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPENSATING THE OWNER FOR ANY CHANGES MADE AS A RESULT OF A DEVIATION FROM THE CONTRACT DOCUMENTS, DEVIATION FROM THE SPECIFICATIONS, FAULTY MATERIALS, OR FAULTY WORKMANSHIP.
- OPTIONS ARE FOR THE CONTRACTORS CONVENIENCE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL REQUIRED DESIGN CHANGES. COST ASSOCIATED WITH ANY DESIGN WORK INITIATED BY THE OPTION SHALL BE BORN BY THE CONTRACTOR.
- CONTRACTOR SHALL BE RESPONSIBLE FOR SAFETY AND PROTECTION WITHIN AND ADJACENT TO THE JOB SITE.
- TEMPORARY SHORING AND BRACING SHALL BE PROVIDED WHEREVER NECESSARY TO TAKE CARE OF ALL LOADS TO WHICH THE STRUCTURE MAY BE SUBJECTED INCLUDING WIND. SUCH BRACING SHALL BE LEFT IN PLACE AS LONG AS MAY BE REQUIRED FOR SAFETY OR UNTIL ALL THE STRUCTURAL ELEMENTS ARE COMPLETE.
- DURING AND AFTER CONSTRUCTION THE CONTRACTOR AND/OR OWNER SHALL KEEP LOADS ON THE STRUCTURE WITHIN THE LIMITS OF THE DESIGN LOADS.
- THE GENERAL CONTRACTOR SHALL HAVE SHOP DRAWINGS REVIEWED BY THE ARCHITECT PRIOR TO THE FABRICATION OR ERECTION FOR THE FOLLOWING ITEMS: REINFORCING STEEL, STRUCTURAL STEEL, MISCELLANEOUS METALS, PREFABRICATED WOOD JOISTS, PREFABRICATED STEEL JOISTS, PREFABRICATED WOOD TRUSSES AND GLU-LAM BEAMS.
- ALL DETAILS, SECTIONS, AND NOTES ARE INTENDED TO BE TYPICAL AND SHALL APPLY TO SIMILAR SITUATIONS UNLESS NOTED OR SHOWN OTHERWISE.
- REFER TO THE SPECIFICATIONS FOR ADDITIONAL INFORMATION NOT COVERED ON THE DRAWINGS.
- OBSERVATION VISITS TO THE JOB SITE BY FIELD REPRESENTATIVES OF CALDER RICHARDS CONSULTING ENGINEERS SHALL NEITHER BE CONSTRUED AS INSPECTION NOR APPROVAL OF CONSTRUCTION.
- SIZES, LOCATIONS, AND ANCHORAGES OF EQUIPMENT SHALL BE VERIFIED IN THE FIELD WITH EQUIPMENT MANUFACTURERS (SUPPLIERS) PRIOR TO PLACING CONCRETE OR FABRICATING STEEL.

QUALITY ASSURANCE PLAN

- SPECIAL INSPECTION SHALL BE PROVIDED BY THE OWNER ACCORDING TO IBC CHAPTER 17 FOR THE ITEMS IDENTIFIED IN THIS SECTION AND ON THE CONTRACT DOCUMENTS.
- THE NAMES AND CREDENTIALS OF SPECIAL INSPECTORS TO BE USED SHALL BE SUBMITTED TO THE BUILDING DEPARTMENT WHEN APPLYING FOR A BUILDING PERMIT.
- SPECIAL INSPECTION REPORTS SHALL BE DELIVERED TO THE ENGINEER OF RECORD, ARCHITECT, AND OWNER (AS REQUESTED) BI-WEEKLY OR MORE FREQUENTLY AS REQUIRED BY THE INSPECTOR OR BUILDING OFFICIAL.
- OFF-SITE FABRICATION: WHERE FABRICATION OF STRUCTURAL LOAD-BEARING MEMBERS AND ASSEMBLIES IS BEING PERFORMED ON THE PREMISES OF A FABRICATORS SHOP, SPECIAL INSPECTION OF THE FABRICATED ITEMS SHALL BE IN ACCORDANCE WITH IBC SECTION 1704.2 UNLESS THE FABRICATOR IS APPROVED ACCORDING TO IBC SECTION 1704.2.2.
- STEEL CONSTRUCTION: SPECIAL INSPECTIONS FOR STEEL ELEMENTS SHALL BE PROVIDED IN ACCORDANCE WITH SECTIONS 1704.3 AND TABLE 1704.3.
- WELDING: WELDING INSPECTION SHALL BE PROVIDED IN ACCORDANCE WITH TABLE 1704.3. ELEMENTS THAT ARE PART OF THE SEISMIC-FORCE-RESISTING SYSTEM SHALL ALSO BE INSPECTED ACCORDING TO SECTION 1707.2 AND 1708.4.

QUALITY ASSURANCE PLAN

- HIGH-STRENGTH BOLTS: PERIODIC SPECIAL INSPECTION SHALL BE PROVIDED FOR INSTALLATION OF HIGH-STRENGTH BOLTS IN ACCORDANCE WITH AISC SPECIFICATIONS. SEE IBC SECTION 1704.3.3.
- CONCRETE CONSTRUCTION: SPECIAL INSPECTIONS AND VERIFICATIONS SHALL BE PROVIDED IN ACCORDANCE WITH TABLE 1704.4.
- MASONRY CONSTRUCTION: LEVEL 1 SPECIAL INSPECTION SHALL BE PROVIDED FOR MASONRY CONSTRUCTION IN ACCORDANCE WITH SECTION 1704.5.2 AND TABLE 1704.5.1. TESTING SHALL COMPLY WITH SECTION 1708.1.3
- COLD-FORMED STEEL FRAMING: CONNECTIONS OF ELEMENTS IN THE SEISMIC-FORCE-RESISTING SYSTEM IN ACCORDANCE WITH SECTION 1707.4.
- SOILS: SPECIAL INSPECTION SHALL BE PROVIDED FOR PLACEMENT OF FILL 12 INCHES OR MORE DEEP IN ACCORDANCE WITH SECTION 1704.7.
- EPOXY ANCHORS: PRIOR TO AND DURING EPOXY INJECTION TO INSURE PROPER INSTALLATION AS PER MANUFACTURERS REQUIREMENTS. CONTRACTOR SHALL SUBMIT PROPOSED EPOXY MANUFACTURERS ICBO REPORT TO STRUCTURAL ENGINEER PRIOR TO INSTALLATION.

QUALITY ASSURANCE - CONTRACTOR RESPONSIBILITY

- EACH CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF A SEISMIC-FORCE-RESISTING SYSTEM, DESIGNATED SEISMIC SYSTEM, OR COMPONENT LISTED IN THE QUALITY ASSURANCE PLAN SHALL SUBMIT A WRITTEN CONTRACTOR'S STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND TO THE OWNER PRIOR TO THE COMMENCEMENT OF WORK ON THE SYSTEM OR COMPONENT. THE CONTRACTOR'S STATEMENT OF RESPONSIBILITY SHALL CONTAIN THE FOLLOWING:
 - ACKNOWLEDGMENT OF AWARENESS OF THE SPECIAL REQUIREMENTS CONTAINED IN THE QUALITY ASSURANCE PLAN.
 - ACKNOWLEDGMENT THAT CONTROL WILL BE EXERCISED TO PROTECTED AS DIRECTED BY THE SPECIFICATIONS AND ACI STANDARDS AND PRACTICES.
 - PROCEDURES FOR EXERCISING CONTROL WITHIN THE CONTRACTOR'S ORGANIZATION, THE METHOD AND FREQUENCY OF REPORTING, AND THE DISTRIBUTION OF REPORTS.
 - IDENTIFICATION AND QUALIFICATIONS OF THE PERSON(S) EXERCISING SUCH CONTROL AND THE POSITION(S) IN THE ORGANIZATION.

STRUCTURAL DEFERRED SUBMITTALS

- CONTRACTOR SHALL SUBMIT DRAWINGS AND CALCULATIONS BEARING THE SEAL OF A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF THE PROJECT TO ARCHITECT/ENGINEER BEFORE SUBMITTING TO JURISDICTION FOR REVIEW AND PERMITTING. ITEMS:
 - OPEN WEB METAL JOISTS AND GIRDERS
 - CONCRETE MIX DESIGN
 - DESIGN-BUILD STAIRS
 - ATTACHMENT OF MECHANICAL UNIT TO SUPPORT

FOOTINGS

- ALL FOOTINGS SHALL BEAR 12" MINIMUM INTO ORIGINAL UNDISTURBED EARTH OR ON ENGINEERED FILL COMPACTED TO 95% OF MAXIMUM RELATIVE DENSITY BASED ON ASTM D1557-91. SUCH FILL SHALL BE PLACED IN LAYERS NOT TO EXCEED 6" IN DEPTH AFTER COMPACTION AND SHALL EXTEND DOWN TO IN-SITU GRANULAR SOILS.
- FOOTING ELEVATIONS SHOWN ON PLAN ARE TOP OF FOOTINGS AND ARE MINIMUM DEPTH. DIFFERENT OR UNUSUAL CONDITIONS SHALL BE REPORTED TO THE ARCHITECT AND/OR ENGINEER.
- EXTERIOR WALL FOOTINGS SHALL BEAR AT A MINIMUM DEPTH OF 2'-6" BELOW FINISHED EXTERIOR GRADE.
- NO FOOTINGS SHALL BE PLACED IN WATER OR ON FROZEN GROUND.
- ANY SOIL CONDITION ENCOUNTERED DURING EXCAVATION THAT IS CONTRARY TO THE CONDITIONS USED FOR DESIGN OF FOOTINGS AS OUTLINED ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT AND ENGINEER BEFORE PROCEEDING.
- DO NOT BACK FILL BEHIND FOUNDATION WALLS UNTIL TOP AND BOTTOM SLABS HAVE BEEN POURED AND ATTAINED THEIR DESIGN STRENGTHS.
- BACK FILL BOTH SIDES OF FOUNDATION WALLS AT SAME TIME TO PREVENT OVERTURNING.
- WHERE 6" DIAMETER OR LARGER PIPE PASSES THROUGH AN INTERIOR OR EXTERIOR FOUNDATION WALL, STEP THE FOOTING DOWN TO PASS BELOW PIPE AND THEN STEP BACK UP TO INDICATED ELEVATION. PROVIDE PIPE SLEEVE THROUGH FOUNDATION WALL.
- ALL FOOTING EXCAVATIONS SHALL BE EXAMINED BY A GEOTECHNICAL ENGINEER FOR VERIFICATION OF ADEQUATE BEARING CONDITIONS BEFORE PLACING CONCRETE.

REINFORCING STEEL

- ALL REINFORCEMENT SHALL BE DETAILED AND PLACED IN ACCORDANCE WITH ACI DETAILING MANUAL 315-92 AND ACI STANDARD 318-02.
- REINFORCING STEEL SHALL BE ASTM A615 GRADE 60.
- WELDED WIRE FABRIC SHALL CONFORM TO ASTM A185. LAP ONE MESH TIE.
- ALL REINFORCEMENT SHALL BE SECURELY TIED AND HELD IN PLACE.

REINFORCING STEEL

- REINFORCING BARS THAT ARE TO BE WELDED, INCLUDING DEFORMED BAR ANCHORS (DBA) SHALL COMPLY WITH ASTM A706 OR ANOTHER WELDABLE GRADE AND SHALL BE WELDED IN ACCORDANCE WITH THE AWS RECOMMENDATIONS.
- ALL CONTINUOUS REINFORCEMENT SHALL TERMINATE WITH A 90 DEGREE TURN OR A SEPARATE CORNER BAR. ALL SPLICE SHALL HAVE A MINIMUM LAP OR EMBEDMENT PER REINFORCING SCHEDULE.
- WHERE THE LENGTH OF A BAR IS GIVEN AND IT IS TO BE HOOKED, THE HOOK SHALL BE IN ADDITION TO THE LENGTH GIVEN, UNLESS SHOWN OTHERWISE.
- COVER TO MAIN REINFORCEMENT FROM ADJACENT SURFACES SHALL BE AS FOLLOWS UNLESS SHOWN OTHERWISE:
 - UNFORMED SURFACES IN CONTACT WITH GROUND OR EXPOSED TO THE WEATHER (BOTTOM OF FOOTINGS). 3"
 - SLABS ON GRADE..... 2"
 - FORMED SURFACES IN CONTACT WITH GROUND OR EXPOSED TO THE WEATHER (GRADE BMS, WALLS, ETC) BEAMS AND COLUMNS..... 2"
 - STRUCTURAL SLABS AND JOISTS NOT EXPOSED TO WEATHER OR EARTH..... 1"
 - INTERIOR WALL SURFACES..... 1"
 - INTERIOR BEAMS AND COLUMNS..... 1-1/2"
 - IN ALL CASES MINIMUM COVER SHALL NOT BE LESS THAN THE DIAMETER OF ADJACENT BARS.
- PRIOR TO FABRICATION AND PLACEMENT, SHOP DRAWINGS FOR ALL REINFORCING STEEL SHALL BE REVIEWED BY THE STRUCTURAL ENGINEER.

CONCRETE

- CONCRETE SHALL ATTAIN THE FOLLOWING MINIMUM COMPRESSIVE STRENGTHS AT 28 DAYS:
 - FOOTINGS & FOUNDATION WALLS..... 3000 PSI
 - INTERIOR SLABS ON GRADE..... 4000 PSI
 - EXTERIOR FLAT WORK..... 4000 PSI
- A STATEMENT OF MIX DESIGN FOR ALL CONCRETE SHALL BE SUBMITTED TO AND REVIEWED BY THE STRUCTURAL ENGINEER PRIOR TO COMMENCING WORK.
- ALL CONCRETE WORK SHALL BE PLACED, CURED, STRIPPED, AND PROTECTED AS DIRECTED BY THE SPECIFICATIONS AND ACI STANDARDS AND PRACTICES.
- UNLESS NOTED OTHERWISE ON THE DRAWINGS, REINFORCE CONCRETE WALLS AS FOLLOWS:

WIDTH	HORIZ REINF	VERT REINF
8" WALL	#5 @ 12"	#5 @ 16" CENTER OF WALL
- DOWEL VERTICAL BARS 36 DIAMETERS INTO STRUCTURE ABOVE AND FOOTINGS BELOW. PROVIDE 90 DEGREE HOOK WHERE 36 DIAMETER IS NOT POSSIBLE. IN ADDITION, PROVIDE (2) #5 CONTINUOUS BARS TOP AND BOTTOM OF 6" AND 8" WALLS AND (2) #6 BARS TOP AND BOTTOM OF WALLS 10" OR THICKER.
- BEFORE CONCRETE IS POURED CHECK WITH ALL TRADES TO ENSURE PROPER PLACEMENT OF ALL OPENINGS, SLEEVES, CURBS, CONDUITS, BOLTS, INSERTS, ETC. RELATIVE TO WORK.
- ADD (2) #5 BARS MINIMUM AROUND ALL OPENINGS (UNLESS OTHERWISE NOTED) AND EXTEND 24" BEYOND CORNER OF OPENING.
- WHERE OPENINGS LARGER THAN 16" IN ANY DIRECTION OCCUR IN WALLS OR SLABS, PROVIDE SAME SIZE ADDITIONAL, FULL LENGTH REINFORCING AT EACH SIDE OF OPENING EQUAL TO 1/2 THE NUMBER OF BARS INTERRUPTED BY THE OPENING. SPACE ADDITIONAL BARS AT 4 x BAR DIAMETER.
- ALL SLABS ON GRADE SHALL BE PLACED IN ALTERNATE PANELS WITH A MAXIMUM WIDTH OF 20' BETWEEN CONTROL OR CONSTRUCTION JOINTS; REFER TO TYPICAL DETAILS ON DRAWINGS. UNLESS OTHERWISE NOTED, SLABS ON GRADE SHALL BE 4" THICK AND SHALL BE REINFORCED WITH 6x6-W1.4xW1.4 WELDED WIRE FABRIC.
- REFER TO DRAWINGS FOR TYPICAL CONSTRUCTION JOINT DETAILS. UNLESS NOTED IN DRAWINGS, ALL REINFORCEMENT SHALL BE CONTINUOUS THRU JOINTS AND EACH CONSTRUCTION JOINT SHALL BE KEYS.
- FORMS, SCREEDS, AND BEAMS SUPPORTING SUSPENDED CONCRETE SHALL BE CAMBERED 1/4 INCH PER 10 FEET OF SPAN TO COMPENSATE FOR DEAD LOAD DEFLECTIONS.
- WHERE EXTERIOR SLABS ON GRADE ABUT WALLS OR COLUMNS PROVIDE 3/8" PREFORMED EXPANSION JOINT WITH SEALANT.

MASONRY (CMU)

- ALL MASONRY SHALL BE REINFORCED WITH BOTH HORIZONTAL AND VERTICAL REINFORCEMENT. ALL BLOCK CELLS OR BRICK CAVITIES WITH REINFORCEMENT SHALL BE GROUTED FULL USING CONCRETE 2000 PSI GROUT. CELLS SHALL BE ALIGNED TO PRESERVE UNOBSTRUCTED VERTICAL CAVITIES OF 2"x3" MINIMUM.
- CONCRETE FOR BLOCK FILL SHALL HAVE 3/8" MAXIMUM SIZE COURSE AGGREGATE AND SUFFICIENT WATER SO THE CONCRETE WILL FLOW INTO THE BLOCK CELLS WITHOUT LEAVING VOIDS. WHERE BEAMS BEAR ON CONCRETE BLOCK WALLS, BLOCK CELLS SHALL BE FILLED WITH CONCRETE 1'-4" WIDE TO FOUNDATION AND REINFORCE WITH A #6 EACH CELL, UNLESS OTHERWISE SHOWN.
- AN ADDITIONAL VERTICAL BAR (MATCHING WALL REINFORCEMENT) SHALL BE PLACED AT EACH CORNER, END OF WALL, AND JAMB OF ALL OPENINGS.
- ALL STEEL JOIST, JOIST GIRDER, AND STEEL BEAM POCKETS IN MASONRY SHALL BE GROUTED SOLID UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- HORIZONTAL BARS SHALL BE PLACED IN BOND BEAMS FILLED WITH GROUT AT THE TOP OF ALL WALLS AND AT 48" OC MAXIMUM BETWEEN TOP OF WALL AND FOUNDATION. BOND BEAM UNITS AND REINFORCING SHALL CONTINUE UNINTERRUPTED AROUND ALL CORNERS AND WALL INTERSECTIONS. WHERE STRUCTURAL STEEL COLUMNS OR BEAMS INTERRUPT THE CONTINUITY OF A BOND BEAM, DOWELS MATCHING BOND BEAM REINFORCEMENT SHALL BE WELDED TO THE STRUCTURAL STEEL TO PROVIDE CONTINUITY.

MASONRY (CMU)

- ALL VERTICAL REINFORCING BARS SHALL BE DOWELED TO STRUCTURE BELOW WITH BARS OF SAME SIZE AND SPACING. LAP ALL SPLICES IN MASONRY PER REBAR SCHEDULE. PLACE ALL BARS SECURELY PRIOR TO GROUTING.
- MASONRY REINFORCEMENT: THE MINIMUM REINFORCEMENT IN GROUTED CELLS FOR ALL MASONRY WALLS SHALL BE AS FOLLOWS:

8" WALLS:	#5 @ 32" OC VERTICAL AND
(2) #4 @ 48" OC HORIZONTAL	
- ALL HORIZONTAL REINFORCING SHALL TERMINATE WITH A HOOK AROUND VERTICAL REINFORCING.
- IN ADDITION LADDER-TYPE REINFORCING CONSISTING OF #9 WIRE FOR EACH FACE SHELL OF EACH WYTHE SHALL BE USED AT 16" OC HORIZONTALLY IN ALL MASONRY WALLS. REINFORCEMENT SHALL BE FOR TOTAL WIDTH OF CAVITY WALLS.
- CONCRETE MASONRY UNITS SHALL BE GRADE N UNITS CONFORMING TO ASTM DESIGNATION C80 AND SHALL HAVE A MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF 1900 PSI ON THE NET SECTION.
- MORTAR SHALL BE TYPE "S" AND SHALL HAVE THE FOLLOWING PROPORTIONS BY VOLUMES:

PORTLAND CEMENT.....	1 PART
HYDRATED LIME.....	1/4 - 1/2 PART
DAMP LOOSE AGGREGATE...	NOT LESS THAN 1-1/4 AND NOT MORE THAN (3) TIMES THE SUM OF CEMENT AND LIME USED.
- STOP GROUT POURS 1/2" BELOW TOP OF BLOCK UNITS.
- ALL ANCHOR BOLTS MUST BE PLACED IN GROUTED CELLS.
- NO MASONRY SHALL BE LAID WHEN THE TEMPERATURE OF THE OUTSIDE AIR IS BELOW 40 DEGREES FAHRENHEIT. UNLESS APPROVED METHODS ARE USED DURING CONSTRUCTION TO PREVENT DAMAGE TO THE MASONRY. SUCH METHODS SHALL INCLUDE PROTECTION OF THE MASONRY FOR A PERIOD OF AT LEAST 48 HOURS.
- ALL REINFORCING SHALL BE IN PLACE PRIOR TO GROUTING. VERTICAL REINFORCING BARS SHALL BE HELD IN POSITION AT THE TOP, BOTTOM AND AT INTERVALS NOT FARTHER APART THAN 200 BAR DIAMETERS. PROVIDE WIRE TIES AT ALL LAP SPLICES.
- ALL MASONRY WALLS SHALL HAVE VERTICAL CONTROL JOINTS AT: MAJOR CHANGES IN WALL HEIGHT, AT CHANGES IN WALL THICKNESS, AT BUILDING CONSTRUCTION JOINTS, AND NOT FARTHER APART THAN 40 FEET ELSEWHERE. PROVIDE MATCHING CONTROL JOINTS FOR BRICK VENEER. CONSULT ARCHITECTURAL DRAWINGS FOR LOCATIONS. VERTICAL CELLS EACH SIDE OF CONTROL JOINTS SHALL BE GROUTED AND REINFORCED WITH REBARS TO MATCH VERTICAL REINFORCEMENT USED THROUGHOUT THAT WALL. ONLY THE TOP PORTION OF THE WALL SHALL BE ON FLOORS AND AT ROOF LEVEL SHALL CONTINUE THROUGH CONTROL JOINTS. PROVIDE FULL HEIGHT HARD RUBBER KEY AT JOINT. WHERE JOINT LOCATIONS ARE NOT SHOWN ON THE DRAWINGS THE CONTRACTOR SHALL SUBMIT PROPOSED LOCATIONS TO ARCHITECT/ENGINEER FOR REVIEW.

STRUCTURAL STEEL

- ALL STRUCTURAL STEEL AND STRUCTURAL STEEL WORK SHALL COMPLY WITH BOTH THE AISC "MANUAL OF STEEL CONSTRUCTION" CONTAINING THE SPECIFICATIONS FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL BUILDINGS, INCLUDING THE "CODE OF STANDARD PRACTICES" (LATEST EDITION), AND WITH THE AISI 2003 EDITION.
- ALL WIDE FLANGE STRUCTURAL STEEL SHALL BE ASTM A992 AND ALL MISCELLANEOUS SHAPES SHALL BE ASTM A36, UNO.
- STRUCTURAL STEEL TUBING SHALL CONFORM TO ASTM A500 GRADE B; YIELD STRESS = 46 KSI.
- STRUCTURAL STEEL PIPE COLUMNS SHALL CONFORM TO ASTM A501, GRADE B; YIELD STRESS = 35 KSI.
- USE A325 BOLTS FOR STEEL TO STEEL CONNECTIONS AND A307 BOLTS FOR ALL OTHER CONNECTIONS. USE 3/4" DIAMETER MINIMUM.
- PRIOR TO FABRICATION AND ERECTION, SHOP DRAWINGS FOR ALL STEEL ITEMS SHALL BE REVIEWED BY THE STRUCTURAL ENGINEER. THE CONTRACTOR SHALL VERIFY ALL SHOP DRAWING DIMENSIONS WITH STRUCTURAL AND ARCHITECTURAL PLANS AND DETAILS.
- ALL WELDS SHALL BE MADE WITH E70XX ELECTRODES AND BY WELDERS CERTIFIED BY AWS STANDARDS WITHIN THE PAST 12 MONTHS; PROVIDE WRITTEN CERTIFICATION IF REQUESTED.
- ALL HIGH-STRENGTH BOLTS SHALL BE TIGHTENED TO THE APPROPRIATE MINIMUM BOLT TENSION IN ACCORDANCE WITH "AISC SPECIFICATIONS FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS". THE PREFERRED METHOD OF TIGHTENING IS BY USE OF A "DIRECT TENSION INDICATOR." THE TURN-OF-NUT METHOD MAY ALSO BE USED. PROVIDE CARBONIZED WASHERS UNDER THE TURNED ELEMENT.
- ALL STEEL JOISTS, JOIST GIRDERS, AND ASSOCIATED WORK SHALL COMPLY WITH THE LATEST EDITION OF THE STANDARD SPECIFICATIONS OF THE STEEL JOIST INSTITUTE". UNLESS SHOWN OTHERWISE, PROVIDE BRIDGING IN ACCORDANCE WITH THIS SPECIFICATION AS A MINIMUM. JOIST FABRICATOR SHALL BE A MEMBER OF THE STEEL JOIST INSTITUTE (SJI). JOISTS SHALL BE DESIGNED BY A PROFESSIONAL ENGINEER, REGISTERED IN THE STATE OF THE PROJECT AND HE SHALL SEAL AND SIGN ALL DESIGN CALCULATIONS AND JOISTS SHOP DRAWINGS. DESIGN SHALL COMPLY WITH ALL LOADING REQUIREMENTS INDICATED ON THE DRAWINGS AND NOTES. DESIGN CALCULATIONS AND SHOP DRAWINGS SHALL CLEARLY INDICATE ALL LOADINGS, DIMENSIONS, MEMBER FORCES, REACTIONS, MEMBER SIZES, WELD REQUIREMENTS AND JOINT DETAILS. JOISTS SHALL BE DESIGNED ASSUMING HORIZONTAL MOVEMENT IS ALLOWED AT ONE END, UNLESS NOTED OTHERWISE.
- ALL BRIDGING SHALL BE SECURELY ANCHORED AT END OF EACH RUN. WELD TO STEEL BEAM OR ANCHOR TO MASONRY WALL WITH 3/8" ANCHOR BOLTS.
- WHERE JOISTS CAN NOT BEAR 2-1/2" ON STEEL BEAMS, STAGGER LOCATION OF JOISTS TO PROVIDE 2-1/2" MINIMUM BEARING ON BEAM.
- CONCENTRATED LOADS SHALL NOT BE PLACED ON NOR HUNG FROM JOISTS UNLESS THEY ARE PLACED AT PANEL POINTS OR A BRACE (L1=1/2xL1-1/2x1/8) IS INSTALLED BETWEEN THE LOAD AND PANEL POINT. CONCENTRATED LOADS NOT SHOWN ON THE DRAWINGS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT/ENGINEER FOR REVIEW.


STRUCTURAL STEEL

- OPEN WEB ROOF JOISTS AND GIRDERS SHALL BE DESIGNED FOR A NET WIND UPLIFT OF 10 PSF, UNLESS NOTED OTHERWISE.
- OPEN WEB ROOF JOISTS AND GIRDERS SHALL BE DESIGNED FOR THE FOLLOWING DEFLECTION LIMITS:

LIVE OR SNOW LOAD	SPAN/360
TOTAL LOAD	SPAN/240
- PROVIDE CAMBER IN OPEN WEB JOIST AND GIRDER PER STEEL JOIST INSTITUTE RECOMMENDATIONS, UNLESS NOTED OTHERWISE.
- JOIST MANUFACTURER TO DESIGN JOIST TOP CHORD WITH UNBRACED LENGTH EQUAL TO SKYLIGHT OPENING.
- WHERE STEEL JOIST OR GIRDER SLOPE EXCEEDS 1/4" PER FOOT, PROVIDE SLOPED BEARING SEAT.
- THE STEEL JOIST AND GIRDER MANUFACTURER SHALL SUBMIT ERECTION DRAWINGS AND STAMPED CALCULATIONS BY A LICENSED CIVIL OR STRUCTURAL ENGINEER TO THE ENGINEER OF RECORD FOR REVIEW.
- JOISTS SHALL BE DESIGNED FOR AN ADDITIONAL 500 LBS CONCENTRATED LOAD AT ANY ONE PANEL POINT.
- GIRDERS SHALL BE DESIGNED FOR AN ADDITIONAL 1000 LBS CONCENTRATED LOAD AT ANY ONE PANEL POINT.
- JOIST MANUFACTURER TO DESIGN FOR THE MECHANICAL UNITS SHOWN WITH WEIGHTS GREATER THAN 500 LBS.
- SPECIAL INSPECTIONS AND TESTING OF WELDS AS REQUIRED BY IBC 2006 SHALL BE PROVIDED BY THE OWNER.
- MECHANICAL ROOF TOP UNITS SHALL BE PLACED OVER ADDITIONAL OR SPECIAL JOISTS AS SHOWN ON DRAWINGS. THE WEIGHT, SIZE AND LOCATION OF ALL PROPOSED UNITS AND CURBS SHALL BE SUBMITTED TO THE ARCHITECT/ENGINEER FOR VERIFICATION BEFORE FABRICATION OF STEEL.
- FRAMES FOR ROOF OPENINGS AND SUPPORTS FOR ROOF MOUNTED MECHANICAL EQUIPMENT ARE INDICATED ON DRAWINGS FOR BID PURPOSES ONLY. UPON RECEIPT OF MECHANICAL SUBMITTALS, THE CONTRACTOR SHALL FURNISH STEEL SUPPLIER SUPPLEMENTARY DRAWINGS OR OTHER INFORMATION NECESSARY TO LAYOUT AND DETAIL THIS PORTION OF THE WORK. OTHER STEEL WORK SHALL NOT BE DELAYED BY THIS PORTION OF THE WORK. SHOP DRAWINGS SHALL BE SUBMITTED TO ENGINEER FOR REVIEW.
- STEEL ROOF DECK SHALL COMPLY WITH THE LATEST REQUIREMENTS OF THE STEEL DECK INSTITUTE, SD1. SUBMIT ICBO REPORT WITH SHOP DRAWINGS.
- WHERE POSSIBLE, ALL DECK SHALL BE (3) SPAN CONTINUOUS MINIMUM. IN AREAS WHERE (3) SPAN CONDITIONS ARE NOT POSSIBLE, THE DECK SHALL MEET THE MINIMUM REQUIREMENTS FOR THE SPAN CONDITION. THE CONTRACTOR SHALL PROVIDE HEAVIER GAGE DECK AND/OR SHORING AS REQUIRED.
- DECK SHALL HAVE A MINIMUM BEARING LENGTH OF 2".


LIGHT GAGE METAL FRAMING

- DESIGN, FABRICATION AND ERECTION OF LIGHT-GAGE METAL FRAMING SHALL COMPLY WITH REQUIREMENTS OF: AISC "MANUAL OF STEEL CONSTRUCTION", AWS "STRUCTURAL WELDING CODE", AISI "SPECIFICATION FOR THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS", AND ICBO REPORT ER-4943P.
- FRAMING SHOWN ON PLANS ARE MINIMUM SIZES AND CONDITIONS. SUBSTITUTION OF FRAMING MEMBERS SHALL BE APPROVED BY ARCHITECT AND ENGINEERS. THEY SHALL HAVE CAPACITY FOR GRAVITY LOADS AND LATERAL LOADS EQUAL TO OR BETTER THAN SPECIFIED FRAMING MEMBERS AND SHALL BE ICBO APPROVED.
- ALL COMPONENTS SHALL BE GALVANIZED ACCORDING TO REQUIREMENTS OF ASTM A-525 FOR MINIMUM G-60 COATING.
- ALL 16 AND 18 GAGE STUDS, AND ALL TRUCK, BRIDGING, END CLOSURES AND ACCESSORIES SHALL BE FORMED FROM STEEL THAT CORRESPONDS TO THE MINIMUM REQUIREMENTS OF ASTM A-446, WITH A MINIMUM YIELD OF 33 KSI FOR 18 GAGE AND 50 KSI FOR 16 GAGE. FOR STUDS AND 33 KSI FOR RUNNERS, BRIDGING, END CLOSURES AND ACCESSORIES.
- ALL WELDS SHALL BE ACCOMPLISHED USING 1/8" AWS TYPE 6013 OR 7014 ROD WITH A WELDING HEAT OF 60 TO 110 AMPERES DEPENDING ON THE GAGE OF MATERIAL AND THE FIT OF THE PARTS. WIRE TYING OF FRAMING COMPONENTS IS NOT PERMITTED.
- ADEQUATE LATERAL BRACING MUST BE PROVIDED DURING CONSTRUCTION.
- UNLESS NOTED OTHERWISE, METAL FRAMING MEMBERS AT LOAD BEARING, SHEAR WALLS AND EXTERIOR WALLS SHALL BE 18 GAGE FOR STUDS, 16 GAGE FOR TOP AND BOTTOM RUNNER. 16 GAGE FOR STUDS AT HOLD DOWNS.
- RUNNER TRACKS: INSTALL CONTINUOUS TRACKS SIZED TO MATCH STUDS. ALIGN TRACKS ACCURATELY TO LAYOUT AT BASE AND TOPS OF STUDS. UNLESS INDICATED OTHERWISE, SECURE TRACKS AS RECOMMENDED BY STUD MANUFACTURER FOR TYPE OF CONSTRUCTION INVOLVED. EXCEPT DO NOT EXCEED 24" OC SPACING FOR NAIL OR POWER-DRIVEN FASTENERS, OR 16" OC FOR OTHER TYPES OF ATTACHMENT. PROVIDE FASTENERS AT CORNERS AND ENDS OF TRACK.
- FASTENINGS: FASTENING OF COMPONENTS SHALL BE WITH SELF-DRILLING SCREWS OR BY WELDING. SCREWS AND WELDS SHALL BE OF SUFFICIENT SIZE TO ENSURE THE STRENGTH OF THE CONNECTION. WIRE TYING OF COMPONENTS SHALL NOT BE PERMITTED. ALL WELDS SHALL BE TOUCHED UP WITH A ZINC-RICH PAINT. FASTENING OF PLYWOOD DIAPHRAGMS AND SILL PLATES SHALL BE AS INDICATED IN STRUCTURAL NOTES, AND DETAILED.
- STUD SECTIONS USED AS RAFTERS OR JOISTS SHALL BE UNPUNCHED.
- ALL NON-LOAD BEARING WALLS SHALL BE ERECTED SO AS TO ALLOW FOR PROPER DEFLECTION OF STRUCTURE ABOVE. THE TOPS OF ALL SUCH WALLS SHALL BE HORIZONTAL, BRACED TO THE STRUCTURE ABOVE AT A MAXIMUM OF 8'-0" OC.



REDWOOD ROAD ABC STORE - REMODEL AND EXPANSION

DPT OF ALCOHOLIC BEVERAGE CONTROL
3381 S REDWOOD ROAD, WEST VALLEY CITY, UTAH
FRANK N MURDOCK JR. Architect & Associates
975 East 100 South Site 100, Salt Lake City, Utah 84102 TEL: (801) 532-4441 FAX: (801) 532-4220



REVISION # DATE:

CONSTRUCTION DOCUMENTS
FILE NAME: S001
PLOT SCALE: 3/4"=1'-0"
DRAWN BY: JRS
CHECKED BY: SP
DATE: 02/05/07

S001




ALL DRAWINGS, PLANS AND DETAILS ARE INSTRUMENTS OF SERVICE AND SHALL REMAIN THE PROPERTY OF CALDER RICHARDS CONSULTING ENGINEERS AND ARE NOT SUITABLE FOR REUSE NOR INTENDED FOR ANY OTHER PROJECT.

SCALE: 1/8" = 1'-0"




(ROOF FRAMING):

- LEGEND:




CONSTRUCTION DOCUMENTS
FILE NAME: S102
PLOT SCALE: 1/8"=1'-0"
DRAWN BY: JRS
CHECKED BY: SP
DATE: 02/05/07

S102



REDWOOD ROAD ABC STORE - REMODEL AND EXPANSION

DPT OF ALCOHOLIC BEVERAGE CONTROL
3381 S REDWOOD ROAD, WEST VALLEY CITY, UTAH
FRANK N. MURDOCK JR., Architect & Associates
975 East 100 South, Suite 100, Salt Lake City, Utah 84102
TEL: (801) 532-4441 FAX: (801) 532-4220



REVISION # DATE:
CONSTRUCTION DOCUMENTS
FILE NAME: S201
PLOT SCALE: 3/4"=1'-0"
DRAWN BY: JRS
CHECKED BY: SP
DATE: 02/05/07

S201

STRUCTURAL DETAILS


E1 DETAIL
SCALE: 3/4" = 1'-0"




E2 DETAIL
SCALE: 3/4" = 1'-0"




E3 DETAIL
SCALE: 3/4" = 1'-0"




E4 DETAIL
SCALE: 3/4" = 1'-0"



E5 DETAIL
SCALE: 3/4" = 1'-0"



E6 DETAIL
SCALE: 3/4" = 1'-0"




MASONRY COLUMN SCHEDULE					
MARK	LENGTH	WIDTH	REINFORCEMENT		TYPE
			VERTICAL	HORIZONTAL TIES	
MC-1	16"	WALL	(4) #5		1
MC-2	24"	WALL	(6) #5	#3 @ 8" OC	2

- MASONRY COLUMN NOTES:
- HORIZONTAL WALL REINFORCEMENT SHALL RUN CONTINUOUS THROUGH MASONRY COLUMNS.
 - GROUT ALL REINFORCED CELLS AND VOIDS SOLID.
 - MASONRY COLUMNS REINFORCING SHALL EXTEND FULL HEIGHT FROM ROOF DOWN TO FOUNDATION. DOWEL VERT REINF INTO FOUNDATIONS.
 - SEE ARCHITECTURAL DRAWINGS FOR SPECIAL COURSING ARRANGEMENTS.


D5 MASONRY COLUMN SCHEDULE
5310.00 SCALE: NONE

MASONRY REBAR SPlice SCHEDULE											
BAR SIZE	#3	#4	#5	#6	#7	#8	#9	#10	#11	MECH	MECH
MASONRY SINGLE MAT	1'-7"	2'-1"	2'-7"	4'-4"	5'-1"	6'-2"	7'-10"				
MASONRY DOUBLE MAT	1'-7"	2'-4"	3'-6"	6'-10"	9'-1"	12'-5"	15'-4"			MECH	MECH


- MASONRY REBAR SPlice NOTES:
- MECH = MECHANICAL SPlice REQUIRED.
 - USE #6 BAR IN 10" OR LARGER WALLS ONLY.
 - f'm = 1500 PSI, f_y = 60,000 PSI
 - DOUBLE MAT REINFORCEMENT SHALL HAVE 2" CLEARANCE BETWEEN FACE OF WALL AND EDGE OF VERTICAL BAR.




D1 DETAIL
SCALE: 3/4" = 1'-0"




D2 DETAIL
SCALE: 3/4" = 1'-0"



C3 DETAIL
SCALE: 3/4" = 1'-0"




C4 DETAIL
SCALE: 3/4" = 1'-0"




REINFORCING LAP LENGTH SPLICE SCHEDULE																
BAR SIZE	TENSION BARS "Ld"															
	f _c =3000psi				f _c =4000psi				f _c =5000psi				f _c =6000psi			
	REGULAR CLASS		TOP CLASS		REGULAR CLASS		TOP CLASS		REGULAR CLASS		TOP CLASS		REGULAR CLASS		TOP CLASS	
	A	B	A	B	A	B	A	B	A	B	A	B	A	B	A	B
#3	17"	22"	22"	28"	15"	19"	19"	24"	13"	17"	17"	22"	12"	16"	16"	21"
#4	22"	29"	29"	36"	18"	25"	25"	33"	17"	22"	22"	30"	16"	20"	21"	27"
#5	28"	36"	37"	48"	24"	31"	32"	42"	21"	28"	28"	37"	20"	25"	26"	34"
#6	33"	43"	45"	58"	29"	37"	39"	50"	26"	33"	35"	45"	24"	30"	32"	41"
#7	48"	63"	63"	82"	42"	55"	55"	71"	37"	48"	48"	62"	34"	45"	45"	58"
#8	55"	72"	72"	93"	48"	63"	63"	81"	42"	55"	55"	71"	39"	51"	51"	66"
#9	62"	81"	81"	105"	54"	71"	71"	92"	48"	62"	62"	80"	44"	57"	57"	74"
#10	70"	91"	91"	118"	61"	79"	79"	103"	54"	70"	70"	90"	50"	65"	65"	84"
#11	78"	101"	101"	131"	68"	88"	88"	114"	60"	77"	77"	100"	55"	72"	72"	93"

- NOTES:
- THE SCHEDULE SHOWN APPLIES TO REG WT CONCRETE WITH 60ksi GRADE REINFORCING BARS.
 - TOP BARS ARE HORIZONTAL BARS WITH 12" (OR MORE), OF FRESH CONCRETE CAST BELOW THE BARS.
 - CLASS "A" SPlices SHALL BE USED WHEN 50% (OR LESS) OF BARS SPliced WITHIN LAP.
 - CLASS "B" SPlices SHALL BE USED FOR ALL ELSE, TYPICALLY WITH SHEARWALLS, COLUMNS, BEAMS & SLABS.
 - FOR EPOXY COATED BARS, INCREASE LAP LENGTHS AS FOLLOWS:
TOP BARS: L_d x 1.7
REGULAR BARS: L_d x 1.5
 - FOR BUNDLED BARS, INCREASE LAP LENGTHS AS FOLLOWS:
BUNDLED BARS, THREE OR LESS: L_d x 1.2
BUNDLED BARS, FOUR OR MORE: L_d x 1.33
INDIVIDUAL BAR SPlices WITHIN A BUNDLE SHALL NOT OVERLAP.
 - LAP SPlices ARE NOT ALLOWED FOR TIES AND STIRRUPS.


C1 DETAIL
SCALE: 3/4" = 1'-0"




C2 DETAIL
SCALE: 3/4" = 1'-0"




C3 DETAIL
SCALE: NONE




C4 DETAIL
SCALE: NONE




C5 DETAIL
SCALE: NONE




C6 DETAIL
SCALE: NONE




B1 TYP MASONRY CONTROL JOINT
SCALE: NONE




B2 TYPICAL SLAB JOINT DETAILS
SCALE: NONE




B3 WALL INTERSECTION DOWELS
SCALE: NONE




B4 FOOTING STEP (CONC FDTN)
SCALE: NONE




B5 DETAIL
SCALE: 3/4" = 1'-0"




B6 DETAIL
SCALE: 3/4" = 1'-0"




A1 SLAB STEP DETAIL
SCALE: 3/4" = 1'-0"




A2 DETAIL
SCALE: 3/4" = 1'-0"




A3 DETAIL
SCALE: 3/4" = 1'-0"




A4 DETAIL
SCALE: 3/4" = 1'-0"



A5 DETAIL
SCALE: 3/4" = 1'-0"




A6 DETAIL
SCALE: 3/4" = 1'-0"



ALL DRAWINGS, PLANS AND DETAILS ARE INSTRUMENTS OF SERVICE AND SHALL REMAIN THE PROPERTY OF CALDER RICHARDS CONSULTING ENGINEERS AND ARE NOT SUITABLE FOR REUSE NOR INTENDED FOR ANY OTHER PROJECT.











STRUCTURAL DETAILS

CONSTRUCTION DOCUMENT
FILE NAME: S202
PLOT SCALE: 3/4"=1'-
DRAWN BY: JRS
CHECKED BY: SP
DATE: 02/05/07

S202



C3 4344_05 S-BMCON2 SCALE: 3/4" = 1'-0"



ALL DRAWINGS, PLANS AND DETAILS ARE INSTRUMENTS OF SERVICE AND SHALL REMAIN THE PROPERTY OF CALDER RICHARDS CONSULTING ENGINEERS AND ARE NOT SUITABLE FOR REUSE NOR INTENDED FOR ANY OTHER PROJECT.

PIPING LEGEND				MECHANICAL LEGEND			
GATE VALVE		CHILLED WATER SUPPLY	CHS	RETURN OR EXHAUST DUCT DOWN			
OS & Y PATTERN GATE VALVE		CHILLED WATER RETURN	CHR	RETURN OR EXHAUST DUCT UP			
BALL VALVE		CONDENSER WATER SUPPLY	CWS	SUPPLY AIR DUCT DOWN			
BUTTERFLY VALVE		CONDENSER WATER RETURN	CWR	SUPPLY AIR DUCT UP			
MOTORIZED BUTTERFLY VALVE		HEATING WATER SUPPLY	HWS	SPIN-IN FITTING W/MSD			
HEAT TRACING		HEATING WATER RETURN	HWR	FLEXIBLE DUCT			
DEIONIZED WATER		WATER TREATMENT	WT	CEILING SLOT DIFFUSER			
CHECK VALVE		FIRE DEPT. HORN & LIGHT		CEILING DIFFUSER			
SOLENOID VALVE		HOT GAS	HG	CEILING EXHAUST GRILLE			
AUTOMATIC CONTROL VALVE (2-WAY)		FLEXIBLE PIPE CONNECTION		CEILING GRILLE			
AUTOMATIC CONTROL VALVE (3-WAY)		REDUCED PRESSURE BACKFLOW PREVENTER	RFBP	ACCESS PANEL			
PRESSURE REDUCING VALVE		DIRECTION OF FLOW		MANUAL VOLUME DAMPER			
P & T RELIEF VALVE		ELBOW DOWN (DN)		MOTORIZED DAMPER			
AIR VENT (AUTOMATIC)		ELBOW UP		FIRE DAMPER			
REFRIGERANT LIQUID		PIPE CAP		COMBINATION FIRE/SMOKE DAMPER			
REFRIGERANT SUCTON		TEE DOWN		THERMOSTAT OR TEMP SENSOR			
THERMAL EXPANSION VALVE		UNION		POINT OF CONNECTION TO EXISTING			
STRAINER		DOMESTIC COLD WATER	---	DETAIL NO. DRAWING NO.			
CIRCUIT SETTER		DOMESTIC HOT WATER	---	NOTE NO. DRAWING NO.			
FLOW METER		HOT WATER CIRC.	---	KEYED NOTE			
FET COCK OR GAUGE COCK		TEMPERED WATER	---	SECTION CUT LINE			
PRESSURE GAUGE W/GAUGE COCK		SANITARY (PLBG) VENT	-----	CONTROL TRANSFORMER			
THERMOMETER		SANITARY SEWER ABOVE GRADE	-----	LOW PRESSURE DUCT W/ TURNING VANES			
TEMPERATURE & PRESSURE TEST PLUG		SANITARY SEWER BELOW GRADE	-----	BALANCER TO TURN ALL SLOTS IN DIFFUSER FACING DIRECTION NOTED			
IN-LINE PUMP		DRAIN	D				
FLOW SWITCH		ROOF DRAIN PIPING	RD				
AQUASTAT		OVERFLOW DRAIN PIPING	OD				
HOSE BIBB OR SILL COCK		STORM DRAIN PIPING ABOVE GRADE	SD				
VACUUM		STORM DRAIN PIPING BELOW GRADE	SD				
FLOOR DRAIN		FIRE SERVICE	F				
FLOOR SINK		NATURAL GAS	G				
HOT GAS BYPASS		COMPRESSED AIR	CA				
WALL CLEANOUT OR CLEANOUT		VENT THROUGH ROOF					
FLOOR OR GRADE CLEANOUT		STEAM	S				
GRADE CLEANOUT W/ CONCRETE PAD		CONDENSATE	C				

GENERAL NOTES

1. (E) INDICATES POINT OF CONNECTION OF NEW TO EXISTING MECHANICAL.
2. (E) INDICATES EXISTING, (N) INDICATES NEW MATERIAL.
3. COORDINATE ALL FIRE SPRINKLER DIFFUSER AND GRILLE LOCATIONS WITH REFLECTED CEILING PLAN AND ELECTRICAL DRAWINGS.
4. THIS CONTRACTOR SHALL NOT SHUT-OFF/PUT OUT OF SERVICE ANY SYSTEMS/SERVICES WITHOUT FIRST COORDINATING ALL DOWNTIME WITH THE OWNER'S PERSONAL.
5. ALL RIGID ROUND DUCTWORK SHALL RECEIVE 1-1/2" x 3.0 LBS/GUFT. FIBERGLASS DUCT WRAP. ALL RECTANGULAR DUCT SHALL RECEIVE 1" x 1.5 LBS/GUFT. DUCT LINER, TRIM AND SEAL JOINTS W/ MYLAR LINING. LOW PRESSURE ROUND FLEXIBLE DUCT TO BE 1-1/2" THICK INSULATED AND A MAXIMUM OF 10 FT. LONG. ALL INSULATION TO MEET NFPA 90 PER UL-181-CLASS 1. MEDIUM PRESSURE FLEXIBLE DUCT TO BE INSULATED, RATED FOR 6" U.L.C. AND SHALL BE STRECHED OUT TO PREVENT ANY KINKS OR OFFSETS (3 FT. MAX. LENGTH).
6. DUCTWORK AND PIPE ROUTING IS APPROXIMATE, DIAGRAMATIC AND IS NOT TO BE SCALED. WHERE ALTERNATE ROUTING, OFFSETS AND TRANSITIONS ARE REQUIRED FOR COORDINATION OF ALL WORK, THIS CONTRACTOR SHALL MAKE CHANGES WITHOUT ADDITIONAL COSTS.
7. THIS CONTRACTOR SHALL CLOSELY COORDINATE NEW MECHANICAL WITH ALL NEW AND EXISTING MECHANICAL, ELECTRICAL, ARCHITECTURAL AND STRUCTURAL MEMBERS.
8. THIS CONTRACTOR SHALL FIELD VERIFY ALL MECHANICAL ITEMS PRIOR TO COMMENCING NEW WORK. NO ADDITIONAL COST WILL BE ALLOWED FOR CONTRACTOR'S FAILURE TO BECOME FAMILIAR WITH EXISTING MECHANICAL CONDITIONS.
9. THIS CONTRACTOR SHALL USE SMACNA STANDARDS FOR HIGH PRESSURE DUCT CONSTRUCTION OF SUPPLY DUCTWORK UPSTREAM OF VAV BOX - SEAL CLASS "A". ALL OTHER DUCTWORK SHALL BE CONSTRUCTED ACCORDING TO SMACNA STANDARDS FOR LOW PRESSURE DUCT CONSTRUCTION - SEAL CLASS "B".
10. ALL MECHANICAL SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ALL CURRENT LOCAL CODES.
11. THIS CONTRACTOR SHALL PROVIDE SUBMITTALS ON ITEMS LISTED IN MECHANICAL EQUIPMENT LIST TO THE ENGINEER FOR REVIEW PRIOR TO THE ORDER, PURCHASE OR INSTALLATION OF THESE SAME ITEMS.
12. ALL VAV BOXES AND DIFFUSERS MUST BE BALANCED PER PLAN. PROVIDE BALANCE REPORT TO ENGINEER.
13. DUCT DIMENSIONS SHOWN ARE INSIDE CLEAR DIMENSIONS.

ELECTRIC WATER HEATER SCHEDULE [UH-]							
PLAN CODE	INPUT (KBTU)	RECOVERY RATE (GAL/HR)	TEMP. RISE (°F)	DIMENSIONS	ELECTRICAL VOLT & PHASE AMPS	MANUFACTURER & MODEL NO.	REMARKS
UH-1	1500	13	80	26" x 18" x 21"	208 / 1 10.4	A.O. SMITH DEL-15	WITH AMTROL ST-5 EXPANSION TANK

PUMP SCHEDULE [P-]							
PLAN CODE	DUTY	GPM	FEET OF HEAD	PUMP RPM	MOTOR H.P. VOLTAGE & PHASE	MANUFACTURER & MODEL NO.	COMMENTS
P-1	CIRCULATOR	8	26	3550	1/8 120 / 1	TACO 2013	BRONZE FITTED

ROOF TOP UNIT SCHEDULE [RTU-]														
PLAN CODE	UNIT TONNAGE	TOTAL CFM	EXTERNAL STATIC PRESSURE	DESIGN CRITERIA OUTSIDE AIR TEMP RETURN AIR DB RETURN AIR WB	LEAVING AIR TEMP	EER	SENSIBLE COOLING CAPACITY (MBH)	HEATING CAPACITY INPUT (MBH) OUTPUT (MBH)	ELECTRICAL VOLTS PHASE MCA MOP	DIMENSIONS (in.) Length Width Height	OPER. WEIGHT (lbs)	MANUFACTURER & MODEL NO.	REMARKS	
RTU-1 & RTU-2	6	2400	0.6	95 80 62	54.3/53.2	10.2	54.5/0	124.5 101.0/0	208 / 3 32.7 50	89 54 55	1100	TRANE YSC07JASHA	SEE GENERAL NOTES	

GENERAL NOTES:


1. VALUES ARE RATED AT 4500 FL. ELEVATION.
2. PROVIDE MINIMUM OUTSIDE AIR SET POINTS.
3. PROVIDE 14" FACTORY CURB.
4. PROVIDE ECONOMIZER, AND POWER EXHAUST.
5. PROVIDE FACTORY 4 OZ. GAS TRAIN.
6. PROVIDE COMPRESSOR CRANKCASE HEATER.
7. ALL ROOFTOP UNITS MUST MEET OR EXCEED CURRENT ASHRAE ENERGY CODE 90.1 STANDARDS.
8. PROVIDE FACTORY HACR CIRCUIT BREAKER.
9. PROVIDE 7 DAY PROGRAMMABLE T-STAT WITH 1000 FL. OF FLEM/RAN T-STAT WIRE.
10. PROVIDE FACTORY MOUNTED CONV. OUTLET TO BE FIELD WIRED.
11. PROVIDE SMOKE DETECTOR IN SUPPLY & RETURN AIR DUCTWORK.
12. PROVIDE COIL GUARDS.

EXHAUST FAN SCHEDULE [EF-]															
PLAN CODE	AREA SERVED	TYPE	CFM @ ELEV.	ESP	FAN RPM	MOTOR			SONES	DAMPER TYPE	METHOD OF CONTROL	OPENING SIZE	OPERATING WT. (LBS.)	MANUFACTURER / MODEL	ACCESSORIES
						WATTS	H.P.	VOLTAGE & PHASE							
EF-1	SEE PLANS	ROOF CENTRIFUGAL	488	0.75	1320	NA	1/4	120 / 1	7.9	BACK DRAFT	TIME CLOCK	12" x 12"	65	PENN BARRY DOMEYX DX068	PROVIDE FACTORY 14" CURB

GAS FIRED UNIT HEATER SCHEDULE [UH-]											
PLAN CODE	HEATING MBH OUTPUT REQD. ELEVATION	MANUFACTURER & MODEL NO.	SPECIFIED UNIT CAP. INPUT (B.L.U.) (MBH) OUTPUT (B.L.U.) (MBH)	CFM (STD.)	THROW AT 12' MOUNTING (FT.)	ELECTRICAL VOLT/ PHASE FAN H.P.	FLUE SIZE / TYPE	SIZE LENGTH WIDTH HEIGHT	WEIGHT	REMARKS	
UH-1	80	MODINE PD 100	100 80	1460	41	120 / 1 1/2	6" x 15"	30" 18" 29"	110 lbs.	WT-STAT, PIPE HANGER KIT AND FACTORY 4 OZ. GAS TRAIN.	


PLUMBING FIXTURE CONNECTION SCHEDULE						
	DESCRIPTION	CONNECTION SIZE				SPECIFICATIONS
		COLD WATER	HOT WATER	WASTE	VENT	
WC-1	WATER CLOSET (HANDICAP)	3/4"	N/A	3"	2 1/2"	KOHLER K-3544-RA SEAT: OLSONITE 95 COMFORT CURVE, COLOR: WHITE. PROVIDE SUPPLIES AND STOP. SET RIM AT 17 1/2" AFF.
WC-2	WATER CLOSET (HANDICAP)	3/4"	N/A	3"	2 1/2"	KOHLER K-3544, SEAT: OLSONITE 95 COMFORT CURVE, COLOR: WHITE. PROVIDE SUPPLIES AND STOP. SET RIM AT 17 1/2" AFF.
L-1	LAVATORY	1/2"	1/2"	1 1/2"	1 1/4"	KOHLER: GREENWICH WALL MOUNT K-2031-N W/ ACCESSORY MODEL #102G FOR HANDICAP INSTALLATION & K-6998 TRAP FAUCET: SYMPHONY ULTRA SENSE 9-6698-G W/ GRID DRAIN FLOVER HYDROGUARD SERIES 480 TEMPERING VALVE.
HB-1	HOSE BIBB	3/4"	N/A	N/A	N/A	WOODFORD: MODEL 74P-3/4
FD-1	FLOOR DRAIN	N/A	N/A	SEE PLANS	N/A	J. R. SMITH 2025 W/ ABS/NB NICKEL/BRONZE STRAINER AND TRAP PRIMER
FS-1	FLOOR SINK	N/A	N/A	SEE PLANS	N/A	J. R. SMITH 3140-12-Y W/ NICKEL/BRONZE TOP 1/2 GRATE AND TRAP PRIMER
SC-1	SILCOCK	3/4"	N/A	N/A	N/A	J. R. SMITH 55090T (w/ INTEGRAL VACUUM BREAKER AND STAINLESS STEEL BOX)
WCO-1	WALL CLEAN OUT	N/A	N/A	SEE PLANS	N/A	J. R. SMITH 4530
FCO-1	FLOOR CLEAN OUT	N/A	N/A	SEE PLANS	N/A	J. R. SMITH 4023
RD-1	ROOF DRAIN	N/A	N/A	N/A	N/A	J.R. SMITH 1010Y - C - R - C1 DOME PROVIDE CAST IRON DOME.
OD-1	OVERFLOW DRAIN	N/A	N/A	N/A	N/A	J.R. SMITH 1000Y - C - R - C1 DOME PROVIDE CAST IRON DOME.
DSN-1	DOWNSPOUT NOZZLE	N/A	N/A	N/A	N/A	J.R. SMITH 1770
UHA	WATER HAMMER ARRESTORS	AS REQUIRED	AS REQUIRED	N/A	N/A	J. R. SMITH 5020
SS-1	SERVICE SINK	3/4"	3/4"	3"	1 1/2"	KOHLER: K-6710 W/ K-9142 STRAINER FAUCET: CHICAGO FAUCET MODEL # 697-RCP
S-1	SINK (50.2 COMPARTMENT)	1/2"	1/2"	2"	1 1/4"	JST: DLX-1879-A-GR WITH J35 STRAINER FAUCET: CHICAGO FAUCET MODEL # 786-SUE79CP. PROVIDE W/ GARBAGE DISPOSAL UNIT GDU-11: ISE MODEL FRD 17, 1 hp, 115 V, 10, 5.0 amps
EW-1	ELECTRIC WATER COOLER	1/2"	N/A	1 1/2"	1 1/4"	SUNROC: NUCA-8-BL (B1 LEVEL FOUNTAIN) 7.0 gpm, 4.5 FLA, 415 Watts, 120v - 10, R-134A

AIR DEVICE SCHEDULE						
PLAN CODE	TYPE & DUTY	NECK SIZE	CEILING TYPE	N.C. LEVEL MAX	MAX CFM	MANUFACTURER & MODEL NO.
1	RETURN	10" x 22"	See Plans	10	610	PRICE 22" x 10" / 24" x 12" / PDOR / 3 / B12 PROVIDE W/ SOUND BOOT
2	RETURN	22" x 22"	See Plans	10	1340	PRICE 22" x 22" / 24" x 24" / PDOR / 3 / B12 PROVIDE W/ DUCT COLLAR
3	EXHAUST	6" x 6"	See Plans	15	170	PRICE 6" x 12" x 12" / PDOR / 2 / B12 PROVIDE OBD
4	EXHAUST	14" x 14"	See Plans	31	490	PRICE 10" x 16" x 16" / PDOR / 2 / B12 PROVIDE OBD
5	SUPPLY	8" x 8"	See Plans	20	280	PRICE 8" x 24" x 24" / SCDA / 3 / B12
6	SUPPLY	10" x 10"	See Plans	20	420	PRICE 10" x 24" x 24" / SCDA / 3 / B12
7	SUPPLY	12" x 12"	See Plans	20	560	PRICE 12" x 24" x 24" / SCDA / 3 / B12

REVISION / DATE:
CITY REVIEW 2/28/2007DFCM PROJECT NO.:
06233030
PERMIT SET
FILE NAME: 6280.00
PLOT SCALE: SEE PLANS
DRAWN BY: AJG
CHECKED BY: KAG
DATE: MAY, 18, 200790 South 400 West, Suite 340
Salt Lake City, UT 84101
Phone: (801) 359-3158
Fax: (801) 321-4114

M0.1

- | KEYED NOTES: | GENERAL NOTES: |
|--|--|
| 1. 6" TYPE 'B' BLUE UP THROUGH ROOF SEE DETAIL 6/16/2 | 1. ALL EXPOSED DUCTWORK OR DUCTWORK ABOVE GYP. CEILING SHALL BE HARD DUCTED. |
| 2. PROVIDE AND INSTALL DUCTWORK DROPS DOWN FROM UNIT SIZED FULL SIZE OF UNITS OPENINGS. (TYPICAL) | 2. USE YOUNG GEAR TYPE BALANCING REGULATORS ABOVE ALL GYP. BOARD CEILING. |
| 3. COORDINATE WITH ROOF STRUCTURAL AND INSTALL DUCTWORK TIGHT TO BOTTOM OF STRUCTURE. IF POSSIBLE ROUTE MAINS UP IN BETWEEN JOIST. (TYPICAL) | 3. ALL MEDIUM PRESSURE DUCTWORK SHALL BE HELD TIGHT TO BOTTOM OF STRUCTURE. OFFSET AND TRANSITION AS REQUIRED. |
| 4. COORDINATE WITH ARCH'S PLANS FOR FINAL ELEVATIONS AND LOCATIONS OF 7-DAY PROGRAMMABLE T-STATS. (TYPICAL) | 4. OFFSET AND TRANSITION ALL DUCTWORK AND PIPING AS REQUIRED. |
| 5. 12"X12" RISER TO AIR DOME EE-1 ON ROOF. | 5. ALL VALVES SHALL BE LOCATED ABOVE ACCESSIBLE CEILING. |
| 6. PROVIDE LOCKING COVER FOR T-STAT. | 6. PROVIDE ACCESS PANELS AS REQUIRED. |
| 7. HOLD DUCTWORK TIGHT TO BOTTOM OF STRUCTURE. (TYPICAL) | 7. CONTRACTOR TO COORDINATE ALL INSTALLATIONS WITH OTHER TRADES. |
| 8. OUTLINE OF RTU ON ROOF ABOVE. | 8. CONTRACTOR TO COORDINATE ALL FINAL LOCATION OF T-STATS WITH OWNER AND ARCHITECT. |
| 9. OUTLINE OF EE-1 ON ROOF ABOVE. | 9. CONTRACTOR TO PROVIDE AND INSTALL SOUND BOOTS ON ALL RETURN AIR GRILLES. BOOTS TO BE PAINTED FLAT BLACK. |
| | 10. CONTRACTOR TO COORDINATE GRILLES WITH REFLECTED CEILING GRID. |
| | 11. CONTRACTOR TO COORDINATE WITH ELECTRICAL AND DO NOT ROUTE PIPING OVER ELECTRICAL EQUIPMENT. |
| | 12. ALL PIPING SHALL BE HELD TIGHT TO BOTTOM OF STRUCTURE. |
| | 13. PROVIDE 4" DEEP SEAL TRAPS WITH TRAP PRIMERS ON ALL FLOOR DRAINS & FLOOR SINKS. |
| | 14. ALL WASTE PIPING TO BE SLOPED AS REQUIRED BY CODE. |




MECHANICAL FLOOR PLAN
SCALE: 1/8" = 1' - 0"

REDWOOD ROAD ABC STORE- REMODEL AND EXPANSION

DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
3381 S. REDWOOD ROAD, WEST VALLEY, UTAH

FRANK N. MURDOCK JR. ■ Architect & Associates
975 East 100 South, Suite 100, Salt Lake City, Utah 84102 TEL: (801) 532-4441 FAX: (801) 532-4220





REVISION # DATE:
CITY REVIEW 2/28/2007

DFCM PROJECT NO.:
06233030
PERMIT SET
FILE NAME: 6280.00
PLOT SCALE: SEE PLANS
DRAWN BY: AJG
CHECKED BY: KAG
DATE: MAY 18, 2007


PVE Inc.
Consulting Mechanical Electrical Engineers
90 South 400 West, Suite 340
Salt Lake City, UT 84101
Phone: (801) 359-3158
Fax: (801) 521-4114

M2.1





PLUMBING FLOOR PLAN
SCALE: 1/8" = 1' - 0"




RESTROOM PIPING PLAN
SCALE: 1/4" = 1' - 0"

- | KEYED NOTES: | GENERAL NOTES: |
|--|--|
| 1. 4" RISER TO OVERFLOW DRAINS ON ROOF. | 1. ALL EXPOSED DUCTWORK OR DUCTWORK ABOVE GYP. CEILINGS SHALL BE HARD DUCTED. |
| 2. EXTEND SECONDARY DOWN SPOUT OUT OF BUILDING. COORDINATE FINAL ELEVATIONS WITH ARCH/OWNER. | 2. USE YOUNG GEAR TYPE BALANCING REGULATORS ABOVE ALL GYP. BOARD CEILINGS. |
| 3. 1" GAS RISER TO ROOF TOP UNIT. M.C. TO PROVIDE FINAL CONNECTIONS REQUIRED. | 3. ALL MEDIUM PRESSURE DUCTWORK SHALL BE HELD TIGHT TO BOTTOM OF STRUCTURE. OFFSET AND TRANSITION AS REQUIRED. |
| 4. GAS LOAD FOR NEW BUILDING/EXISTING BUILDING IS 726 CFH @ 402.1 PRESSURE. QUESTAR TO VERIFY EXISTING PETER OR REPLACE IF REQUIRED. | 4. OFFSET AND TRANSITION ALL DUCTWORK AND PIPING AS REQUIRED. |
| 5. M.C. TO FIELD VERIFY AND COORDINATE WITH ARCH'S AND CIVIL'S PLANS IN PROVIDING CODE REQUIRED COVERAGE OVER ALL PLUMBING LINES ENTERING & EXISTING THE BUILDING. | 5. ALL VALVES SHALL BE LOCATED ABOVE ACCESSIBLE CEILINGS. |
| 6. F.P.C. TO FIELD VERIFY AND MODIFY EXISTING FIRE SPRINKLER SYSTEM AS REQUIRED TO HANDLE NEW BUILDING SPACE. | 6. PROVIDE ACCESS PANELS AS REQUIRED. |
| 7. M.C. TO EXTEND AND CONNECT ALL NEW UTILITIES TO EXISTING SITE UTILITIES AS REQUIRED. | 7. CONTRACTOR TO COORDINATE ALL INSTALLATIONS WITH OTHER TRADES. |
| 8. PROVIDE FINAL CONNECTION TO UNIT HEATER. | 8. CONTRACTOR TO COORDINATE ALL FINAL LOCATION OF T-SISTS WITH OWNER AND ARCHITECT. |
| 9. M.C. TO PROVIDE WATER HAMMER ARRESTORS ON ALL PIPING WITH QUICK CLOSE VALVES. (TYPICAL) | 9. CONTRACTOR TO PROVIDE AND INSTALL SOUND BOOTS ON ALL RETURN AIR GRILLES. BOOTS TO BE PAINTED FLAT BLACK. |
| 10. PROVIDE HOSE BIBB UNDER LAVATORY. (TYPICAL) | 10. CONTRACTOR TO COORDINATE GRILLES WITH REFLECTED CEILING GRID. |
| 11. PROVIDE ICE MAKER CONNECTION BOX AT REFRIGERATOR. COORDINATE WITH ARCH/OWNER AS TO FINAL LOCATION. | 11. CONTRACTOR TO COORDINATE WITH ELECTRICAL AND DO NOT ROUTE PIPING OVER ELECTRICAL EQUIPMENT. |
| 12. M.C. TO DEMO ALL PIPING IN THIS SHADED AREA BACK TO MAINS AND CAP AS REQUIRED. | 12. ALL PIPING SHALL BE HELD TIGHT TO BOTTOM OF STRUCTURE. |
| 13. M.C. TO FIELD VERIFY AND DEMO EXISTING GAS PIPING THRU WALL AND REPLACE WITH NEW 2" GAS PIPING AS SHOWN. RECONNECT EXISTING GAS AS SHOWN. | 13. PROVIDE 4" DEEP SEAL TRAPS WITH TRAP PRIMERS ON ALL FLOOR DRAINS & FLOOR SINKS. |
| 14. M.C. TO CONNECT EXISTING COLD WATER PIPING TO NEW COLD WATER PIPING AS SHOWN. | 14. ALL WASTE PIPING TO BE SLOPED AS REQUIRED BY CODE. |
| 15. M.C. TO FIELD VERIFY AND DEMO EXISTING ROOF SCUPPER DRAINS AS SHOWN. | |
| 16. M.C. TO COORDINATE WITH ARCH/OWNER AND DEMO EXISTING PRV STATION. M.C. TO PROVIDE TEMPORARY WATER SERVICE IF REQUIRED UNTIL NEW SERVICE IS INSTALLED. | |
| 17. M.C. TO DEMO EXISTING WATER HEATER AS SHOWN. | |
| 18. M.C. TO FIELD VERIFY EXISTING ROOF DRAIN DROP AND NOZZLE AND PROVIDE NEW ELECTRICAL HEAT TAPE FOR EXISTING AND NEW OVERFLOW DRAIN DROPS. COORDINATE WITH ELECTRICAL TO PROVIDE SERVICE. TAPE TO BE SELF REGULATING AT 20 WATTS PER FOOT. | |
| 19. SEE ENLARGED PLAN FOR CONTINUATION OF PIPING. | |
| 20. M.C. TO FIELD VERIFY AND CONNECT TO EXISTING ROOF DRAIN ON ROOF. M.C. TO REMOVE EXISTING ROOF DRAIN PIPING AND DOWN SPOUT NOZZLE. | |
| 21. M.C. TO DROP 6" DRAINAGE PIPING DOWN TIGHT ALONG OUTSIDE WALL. | |
| 22. M.C. TO EXTEND PIPING AS REQUIRED AND CONNECT TO NEW CIVIL DRAINAGE PIPING. SEE ARCH'S PLANS AND CIVIL'S PLANS FOR FINAL LOCATIONS. | |
| 23. M.C. TO COORDINATE WITH STRUCTURAL AND ROUTE UP IN JOIST SPACE. COORDINATE ROUTING WITH DUCTWORK. | |
| 24. OFFSET PIPING SO THAT IT ROUTES INTO JOIST SPACE IN NEW ADDITION. FIELD VERIFY. | |
| 25. OFFSET PIPING AS REQUIRED TO ROUTE TIGHT TO BOTTOM OF STRUCTURE IN BOTH NEW AND EXISTING BUILDING. (TYPICAL) | |
| 26. M.C. TO FIELD VERIFY EXISTING ROOF DRAIN AND REPLACE WITH NEW 4" WITH FAST IRON DOME AS REQUIRED. (TYPICAL) | |

PVE Inc.
Consulting Mechanical Electrical Engineers
90 South 400 West, Suite 340
Salt Lake City, UT 84101
Phone: (801) 359-3158
Fax: (801) 321-4114

REDWOOD ROAD ABC STORE- REMODEL AND EXPANSION
DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
3381 S. REDWOOD ROAD, WEST VALLEY, UTAH
FRANK N. MURDOCK JR. ■ Architect & Associates
975 East 100 South Suite 100, Salt Lake City, Utah 84102 TEL: (801) 532-4441 FAX: (801) 532-4220



REVISION / DATE:
CITY REVIEW 2/28/2007

DFCM PROJECT NO.:
06233030
PERMIT SET
FILE NAME: 6280.00
PLOT SCALE: SEE PLANS
DRAWN BY: AJG
CHECKED BY: KAG
DATE: MAY. 18, 2007



P2.1

[illegible]


- [illegible]

[illegible]


STANDARD MOUNTING HEIGHT UNLESS OTHERWISE NOTED ON PLANS			
SYMBOL	DESCRIPTION	MOUNTING HEIGHT	NOTES
	ONE CIRCUIT, TWO WIRE HOME RUN TO PANEL		
	2 CIRCUIT, 3 WIRE, COMMON NEUTRAL, HOME RUN		
	3 CIRCUIT, 4 WIRE, COMMON NEUTRAL, HOME RUN		
	CONDUIT RUN CONCEALED IN WALL OR CEILING		
	CONDUIT UP		
	CONDUIT DOWN		
	CONDUIT STUB LOCATION	CAP CONDUIT	
	CEILING LIGHT FIXTURE	CEILING	
	WALL LIGHT FIXTURE	AS NOTED	
	RECESSED DOWNLIGHT FIXTURE	CEILING	
	FLUORESCENT LIGHT FIXTURE	AS NOTED	
	FLUORESCENT EGRESS LIGHT FIXTURE	AS NOTED	UNSWITCHED
	CEILING MOUNTED EXIT LIGHT	CEILING	
	WALL MOUNTED EXIT LIGHT	AS NOTED	
	SINGLE POLE SWITCH	4'-0"	
	THREE-WAY SWITCH	4'-0"	
	FOUR-WAY SWITCH	4'-0"	
	DIMMER SWITCH	4'-0"	
	DUPLEX RECEPTACLE	16"	
	DUPLEX RECEPTACLE		ABOVE COUNTER
	ELECTRIC WATER COOLER RECEPTACLE		SEE DETAIL
	WEATHERPROOF RECEPTACLE	24"	
	ISOLATED GROUND RECEPTACLE	16"	
	GROUND FAULT INTERRUPTER DUPLEX RECEPTACLE	16"	
	FOURPLEX RECEPTACLE	16"	
	SPECIAL PURPOSE OUTLET	16" OR AS NOTED	
	TELEPHONE OUTLET-RUN 3/4" & TEL. EQUIP BOARD	16"	
	TELEPHONE/DATA OUTLET-RUN 3/4" TO TEL EQUIP BOARD	16"	
	JUNCTION BOX (F' IN FLOOR)	AS NOTED	TO SUIT EQUIP.
	MOTOR OUTLET	4'-0"	
	MANUAL STARTER THERMAL OVERLOAD SWITCH UNPILOT LIGHT	4'-0"	
	PANEL BOARD	TOP AT 4'-0"	
	TELEPHONE TERMINAL BOARD		
	FIRE ALARM MANUAL STATION	4'-0"	
	FIRE ALARM SIGNAL HORN/STROBE (CLG.) + CEILING	4'-8"	
	SMOKE DETECTOR	CEILING	
	DUCT SMOKE DETECTOR		MTD. IN DUCT
	HEAT DETECTOR	CEILING	
	ARCHITECTURAL ROOM NUMBER		
	LIGHT FIXTURE (LETTER DESIGNATES TYPE)		
	EQUIPMENT NUMBER		
	OVER HEAD DOOR CONTROLLER		
	FUSED DISCONNECT SWITCH		
	DISCONNECT SWITCH		
	CLOSED CIRCUIT TELEVISION CAMERA	CEILING	
	SECURITY DOOR POSITION INDICATING SWITCH	DOOR JAMB	
	SECURITY MOTION SENSOR	CEILING	
	GLASS BREAK SENSOR	106"	VERIFY



SCALE: 1/8" = 1' - 0"




- ### KEYED NOTES
-
- 1 MOMENTARY CONTACT SWITCH, WIRE TO CONTACTOR.
 - 2 EXISTING EXTERIOR LTG. WALLPACK TO BE REMOVED & RETURNED TO OWNER.
 - 3 WIRE CIRCUIT THROUGH CONTACTOR.
 - 4 CLEAN & RELAMP ALL EXISTING LENSED FLUORESCENT 4-LAMP TROFFERS.
 - 5 WIRE NEW FIXTURE TO EXISTING CIRCUIT.



LIGHTING PLAN


REDWOOD ROAD ABC STORE
DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL
1000 N. REDWOOD ROAD, SUITE 100, FOLSOM, CA 95630

FRANK N MURDOCK JR ■ **Architect & Associates**
975 East 100 South Suite 100, Salt Lake City, Utah 84102 TEL: (801) 531-5353




REVISION # DATE:

DFCM PROJECT NO.:
06234030
PERMIT SET
FILE NAME: 06280
PLOT SCALE: SEE PLANS
DRAWN BY: KDM
CHECKED BY: RKR
DATE: JAN. 2007



90 South 400 West, Suite 340
Salt Lake City, UT 84101
Phone: (801) 359-3158
Fax: (801) 521-4114

E201




- KEYED NOTES
- 1 SAW CUT FLOOR FOR INSTALLATION OF POWER, DATA & PHONE CONDUITS.
 - 2 OUTLET IN CEILING FOR SEASONAL DISPLAYS WITH SWITCH AT OFFICE.
 - 3 3/4\"/>
 - 4 3/4\"/>
 - 5 3/4\"/>
 - 6 3/4\"/>
 - 7 POWER DOOR CONTROLLER PROVIDED WITH DOOR. INSTALLED & WIRED BY ELECTRICAL.
 - 8 9160R LIFT CONTROLLER PROVIDED WITH LIFT. INSTALLED & WIRED BY ELECTRICAL.
 - 9 RECEPTACLE IN CEILING FOR T.V. MONITOR WITH SWITCH IN OFFICE. VERIFY EXACT LOCATION WITH ABC.
 - 10 REMOVE AND ABANDON ALL ELECTRICAL TO EXISTING 9160R LIFT.

POWER PLAN

SCALE: 1/8" = 1' - 0"

0' 4' 8' 12' 16'



REDWOOD ROAD ABC STORE


DEPARTMENT OF ALCOHOLIC BEVERAGE CONTROL

3381 S. REDWOOD ROAD, WEST VALLEY, UTAH

FRANK N. MURDOCK JR. ■ Architect & Associates


975 East 100 South Suite 100, Salt Lake City, Utah 84102 TEL: (801) 532-4441 FAX: (801) 532-4220

POWER PLAN



REVISION # DATE:

DFCM PROJECT NO.: 06234030
PERMIT SET
FILE NAME: 06280
PLOT SCALE: SEE PLANS
DRAWN BY: KDM
CHECKED BY: RKR
DATE: JAN. 2007



90 South 400 West, Suite 340
Salt Lake City, UT 84101
Phone: (801) 359-3158
Fax: (801) 521-4114

E301

PANELBOARD SCHEDULE

PANEL M

120/208 VOLTS

3 PH

4 W

MOUNTING

☐ FLUSH
☒ SURFACE

LOCATION: STOCK RM.

RATING: 10000 AIC

AMP 400


PROJECT: KIMBAL JCTN.

LIQUOR STORE


BRANCH BREAKERS

ITEM	AMPS	POLE	WIRE	CIR	LEFT PHASE LOAD	RIGHT PHASE LOAD	CIR	WIRE	ITEM	AMPS	POLE	WIRE	CIR	LEFT PHASE LOAD	RIGHT PHASE LOAD	CIR	WIRE	ITEM			
NIGHT LIGHTS	20	1	12	1	800			2	20	1	12	1	800				2	20	1	12	RECEPTACLE
LIGHTING	*				1600	500	500	4					500	500	500	500	6				
	*				1200	1600	1000	8					1000	1000	1000	1000	10				
	*				1000	1400	600	12					1000	1000	600	12					
EXTERIOR LIGHTS	20	1	12	1	1400	1000	600	14					1400	1000	600	14					
SPARE	20	1	12	1	1000	1000	600	16					1000	1000	600	16					
SPARE	20	1	12	1	1000	1000	600	18					1000	1000	600	18					
SPARE	20	1	12	1	1000	1000	600	20					1000	1000	600	20					
BOX CRUSHER	20	1	12	1	1000	1000	600	22					1000	1000	600	22					
ROLL-UP DOOR	20	1	12	1	1000	1000	600	24					1000	1000	600	24					
SCISSOR LIFT	40	3	8	25	2000	600	600	26					2000	600	600	26					
-	-	-	-	-	2000	600	600	28					2000	600	600	28					
-	-	-	-	-	2000	600	600	30					2000	600	600	30					
EXIST. PANEL	200	3	30	31	20000	400	400	32					20000	400	400	32					
-	-	-	-	-	20000	400	400	34					20000	400	400	34					
-	-	-	-	-	20000	400	400	36					20000	400	400	36					
RTU-1	50	3	8	31	3900	3900	3900	38					3900	3900	3900	38					
-	-	-	-	-	3900	3900	3900	40					3900	3900	3900	40					
-	-	-	-	-	3900	3900	3900	42					3900	3900	3900	42					
TOTAL					27900	23500	23500	7300	LOAD TOTAL					110200							
					33800	31100	31300	7600											FLA		306


* WIRE THRU
 CONTACTOR CABINET



VOICE DATA WIRING DIAGRAM
SCHEMATIC



SECURITY SYSTEM WIRING DIAGRAM
SCHEMATIC



CCTV SYSTEM WIRING DIAGRAM
SCHEMATIC