



STATE OF UTAH - DEPARTMENT OF ADMINISTRATIVE SERVICES

Division of Facilities Construction and Management

DFCM

STANDARD LOW BID PROJECT – INVITATIONAL
Project Budgets \$50,000 - \$100,000

October 4, 2007

MOAB REGIONAL SECURITY UPGRADE
DEPARTMENT OF HUMAN SERVICES
MOAB, UTAH

DFCM Project Number 07144400

P + A Architects
821 East Kensington Ave.
Salt Lake City, Utah 84105

TABLE OF CONTENTS

| | <u>Page Numbers</u> |
|--|---------------------|
| Title Page | 1 |
| Table of Contents | 2 |
| Invitation to Bid | 3 |
| Project Description | 4 |
| Project Schedule | 5 |
| Bid Form | 6 |
| Instructions to Bidders | 8 |
| Bid Bond | 12 |
| Contractors Sublist Form | 13 |
| Contractor's Agreement | 16 |
| Performance Bond | 21 |
| Payment Bond | 22 |
| Certificate of Substantial Completion | 23 |
| General Contractor Past Performance Rating | |

Current copies of the following documents are hereby made part of these contract documents by reference. These documents are available on the DFCM web site at <http://dfcm.utah.gov> or are available upon request from DFCM.

DFCM General Conditions dated May 25, 2005.

DFCM Application and Certification for Payment dated May 25, 2005.

Technical Specifications :

Drawings:

The Agreement and General Conditions dated May 25, 2005 have been updated from versions that were formally adopted and in use prior to this date. The changes made to the General Conditions are identified in a document entitled Revisions to General Conditions that is available on DFCM's web site at <http://dfcm.utah.gov>

INVITATION TO BID

Only firms that have been invited to submit bids on this project are allowed to bid on this project.

Sealed bids will be received by the Division of Facilities Construction and Management (DFCM) for:

MOAB REGIONAL CENTER SECURITY UPGRADE
DEPARTMENT OF HUMAN SERVICES – MOAB, UTAH
DFCM PROJECT NO: 07144400

| <u>Company</u> | <u>Contact</u> | <u>Fax</u> |
|--|------------------|--------------|
| Ben Byrd Construction | Ben | 435-259-0012 |
| Chad Husband Construction | Richard | 801-886-1784 |
| Wasatch West Construction | JD Tyrrell | 801-299-8541 |
| Bellock Construction, Inc. | Melody | 801-277-5751 |
| McCullough Engineering and Contracting | James McCullough | 801-466-4989 |

Bids will be in accordance with the Contract Documents that will be available on October 4, 2007 and distributed in electronic format only on CDs from DFCM, 4110 State Office Building, Salt Lake City, Utah and on the DFCM web page at <http://dfcm.utah.gov>. For questions regarding this project, please contact Michael Ambre, DFCM, at 801-209-9104. No others are to be contacted regarding this bidding process. The construction budget for this project is \$100,000.

A **mandatory** pre-bid meeting will be held at **10:30 AM on October 11, 2007** at Moab Regional Center (1165 South Highway 191 Moab, Ut 84095). All bidders wishing to bid on this project are required to attend this meeting.

Bids will be received until the hour of **3:00 PM on October 23, 2007** at DFCM, 4110 State Office Building, Salt Lake City, Utah 84114. Bids will be opened and read aloud in the DFCM Conference Room, 4110 State Office Building, Salt Lake City, Utah. NOTE: Bids must be received at 4110 State Office Building by the specified time.

A bid bond in the amount of five percent (5%) of the bid amount, made payable to the Division of Facilities Construction and Management on DFCM's bid bond form, shall accompany the bid.

The Division of Facilities Construction and Management reserves the right to reject any or all bids or to waive any formality or technicality in any bid in the interest of DFCM.

DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT
Joanna Fisher, Contract Coordinator
4110 State Office Building, Salt Lake City, Utah 84114

PROJECT DESCRIPTION

This project will include moving and/or adding walls, electrical, duct work, and interior finishes.

**PROJECT SCHEDULE**

| PROJECT NAME: MOAB REGIONAL SECURITY UPGRADE DEPARTMENT OF HUMAN SERVICES – MOAB, UTAH DFCM PROJECT NO. 07144400 | | | | |
|---|------------|-------------------|-------------|---|
| Event | Day | Date | Time | Place |
| Bidding Documents Available | Thursday | October 4, 2007 | 12:00 PM | DFCM 4110 State Office Bldg SLC, UT and the DFCM web site * |
| Mandatory Pre-bid Site Meeting | Thursday | October 11, 2007 | 10: 30 AM | Moab Regional Center 1165 So. Highway 191 Moab, Ut 84095 |
| Last Day to Submit Questions | Wednesday | October 17, 2007 | 12:00 PM | <i>Michael Ambre</i> – DFCM E-mail mambre@utah.gov Fax 801-538-3267 |
| Addendum Deadline (exception for bid delays) | Thursday | October 18, 2007 | 2:00 PM | DFCM web site * |
| Prime Contractors Turn In Bid and Bid Bond | Tuesday | October 23, 2007 | 3:00 PM | DFCM 4110 State Office Bldg SLC, UT |
| Sub-contractor List Due | Wednesday | October 24, 2007 | 3:00 PM | DFCM 4110 State Office Bldg SLC, UT Fax 801-538-3677 |
| Substantial Completion Date | Friday | February 15, 2008 | 5:00 PM | |

* **NOTE:** DFCM's web site address is <http://dfcm.utah.gov>



STATE OF UTAH - DEPARTMENT OF ADMINISTRATIVE SERVICES

Division of Facilities Construction and Management

DFCM

BID FORM

NAME OF BIDDER _____ DATE _____

To the Division of Facilities Construction and Management
4110 State Office Building
Salt Lake City, Utah 84114

The undersigned, responsive to the "Notice to Contractors" and in accordance with the "Instructions to Bidders", in compliance with your invitation for bids for the **Moab Regional Security Upgrade – Department of Human Services – Moab, Utah DFCM Project #07144400** and having examined the Contract Documents and the site of the proposed Work and being familiar with all of the conditions surrounding the construction of the proposed Project, including the availability of labor, hereby proposes to furnish all labor, materials and supplies as required for the Work in accordance with the Contract Documents as specified and within the time set forth and at the price stated below. This price is to cover all expenses incurred in performing the Work required under the Contract Documents of which this bid is a part:

I/We acknowledge receipt of the following Addenda: _____

For all work shown on the Drawings and described in the Specifications and Contract Documents, I/we agree to perform for the sum of:

_____ DOLLARS (\$_____) (In case of discrepancy, written amount shall govern)

I/We guarantee that the Work will be Substantially Complete by February 15, 2008, should I/we be the successful bidder, and agree to pay liquidated damages in the amount of **\$300.00** per day for each day after expiration of the Contract Time as stated in Article 3 of the Contractor's Agreement.

This bid shall be good for 45 days after bid opening.

Enclosed is a 5% bid bond, as required, in the sum of _____

The undersigned Contractor's License Number for Utah is _____.

Upon receipt of notice of award of this bid, the undersigned agrees to execute the contract within ten (10) days, unless a shorter time is specified in the Contract Documents, and deliver acceptable Performance and Payment bonds in the prescribed form in the amount of 100% of the Contract Sum for faithful performance of the contract.

The Bid Bond attached, in the amount not less than five percent (5%) of the above bid sum, shall become the property of the Division of Facilities Construction and Management as liquidated damages for delay and additional expense caused thereby in the event that the contract is not executed and/or acceptable 100% Performance and Payment bonds are not delivered within the time set forth.

Type of Organization:

(Corporation, Partnership, Individual, etc.)

Any request and information related to Utah Preference Laws:

Respectfully submitted,

Name of Bidder

ADDRESS:

Authorized Signature

INSTRUCTIONS TO BIDDERS

1. Drawings and Specifications, Other Contract Documents

Drawings and Specifications, as well as other available Contract Documents, may be obtained as stated in the Invitation to Bid.

2. Bids

Before submitting a bid, each contractor shall carefully examine the Contract Documents, shall visit the site of the Work; shall fully inform themselves as to all existing conditions and limitations; and shall include in the bid the cost of all items required by the Contract Documents. If the bidder observes that portions of the Contract Documents are at variance with applicable laws, building codes, rules, regulations or contain obvious erroneous or uncoordinated information, the bidder shall promptly notify the DFCM Representative and the necessary changes shall be accomplished by Addendum.

The bid, bearing original signatures, must be typed or handwritten in ink on the Bid Form provided in the procurement documents and submitted in a sealed envelope at the location specified by the Invitation to Bid prior to the deadline for submission of bids.

Bid bond security, in the amount of five percent (5%) of the bid, made payable to the Division of Facilities Construction and Management, shall accompany bid. **THE BID BOND MUST BE ON THE BID BOND FORM PROVIDED IN THE PROCUREMENT DOCUMENTS IN ORDER TO BE CONSIDERED AN ACCEPTABLE BID.**

If the bid bond security is submitted on a bid bond form other than DFCM's required bid bond form, and the bid security meets all other legal requirements, the bidder will be allowed to provide an acceptable bid bond by the close of business on the next business day following notification by DFCM of submission of a defective bid bond security. **NOTE: A cashier's check cannot be used as a substitute for a bid bond.**

3. Contract and Bond

The Contractor's Agreement will be in the form found in the specifications. The Contract Time will be as indicated in the bid. The successful bidder, simultaneously with the execution of the Contract Agreement, will be required to furnish a performance bond and a payment bond, both bearing original signatures, upon the forms provided in the procurement documents. The performance and payment bonds shall be for an amount equal to one hundred percent (100%) of the contract sum and secured from a company that meets the requirements specified in the requisite forms. Any bonding requirements for subcontractors will be specified in the Supplementary General Conditions.

4. Listing of Subcontractors

Listing of Subcontractors shall be as summarized in the “Instructions and Subcontractor’s List Form”, which are included as part of these Contract Documents. The Subcontractors List shall be delivered to DFCM or faxed to DFCM at (801)538-3677 within 24 hours of the bid opening. Requirements for listing additional subcontractors will be listed in the Contract Documents.

DFCM retains the right to audit or take other steps necessary to confirm compliance with requirements for the listing and changing of subcontractors. Any contractor who is found to not be in compliance with these requirements is subject to a debarment hearing and may be debarred from consideration for award of contracts for a period of up to three years.

5. Interpretation of Drawings and Specifications

If any person or entity contemplating submitting a bid is in doubt as to the meaning of any part of the drawings, specifications or other Contract Documents, such person shall submit to the DFCM Project Manager a request for an interpretation thereof. The person or entity submitting the request will be responsible for its prompt delivery. Any interpretation of the proposed documents will be made only by addenda posted on DFCM’s web site at <http://dfcm.utah.gov>. Neither the DFCM nor A/E will be responsible for any other explanations or interpretations of the proposed documents. A/E shall be deemed to refer to the architect or engineer hired by DFCM as the A/E or Consultant for the Project.

6. Addenda

Addenda will be posted on DFCM’s web site at <http://dfcm.utah.gov>. Contractors are responsible for obtaining information contained in each addendum from the web site. Addenda issued prior to the submittal deadline shall become part of the bidding process and must be acknowledged on the bid form. Failure to acknowledge addenda may result in disqualification from bidding.

7. Award of Contract

The Contract will be awarded as soon as possible to the lowest, responsive and responsible bidder, based on the lowest combination of base bid and acceptable prioritized alternates, provided the bid is reasonable, is in the interests of the State of Utah to accept and after applying the Utah Preference Laws in U.C.A. Title 63, Chapter 56. DFCM reserves the right to waive any technicalities or formalities in any bid or in the bidding. Alternates will be accepted on a prioritized basis with Alternate 1 being highest priority, Alternate 2 having second priority, etc.

8. DFCM Contractor Performance Rating

As a contractor completes each DFCM project, DFCM, the architect/engineer and the using agency will evaluate project performance based on the enclosed “DFCM Contractor Performance Rating” form. The ratings issued on this project will not affect this project but may affect the award on future projects.

9. Licensure

The Contractor shall comply with and require all of its subcontractors to comply with the license laws as required by the State of Utah.

10. Right to Reject Bids

DFCM reserves the right to reject any or all Bids.

11. Time is of the Essence

Time is of the essence in regard to all the requirements of the Contract Documents.

12. Withdrawal of Bids

Bids may be withdrawn on written request received from bidder prior to the time fixed for opening. Negligence on the part of the bidder in preparing the bid confers no right for the withdrawal of the bid after it has been opened.

13. Product Approvals

Where reference is made to one or more proprietary products in the Contract Documents, but restrictive descriptive materials of one or more manufacturer(s) is referred to in the Contract Documents, the products of other manufacturers will be accepted, provided they equal or exceed the standards set forth in the drawings and specifications and are compatible with the intent and purpose of the design, subject to the written approval of the A/E. Such written approval must occur prior to the deadline established for the last scheduled addenda to be issued. The A/E's written approval will be in an issued addendum. If the descriptive material is not restrictive, the products of other manufacturers specified will be accepted without prior approval provided they are compatible with the intent and purpose of the design as determined by the A/E.

14. Financial Responsibility of Contractors, Subcontractors and Sub-subcontractors

Contractors shall respond promptly to any inquiry in writing by DFCM to any concern of financial responsibility of the contractor, subcontractor or sub-subcontractor.

15. Debarment

By submitting a bid, the Contractor certifies that neither it nor its principals, including project and site managers, have been, or are under consideration for, debarment or suspension, or any action that would exclude such from participation in a construction contract by any governmental department or agency. If the Contractor cannot certify this statement, attach to the bid a detailed written explanation which must be reviewed and approved by DFCM as part of the requirements for award of the Project.

BID BOND

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL PERSONS BY THESE PRESENTS:

That _____ hereinafter referred to as the "Principal," and _____, a corporation organized and existing under the laws of the State of _____, with its principal office in the City of _____ and authorized to transact business in this State and U. S. Department of the Treasury Listed, (Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies); hereinafter referred to as the "Surety," are held and firmly bound unto the STATE OF UTAH, hereinafter referred to as the "Obligee," in the amount of \$ _____ (5% of the accompanying bid), being the sum of this Bond to which payment the Principal and Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents.

THE CONDITION OF THIS OBLIGATION IS SUCH that whereas the Principal has submitted to Obligee the accompanying bid incorporated by reference herein, dated as shown, to enter into a contract in writing for the _____ Project.

NOW, THEREFORE, THE CONDITION OF THE ABOVE OBLIGATION IS SUCH, that if the said principal does not execute a contract and give bond to be approved by the Obligee for the faithful performance thereof within ten (10) days after being notified in writing of such contract to the principal, then the sum of the amount stated above will be forfeited to the State of Utah as liquidated damages and not as a penalty; if the said principal shall execute a contract and give bond to be approved by the Obligee for the faithful performance thereof within ten (10) days after being notified in writing of such contract to the Principal, then this obligation shall be null and void. It is expressly understood and agreed that the liability of the Surety for any and all defaults of the Principal hereunder shall be the full penal sum of this Bond. The Surety, for value received, hereby stipulates and agrees that obligations of the Surety under this Bond shall be for a term of sixty (60) days from actual date of the bid opening.

PROVIDED, HOWEVER, that this Bond is executed pursuant to provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended, and all liabilities on this Bond shall be determined in accordance with said provisions to same extent as if it were copied at length herein.

IN WITNESS WHEREOF, the above bounden parties have executed this instrument under their several seals on the date indicated below, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

DATED this _____ day of _____, 20_____.

Principal's name and address (if other than a corporation):

By: _____

Title: _____

Principal's name and address (if a corporation):

By: _____

Title: _____
(Affix Corporate Seal)

Surety's name and address:

STATE OF _____)
COUNTY OF _____) ss.

By: _____
Attorney-in-Fact (Affix Corporate Seal)

On this ____ day of _____, 20_____, personally appeared before me _____, whose identity is personally known to me or proved to me on the basis of satisfactory evidence, and who, being by me duly sworn, did say that he/she is the Attorney-in-fact of the above-named Surety Company, and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations, and that he/she acknowledged to me that as Attorney-in-fact executed the same.

Subscribed and sworn to before me this _____ day of _____, 20_____.

My Commission Expires: _____

Resides at: _____

Agency: _____
Agent: _____
Address: _____
Phone: _____

NOTARY PUBLIC

Approved As To Form: May 25, 2005
By Alan S. Bachman, Asst Attorney General

**Division of Facilities Construction and****INSTRUCTIONS AND SUBCONTRACTORS LIST FORM**

The three low bidders, as well as all other bidders that desire to be considered, are required by law to submit to DFCM within 24 hours of bid opening a list of **ALL** first-tier subcontractors, including the subcontractor's name, bid amount and other information required by Building Board Rule and as stated in these Contract Documents, on the following basis:

PROJECTS UNDER \$500,000 - ALL SUBS \$20,000 OR OVER MUST BE LISTED
PROJECTS \$500,000 OR MORE - ALL SUBS \$35,000 OR OVER MUST BE LISTED

- Any additional subcontractors identified in the bid documents shall also be listed.
- The DFCM Director may not consider any bid submitted by a bidder if the bidder fails to submit a subcontractor list meeting the requirements of State law.
- List subcontractors for base bid as well as the impact on the list that the selection of any alternate may have.
- Bidder may not list more than one subcontractor to perform the same work.
- Bidder must list "Self" if performing work itself.

LICENSURE:

The subcontractor's name, the type of work, the subcontractor's bid amount, and the subcontractor's license number as issued by DOPL, if such license is required under Utah Law, shall be listed. Bidder shall certify that all subcontractors, required to be licensed, are licensed as required by State law. A subcontractor includes a trade contractor or specialty contractor and does not include suppliers who provide only materials, equipment, or supplies to a contractor or subcontractor.

BIDDER LISTING 'SELF' AS PERFORMING THE WORK:

Any bidder that is properly licensed for the particular work and intends to perform that work itself in lieu of a subcontractor that would otherwise be required to be on the subcontractor list, must insert the term 'Self' for that category on the subcontractor list form. Any listing of 'Self' on the sublist form shall also include the amount allocated for that work.

'SPECIAL EXCEPTION':

A bidder may list 'Special Exception' in place of a subcontractor when the bidder intends to obtain a subcontractor to perform the work at a later date because the bidder was unable to obtain a qualified or reasonable bid under the provisions of U.C.A. Section 63A-5-208(4). The bidder shall insert the term 'Special Exception' for that category of work, and shall provide documentation with the subcontractor list describing the bidder's efforts to obtain a bid of a qualified subcontractor at a reasonable cost and why the bidder was unable to obtain a qualified subcontractor bid. The Director must find that the bidder complied in good faith with State law requirements for any 'Special Exception' designation, in order for the bid to be considered. If awarded the contract, the Director shall supervise the bidder's efforts to obtain a qualified subcontractor bid. The amount of the awarded contract may not be adjusted to reflect the actual amount of the subcontractor's bid. Any listing of 'Special Exception' on the sublist form shall also include amount allocated for that work.

INSTRUCTIONS AND SUBCONTRACTORS LIST FORM
Page No. 2

GROUND FOR DISQUALIFICATION:

The Director may not consider any bid submitted by a bidder if the bidder fails to submit a subcontractor list meeting the requirements of State law. Director may withhold awarding the contract to a particular bidder if one or more of the proposed subcontractors are considered by the Director to be unqualified to do the Work or for such other reason in the best interest of the State of Utah. Notwithstanding any other provision in these instructions, if there is a good faith error on the sublist form, at the sole discretion of the Director, the Director may provide notice to the contractor and the contractor shall have 24 hours to submit the correction to the Director. If such correction is submitted timely, then the sublist requirements shall be considered met.

CHANGES OF SUBCONTRACTORS SPECIFICALLY IDENTIFIED ON SUBLIST FORM:

Subsequent to twenty-four hours after the bid opening, the contractor may change its listed subcontractors only after receiving written permission from the Director based on complying with all of the following criteria.

- (1) The contractor has established in writing that the change is in the best interest of the State and that the contractor establishes an appropriate reason for the change, which may include, but not is not limited to, the following reasons: the original subcontractor has failed to perform, or is not qualified or capable of performing, and/or the subcontractor has requested in writing to be released.
- (2) The circumstances related to the request for the change do not indicate any bad faith in the original listing of the subcontractors.
- (3) Any requirement set forth by the Director to ensure that the process used to select a new subcontractor does not give rise to bid shopping.
- (4) Any increase in the cost of the subject subcontractor work is borne by the contractor.
- (5) Any decrease in the cost of the subject subcontractor work shall result in a deductive change order being issued for the contract for such decreased amount.
- (6) The Director will give substantial weight to whether the subcontractor has consented in writing to being removed unless the Contractor establishes that the subcontractor is not qualified for the work.

EXAMPLE:

Example of a list where there are only four subcontractors:

| TYPE OF WORK | SUBCONTRACTOR, "SELF" OR "SPECIAL EXCEPTION" | SUBCONTRACTOR BID AMOUNT | CONT. LICENSE # |
|-------------------------|---|-----------------------------|--|
| ELECTRICAL | ABCD Electric Inc. | \$350,000.00 | 123456789000 |
| LANDSCAPING | "Self" | 300,000.00 | 123456789000 |
| CONCRETE (ALTERNATE #1) | XYZ Concrete Inc | 298,000.00 | 987654321000 |
| MECHANICAL | "Special Exception" (attach documentation) | Fixed at: 350,000.00 | (TO BE PROVIDED AFTER OBTAINING SUBCONTRACTOR) |

**PURSUANT TO STATE LAW - SUBCONTRACTOR BID AMOUNTS CONTAINED IN THIS
SUBCONTRACTOR LIST SHALL NOT BE DISCLOSED UNTIL THE CONTRACT HAS BEEN AWARDED.**

**SUBCONTRACTORS LIST**

FAX TO 801-538-3677

PROJECT TITLE: _____

Caution: You must read and comply fully with instructions.

| TYPE OF WORK | SUBCONTRACTOR, "SELF" OR "SPECIAL EXCEPTION" | SUBCONTRACTOR BID AMOUNT | CONT. LICENSE # |
|--------------|---|-----------------------------|-----------------|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

We certify that:

1. This list includes all subcontractors as required by the instructions, including those related to the base bid as well as any alternates.
2. We have listed "Self" or "Special Exception" in accordance with the instructions.
3. All subcontractors are appropriately licensed as required by State law.

FIRM: _____

DATE: _____

SIGNED BY: _____

NOTICE: FAILURE TO SUBMIT THIS FORM, PROPERLY COMPLETED AND SIGNED, AS REQUIRED IN THESE CONTRACT DOCUMENTS, SHALL BE GROUNDS FOR DFCMS REFUSAL TO ENTER INTO A WRITTEN CONTRACT WITH BIDDER. ACTION MAY BE TAKEN AGAINST BIDDERS BID BOND AS DEEMED APPROPRIATE BY DFCM. ATTACH A SECOND PAGE IF NECESSARY.

FUGITIVE DUST PLAN

The Contractor will fill out the form and file the original with the Division of Air Quality and a copy of the form with the Division of Facilities Construction & Management, prior to the issuance of any notice to proceed.

The Contractor will be fully responsible for compliance with the Fugitive Dust Control Plan, including the adequacy of the plan, any damages, fines, liability, and penalty or other action that results from noncompliance.

Utah Division of Air Quality

April 20, 1999

**GUIDANCE THAT MUST BE CONSIDERED IN DEVELOPING AND SUBMITTING A
DUST CONTROL PLAN FOR COMPLIANCE WITH R307-309-3, 4, 5, 6, 7**

Source Information:

1. Name of your operation (source): provide a name if the source is a construction site.
2. Address or location of your operation or construction site.
3. UTM coordinates or Longitude/Latitude of stationary emission points at your operation.
4. Lengths of the project, if temporary (time period).
5. Description of process (include all sources of dust and fugitive dust). Please, if necessary, use additional sheets of paper for this description. Be sure to mark it as an attachment.
6. Type of material processed or disturbed.
7. Amount of material processed (tons per year, tons per month, lbs./hr., and applicable units).

8. Destination of product (where will the material produced be used or transported, be specific, provide address or specific location), information needed for temporary relocation applicants.
9. Identify the individual who is responsible for the implementation and maintenance of fugitive dust control measures. List name(s), position(s) and telephone number(s).
10. List, and attach copies of any contract lease, liability agreement with other companies that may, or will, be responsible for dust control on site or on the project.

Description of Fugitive Dust Emission Activities
(Things to consider in addressing fugitive dust control strategies.)

1. Type of activities (drilling and blasting, road construction, development construction, earth moving and excavation, handling and hauling materials, cleaning and leveling, etc).
2. List type of equipment generating the fugitive dust.
3. Diagram the location of each activity or piece of equipment on site. Please attach the diagram.
4. Provide pictures or drawings of each activity. Include a drawing of the unpaved/paved road network used to move loads “on” and “off” property.
5. Vehicle miles travels on unpaved roads associated with the activity (average speed).
6. Type of dust emitted at each source (coal, cement, sand, soil, clay, dust, etc.)
7. Estimate the size of the release area at which the activity occurs (square miles). For haul or dirt roads include total miles of road in use during the activity.

Description of Fugitive Dust Emission Controls on Site

Control strategies must be designed to meet 20% opacity or less on site (a lesser opacity may be defined by Approval Order conditions or federal requirements such as NSPS), and control strategies must prevent exceeding 10% opacity from fugitive dust at the property boundary (site boundary) for compliance with R307-309-3.

1. Types of ongoing emission controls proposed for each activity, each piece of equipment, and haul roads.
2. Types of additional dust controls proposed for bare, exposed surfaces (chemical stabilization, synthetic cover, wind breaks, vegetative cover, etc).
3. Method of application of dust suppressant.
4. Frequency of application of dust suppressant.
5. Explain what triggers the use of a special control measure other than routine measures already in place, such as covered loads or measures covered by a permit condition (increase in opacity, high winds, citizen complaints, dry conditions, etc).
6. Explain in detail what control strategies/measures will be implemented off-hours, i.e., Saturdays/Sundays/Holidays, as well as 6 PM to 6 AM each day.

Description of Fugitive Dust Control Off-site

Prevent, to the maximum extent possible, deposition of materials, which may create fugitive dust on public and private paved roads in compliance with R307-309-5, 6, 7.

1. Types of emission controls initiated by your operation that are in place “off” property (application of water, covered loads, sweeping roads, vehicle cleaning, etc.).

2. Proposed remedial controls that will be initiated promptly if materials, which may create fugitive dust, are deposited on public and private paved roads.

Submit the Dust Control Plan to:

Executive Secretary
Utah Air Quality Board
POB 144820
15 North 1950 West
Salt Lake City, Utah 84114-4820

Phone: (801) 536-4000
FAX: (801) 536-4099

Fugitive Dust Control Plan Violation Report

When a source is found in violation of R307-309-3 or in violation of the Fugitive Dust Control Plan, the source must submit a report to the Executive Secretary within 15 days after receiving a Notice of Violation. The report must include the following information:

1. Name and address of dust source.
2. Time and duration of dust episode.
3. Meteorological conditions during the dust episode.
4. Total number and type of fugitive dust activities and dust producing equipment within each operation boundary. If no change has occurred from the existing dust control plan, the source should state that the activity/equipment is the same.
5. Fugitive dust activities or dust producing equipment that caused a violation of R-307-309-3 or the source's dust control plan.
6. Reasons for failing to control dust from the dust generating activity or equipment.
7. New and/or additional fugitive dust control strategies necessary to achieve compliance with R307-309-3, 4, 5, 6, or 7.
8. If it can not be demonstrated that the current approved Dust Control Plan can result in compliance with R307-309-3 through 7, the Dust Control Plan must be revised so as to demonstrate compliance with 307-309-3 through 7. Within 30 days of receiving a fugitive dust Notice of Violation, the source must submit the revised Plan to the Executive Secretary for review and approval.

Submit the Dust Control Plan to:

| | |
|---------------------------------|-----------------------|
| Executive Secretary | Phone: (801) 536-4000 |
| Utah Air Quality Board | FAX: (801) 536-4099 |
| POB 144820 | |
| 15 North 1950 West | |
| Salt Lake City, Utah 84114-4820 | |

Attachments: DFCM Form FDR R-307-309, Rule 307-309

CONTRACTOR'S AGREEMENT

FOR:

THIS CONTRACTOR'S AGREEMENT, made and entered into this ____ day of _____, 20__, by and between the DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT, hereinafter referred to as "DFCM", and _____, incorporated in the State of _____ and authorized to do business in the State of Utah, hereinafter referred to as "Contractor", whose address is _____.

WITNESSETH: WHEREAS, DFCM intends to have Work performed at _____.

WHEREAS, Contractor agrees to perform the Work for the sum stated herein.

NOW, THEREFORE, DFCM and Contractor for the consideration provided in this Contractor's Agreement, agree as follows:

ARTICLE 1. SCOPE OF WORK. The Work to be performed shall be in accordance with the Contract Documents prepared by _____ and entitled "_____"

The DFCM General Conditions ("General Conditions") dated May 25, 2005 on file at the office of DFCM and available on the DFCM website, are hereby incorporated by reference as part of this Agreement and are included in the specifications for this Project. All terms used in this Contractor's Agreement shall be as defined in the Contract Documents, and in particular, the General Conditions.

The Contractor Agrees to furnish labor, materials and equipment to complete the Work as required in the Contract Documents which are hereby incorporated by reference. It is understood and agreed by the parties hereto that all Work shall be performed as required in the Contract Documents and shall be subject to inspection and approval of DFCM or its authorized representative. The relationship of the Contractor to the DFCM hereunder is that of an independent Contractor.

ARTICLE 2. CONTRACT SUM. The DFCM agrees to pay and the Contractor agrees to accept in full performance of this Contractor's Agreement, the sum of _____ DOLLARS AND NO CENTS (\$_____.00), which is the base bid, and which sum also includes the cost of a 100% Performance Bond and a 100%

CONTRACTOR'S AGREEMENT
PAGE NO. 2

Payment Bond as well as all insurance requirements of the Contractor. Said bonds have already been posted by the Contractor pursuant to State law. The required proof of insurance certificates have been delivered to DFCM in accordance with the General Conditions before the execution of this Contractor's Agreement.

ARTICLE 3. TIME OF COMPLETION AND DELAY REMEDY. The Work shall be Substantially Complete by _____. Contractor agrees to pay liquidated damages in the amount of \$_____ per day for each day after expiration of the Contract Time until the Contractor achieves Substantial Completion in accordance with the Contract Documents, if Contractor's delay makes the damages applicable. The provision for liquidated damages is: (a) to compensate the DFCM for delay only; (b) is provided for herein because actual damages can not be readily ascertained at the time of execution of this Contractor's Agreement; (c) is not a penalty; and (d) shall not prevent the DFCM from maintaining Claims for other non-delay damages, such as costs to complete or remedy defective Work.

No action shall be maintained by the Contractor, including its or Subcontractor or suppliers at any tier, against the DFCM or State of Utah for damages or other claims due to losses attributable to hindrances or delays from any cause whatsoever, including acts and omissions of the DFCM or its officers, employees or agents, except as expressly provided in the General Conditions. The Contractor may receive a written extension of time, signed by the DFCM, in which to complete the Work under this Contractor's Agreement in accordance with the General Conditions.

ARTICLE 4. CONTRACT DOCUMENTS. The Contract Documents consist of this Contractor's Agreement, the Conditions of the Contract (DFCM General Conditions, Supplementary and other Conditions), the Drawings, Specifications, Addenda and Modifications. The Contract Documents shall also include the bidding documents, including the Invitation to Bid, Instructions to Bidders/ Proposers and the Bid/Proposal, to the extent not in conflict therewith and other documents and oral presentations that are documented as an attachment to the contract.

All such documents are hereby incorporated by reference herein. Any reference in this Contractor's Agreement to certain provisions of the Contract Documents shall in no way be construed as to lessen the importance or applicability of any other provisions of the Contract Documents.

ARTICLE 5. PAYMENT. The DFCM agrees to pay the Contractor from time to time as the Work progresses, but not more than once each month after the date of Notice to Proceed, and only upon Certificate of the A/E for Work performed during the preceding calendar month, ninety-five percent (95%) of the value of the labor performed and ninety-five percent (95%) of the value of materials furnished in place or on the site. The Contractor agrees to furnish to the DFCM invoices for materials purchased and on the site but not installed, for which the Contractor requests payment and agrees to

safeguard and protect such equipment or materials and is responsible for safekeeping thereof and if such be stolen, lost or destroyed, to replace same.

Such evidence of labor performed and materials furnished as the DFCM may reasonably require shall be supplied by the Contractor at the time of request for Certificate of Payment on account. Materials for which payment has been made cannot be removed from the job site without DFCM's written approval. Five percent (5%) of the earned amount shall be retained from each monthly payment. The retainage, including any additional retainage imposed and the release of any retainage, shall be in accordance with UCA 13-8-5 as amended. Contractor shall also comply with the requirements of UCA 13-8-5, including restrictions of retainage regarding subcontractors and the distribution of interest earned on the retention proceeds. The DFCM shall not be responsible for enforcing the Contractor's obligations under State law in fulfilling the retention law requirements with subcontractors at any tier.

ARTICLE 6. INDEBTEDNESS. Before final payment is made, the Contractor must submit evidence satisfactory to the DFCM that all payrolls, materials bills, subcontracts at any tier and outstanding indebtedness in connection with the Work have been properly paid. Final Payment will be made after receipt of said evidence, final acceptance of the Work by the DFCM as well as compliance with the applicable provisions of the General Conditions.

Contractor shall respond immediately to any inquiry in writing by DFCM as to any concern of financial responsibility and DFCM reserves the right to request any waivers, releases or bonds from Contractor in regard to any rights of Subcontractors (including suppliers) at any tier or any third parties prior to any payment by DFCM to Contractor.

ARTICLE 7. ADDITIONAL WORK. It is understood and agreed by the parties hereto that no money will be paid to the Contractor for additional labor or materials furnished unless a new contract in writing or a Modification hereof in accordance with the General Conditions and the Contract Documents for such additional labor or materials has been executed. The DFCM specifically reserves the right to modify or amend this Contractor's Agreement and the total sum due hereunder either by enlarging or restricting the scope of the Work.

ARTICLE 8. INSPECTIONS. The Work shall be inspected for acceptance in accordance with the General Conditions.

ARTICLE 9. DISPUTES. Any dispute, PRE or Claim between the parties shall be subject to the provisions of Article 7 of the General Conditions. DFCM reserves all rights to pursue its rights and remedies as provided in the General Conditions.

ARTICLE 10. TERMINATION, SUSPENSION OR ABANDONMENT. This Contractor's Agreement may be terminated, suspended or abandoned in accordance with the General Conditions.

ARTICLE 11. DFCM'S RIGHT TO WITHHOLD CERTAIN AMOUNT AND MAKE USE THEREOF. The DFCM may withhold from payment to the Contractor such amount as, in DFCM's judgment, may be necessary to pay just claims against the Contractor or Subcontractor at any tier for labor and services rendered and materials furnished in and about the Work. The DFCM may apply such withheld amounts for the payment of such claims in DFCM's discretion. In so doing, the DFCM shall be deemed the agent of Contractor and payment so made by the DFCM shall be considered as payment made under this Contractor's Agreement by the DFCM to the Contractor. DFCM shall not be liable to the Contractor for any such payment made in good faith. Such withholdings and payments may be made without prior approval of the Contractor and may be also be prior to any determination as a result of any dispute, PRE, Claim or litigation.

ARTICLE 12. INDEMNIFICATION. The Contractor shall comply with the indemnification provisions of the General Conditions.

ARTICLE 13. SUCCESSORS AND ASSIGNMENT OF CONTRACT. The DFCM and Contractor, respectively bind themselves, their partners, successors, assigns and legal representatives to the other party to this Agreement, and to partners, successors, assigns and legal representatives of such other party with respect to all covenants, provisions, rights and responsibilities of this Contractor's Agreement. The Contractor shall not assign this Contractor's Agreement without the prior written consent of the DFCM, nor shall the Contractor assign any moneys due or to become due as well as any rights under this Contractor's Agreement, without prior written consent of the DFCM.

ARTICLE 14. RELATIONSHIP OF THE PARTIES. The Contractor accepts the relationship of trust and confidence established by this Contractor's Agreement and covenants with the DFCM to cooperate with the DFCM and A/E and use the Contractor's best skill, efforts and judgment in furthering the interest of the DFCM; to furnish efficient business administration and supervision; to make best efforts to furnish at all times an adequate supply of workers and materials; and to perform the Work in the best and most expeditious and economic manner consistent with the interests of the DFCM.

ARTICLE 15. AUTHORITY TO EXECUTE AND PERFORM AGREEMENT. Contractor and DFCM each represent that the execution of this Contractor's Agreement and the performance thereunder is within their respective duly authorized powers.

ARTICLE 16. ATTORNEY FEES AND COSTS. Except as otherwise provided in the dispute resolution provisions of the General Conditions, the prevailing party shall be entitled to reasonable attorney fees and costs incurred in any action in the District Court and/or appellate body to enforce this Contractor's Agreement or recover damages or any other action as a result of a breach thereof.

CONTRACTOR'S AGREEMENT
PAGE NO. 5

IN WITNESS WHEREOF, the parties hereto have executed this Contractor's Agreement on the day and year stated hereinabove.

CONTRACTOR: _____

Signature Date

Title: _____

State of _____)
County of _____)

Please type/print name clearly

On this ____ day of _____, 20____, personally appeared before me, _____, whose identity is personally known to me (or proved to me on the basis of satisfactory evidence) and who by me duly sworn (or affirmed), did say that he (she) is the _____ (title or office) of the firm and that said document was signed by him (her) in behalf of said firm.

(SEAL)

Notary Public

My Commission Expires _____

APPROVED AS TO AVAILABILITY
OF FUNDS:

David D. Williams, Jr. Date
DFCM Administrative Services Director

**DIVISION OF FACILITIES
CONSTRUCTION AND MANAGEMENT**

- Manager Date
Capital Development/Improvements

APPROVED AS TO FORM:
ATTORNEY GENERAL
November 30, 2006
By: Alan S. Bachman
Asst Attorney General

APPROVED FOR EXPENDITURE:

Division of Finance Date

PERFORMANCE BOND
(Title 63, Chapter 56, U. C. A. 1953, as Amended)

That _____ hereinafter referred to as the "Principal" and _____, a corporation organized and existing under the laws of the State of _____, with its principal office in the City of _____ and authorized to transact business in this State and U. S. Department of the Treasury Listed (Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies); hereinafter referred to as the "Surety," are held and firmly bound unto the State of Utah, hereinafter referred to as the "Obligee," in the amount of _____ DOLLARS (\$ _____) for the payment whereof, the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain written Contract with the Obligee, dated the _____ day of _____, 20____, to construct _____ in the County of _____, State of Utah, Project No. _____, for the approximate sum of _____ Dollars (\$ _____), which Contract is hereby incorporated by reference herein.

NOW, THEREFORE, the condition of this obligation is such that if the said Principal shall faithfully perform the Contract in accordance with the Contract Documents including, but not limited to, the Plans, Specifications and conditions thereof, the one year performance warranty, and the terms of the Contract as said Contract may be subject to Modifications or changes, then this obligation shall be void; otherwise it shall remain in full force and effect.

No right of action shall accrue on this bond to or for the use of any person or corporation other than the state named herein or the heirs, executors, administrators or successors of the Owner.

The parties agree that the dispute provisions provided in the Contract Documents apply and shall constitute the sole dispute procedures of the parties.

PROVIDED, HOWEVER, that this Bond is executed pursuant to the Provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended, and all liabilities on this Bond shall be determined in accordance with said provisions to the same extent as if it were copied at length herein.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument this _____ day of _____, 20____.

WITNESS OR ATTESTATION:

PRINCIPAL:

By: _____

(Seal)

Title: _____

WITNESS OR ATTESTATION:

SURETY:

By: _____

Attorney-in-Fact (Seal)

STATE OF _____)
) ss.
COUNTY OF _____)

On this _____ day of _____, 20____, personally appeared before me _____, whose identity is personally known to me or proved to me on the basis of satisfactory evidence, and who, being by me duly sworn, did say that he/she is the Attorney in-fact of the above-named Surety Company and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations, and that he/she acknowledged to me that as Attorney-in-fact executed the same.

Subscribed and sworn to before me this _____ day of _____, 20____.

My commission expires: _____

Resides at: _____

NOTARY PUBLIC

Agency: _____
Agent: _____
Address: _____
Phone: _____

Approved As To Form: May 25, 2005
By Alan S. Bachman, Asst Attorney General

PAYMENT BOND

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL PERSONS BY THESE PRESENTS:

That _____ hereinafter referred to as the "Principal," and _____, a corporation organized and existing under the laws of the State of _____ authorized to do business in this State and U. S. Department of the Treasury Listed (Circular 570, Companies Holding Certificates of Authority as Acceptable Securities on Federal Bonds and as Acceptable Reinsuring Companies); with its principal office in the City of _____, hereinafter referred to as the "Surety," are held and firmly bound unto the State of Utah hereinafter referred to as the "Obligee," in the amount of _____ Dollars (\$ _____) for the payment whereof, the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain written Contract with the Obligee, dated the _____ day of _____, 20____, to construct _____ in the County of _____, State of Utah, Project No. _____ for the approximate sum of _____ Dollars (\$ _____), which contract is hereby incorporated by reference herein.

NOW, THEREFORE, the condition of this obligation is such that if the said Principal shall pay all claimants supplying labor or materials to Principal or Principal's Subcontractors in compliance with the provisions of Title 63, Chapter 56, of Utah Code Annotated, 1953, as amended, and in the prosecution of the Work provided for in said Contract, then, this obligation shall be void; otherwise it shall remain in full force and effect.

That said Surety to this Bond, for value received, hereby stipulates and agrees that no changes, extensions of time, alterations or additions to the terms of the Contract or to the Work to be performed thereunder, or the specifications or drawings accompanying same shall in any way affect its obligation on this Bond, and does hereby waive notice of any such changes, extensions of time, alterations or additions to the terms of the Contract or to the Work or to the specifications or drawings and agrees that they shall become part of the Contract Documents.

PROVIDED, HOWEVER, that this Bond is executed pursuant to the provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended, and all liabilities on this Bond shall be determined in accordance with said provisions to the same extent as if it were copied at length herein.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument this _____ day of _____, 20____.

WITNESS OR ATTESTATION:

PRINCIPAL:

By: _____

(Seal)

Title: _____

WITNESS OR ATTESTATION:

SURETY:

By: _____

Attorney-in-Fact (Seal)

STATE OF _____)

) ss.

COUNTY OF _____)

On this _____ day of _____, 20____, personally appeared before me _____, whose identity is personally known to me or proved to me on the basis of satisfactory evidence, and who, being by me duly sworn, did say that he/she is the Attorney-in-fact of the above-named Surety Company, and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations, and that he/she acknowledged to me that as Attorney-in-fact executed the same.

Subscribed and sworn to before me this _____ day of _____, 20____.

My commission expires: _____

Resides at: _____

NOTARY PUBLIC

Agency: _____
Agent: _____
Address: _____
Phone: _____

Approved As To Form: May 25, 2005
By Alan S. Bachman, Asst Attorney General



Division of Facilities Construction and Management

CHANGE ORDER # _____

CONTRACTOR: _____

AGENCY OR INSTITUTION: _____

PROJECT NAME: _____

PROJECT NUMBER: _____

CONTRACT NUMBER: _____

ARCHITECT: _____

DATE: _____

| CONSTRUCTION CHANGE DIRECTIVE NO. | PROPOSAL REQUEST NO. | AMOUNT | | DAYS | |
|---|----------------------------|----------|----------|----------|----------|
| | | INCREASE | DECREASE | INCREASE | DECREASE |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

| | Amount | Days | Date |
|------------------------------|--------|------|------|
| ORIGINAL CONTRACT | | | |
| TOTAL PREVIOUS CHANGE ORDERS | | | |
| TOTAL THIS CHANGE ORDER | | | |
| ADJUSTED CONTRACT | | | |

DFCM and Contractor agree that the terms, contract sum, scope of the Work and time specified in this Change Order shall constitute the full accord and satisfaction, and complete adjustment to the Contract and includes all direct and indirect costs and effects related to, incidental to, and/or reasonably implied from such change in the contract terms, sum, scope of the Work and time.

Contractor: _____

Date

Architect/Engineer: _____

Date

Agency or Institution: _____

Date

DFCM: _____

Date

Funding Verification: _____

Date

Page ____ of ____ page(s)

30

CERTIFICATE OF SUBSTANTIAL COMPLETION

PROJECT _____ PROJECT NO: _____
AGENCY/INSTITUTION _____

AREA ACCEPTED

The Work performed under the subject Contract has been reviewed on this date and found to be Substantially Completed as defined in the General Conditions; including that the construction is sufficiently completed in accordance with the Contract Documents, as modified by any change orders agreed to by the parties, so that the State of Utah can occupy the Project or specified area of the Project for the use for which it is intended.

The DFCM - (Owner) accepts the Project or specified area of the Project as Substantially Complete and will assume full possession of the Project or specified area of the Project at _____ (time) on _____ (date).

The DFCM accepts the Project for occupancy and agrees to assume full responsibility for maintenance and operation, including utilities and insurance, of the Project subject to the itemized responsibilities and/or exceptions noted below:

The Owner acknowledges receipt of the following closeout and transition materials:

| | | | |
|--|--|---|--|
| <input type="checkbox"/> As-built Drawings | <input type="checkbox"/> O & M Manuals | <input type="checkbox"/> Warranty Documents | <input type="checkbox"/> Completion of Training Requirements |
|--|--|---|--|

A list of items to be completed or corrected (Punch List) is attached hereto. The failure to include an item on it does not alter the responsibility of the Contractor to complete all the Work in accordance with the Contract Documents, including authorized changes thereof. The amount of _____ (Twice the value of the punch list work) shall be retained to assure the completion of the punch list work.

The Contractor shall complete or correct the Work on the list of (Punch List) items appended hereto within _____ calendar days from the above date of issuance of this Certificate. The amount withheld pending completion of the list of items noted and agreed to shall be: \$ _____. If the list of items is not completed within the time allotted the Owner has the right to be compensated for the delays and/or complete the work with the help of independent contractor at the expense of the retained project funds. If the retained project funds are insufficient to cover the delay/completion damages, the Owner shall be promptly reimbursed for the balance of the funds needed to compensate the Owner.

by: _____
 CONTRACTOR (include name of firm) (Signature) DATE

by: _____
A/E (include name of firm) (Signature) DATE

USING INSTITUTION OR AGENCY

by: _____
(Signature) _____ DATE _____

by: _____

DFCM (Owner) (Signature) DATE


4110 State Office Building, Salt Lake City, Utah 84114 cc:
telephone 801-538-3018 • facsimile 801-538-3267 • <http://dfcm.utah.gov>

Parties Noted
DFCM, Director

Technical Specification For
Department of Human Services
Moab Regional Center Interior Remodel, Moab Utah
Division of Facilities Construction Management Project Number 07144400

28 September 2007

P+A Architects
821 Kensington Avenue
Salt Lake City, Utah 84105



| | |
|----------------|---|
| Section 09680 | CARPET |
| Section 09900 | PAINTING |
| DIVISION 10 | SPECIALTIES |
| Section 10100 | VISUAL DISPLAY BOARDS |
| DIVISION 11 | EQUIPMENT |
| NOT USED | NONE |
| DIVISION 12 | FURNISHINGS |
| NOT USED | NONE |
| DIVISION 13 | SPECIAL CONSTRUCTION |
| NOT USED | NONE |
| DIVISION 14 | CONVEYING SYSTEMS |
| NOT USED | NONE |
| DIVISION 15 | MECHANICAL SPECIFICATIONS |
| NOT USED | NONE |
| DIVISION 16 | ELECTRICAL SPECIFICATIONS |
| Section 16001 | ELECTRICAL GENERAL PROVISIONS |
| Section 16070 | ELECTRICAL CONNECTIONS FOR EQUIPMENT |
| Section 16072 | ELECTRICAL SUPPORT & SEISMIC RESTRAINTS |
| Section 16080 | ELECTRICAL DEMOLITION |
| Section 16110 | CONDUIT RACEWAYS |
| Section 16120 | CONDUCTORS & CABLES |
| Section 16135 | ELECTRICAL BOXES & FITTINGS |
| Section 16140 | WIRING DEVICES |
| Section 16180 | OVERCURRENT PROTECTIVE DEVICES |
| Section 16452 | GROUNDING |
| Section 16510 | INTERIOR AND EXTERIOR BUILDING LIGHTING |
| Section 16532 | FLOURESCENT EMERGENCY BALLASTS |
| Section 16740 | TELEPHONE/DATA SYSTEM |
| DIVISION 21 | PLUMBING SPECIFICATIONS |
| Section 211000 | WET PIPE FIRE SUPPRESSION SPRINKLERS AND PIPING |

SECTION 01010 - SUMMARY OF WORK

1.1 GENERAL

- A. The Project consists of interior demolition of existing spaces, ceiling systems, doors and frames as shown on construction documents. The general contractor will build new spaces as show on the construction documents. The project work includes gypsum board wall assemblies, painting, hollow metal doorframes and solid core wood doors, lay-in ceiling systems, new carpet, mechanical upgrades and electrical upgrades as shown on the architectural drawings.
 - 1. Project Location: 1165 South Highway 91, Moab, Utah
 - 2. Owner: State of Utah.
- B. Contract Documents, dated September 28th 2007, were prepared for the project by P+A architects. located at 821 East Kensington Avenue, Salt Lake City, Utah
- C. The Work will be constructed under a single prime contract.
- D. Use of the Site: Limit use of premises to areas indicated on construction documents. Do not disturb portions of the site beyond the areas indicated.
 - 1. Allow for Owner occupancy and use by the public.
 - 2. Keep driveways and entrances clear. Do not use these areas for parking or material storage. Schedule deliveries to minimize on-site storage of materials and equipment.

1.2 CONTRACTOR USE OF PREMISES

- A. General: During the construction period, the Contractor shall have use of the premises for construction operations as shown on construction documents. Parking and contractor staging at the site is limited and will be reviewed at the pre bid conference.
- B. Use of the Site: Limit use of the premises to work in areas indicated. Confine operations to areas within contract limits indicated. Do not disturb portions of the site beyond the areas in which the Work is indicated.
 - 1. Driveways and Entrances: Keep driveways and entrances serving the premises clear and available to other occupants and emergency vehicles at all times. Do not use these areas for parking or storage of materials. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
 - 2. The general contractor shall provide 72 hours notice prior to shutting down any mechanical or electrical items that affect other areas in the building.
 - 3. The general contractor shall provide protection of the existing elevator walls when using the elevators.
 - 4. All interior corridors are to remain clear during the construction process.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

5. The general contractors shall inform the owner, architect and D.F.C.M at least 36 hours prior to all work that will create sufficient noise that could disturb other classroom areas within the building.

END OF SECTION 01010

SECTION 01027 - APPLICATIONS FOR PAYMENT

1.1 GENERAL

- A. Coordinate the Schedule of Values and Applications for Payment with the Contractor's Construction Schedule, Submittal Schedule, and List of Subcontracts.
- B. Schedule of Values: Coordinate preparation of the Schedule of Values with preparation of the Contractor's Construction Schedule.
 - 1. Correlate line items in the Schedule of Values with other required administrative schedules and forms, including:
 - a. Contractor's Construction Schedule.
 - b. Application for Payment forms, including Continuation Sheets.
 - c. List of subcontractors.
 - d. List of products.
 - e. List of principal suppliers and fabricators.
 - f. Schedule of submittals.
 - 2. Submit the Schedule of Values at the earliest possible date but no later than 7 days before the date scheduled for submittal of the initial Applications for Payment.
- C. Format and Content: Use the Project Manual table of contents as a guide to establish the format for the Schedule of Values. Provide at least one line item for each Specification Section.
 - 1. Include the following Project identification:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 - 2. Arrange the Schedule of Values in tabular form with separate columns to indicate the following for each item listed:
 - a. Related Specification Section or Division.
 - b. Description of Work.
 - c. Name of subcontractor.
 - d. Name of manufacturer or fabricator.
 - e. Name of supplier.
 - f. Change Orders (numbers) that affect value.
 - g. Dollar value.
 - h. Percentage of Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
 - 3. Provide a breakdown of the Contract Sum in sufficient detail to facilitate evaluation of Applications for Payment. Break subcontract amounts down into several line items. Round amounts to nearest whole dollar; the total shall equal the Contract Sum.
 - 4. Provide a separate line item for each part of the Work where Applications for Payment may include materials or equipment, purchased or fabricated and stored, but not yet installed.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

5. Provide separate line items for initial cost of the materials, for each subsequent stage of completion, and for total installed value. .
 6. Show line items for indirect costs and margins on costs only when such items are listed individually in Applications for Payment. Each item in the Schedule of Values and Applications for Payment shall be complete. Include the total cost and proportionate share of general overhead and profit margin for each item.
 - a. Temporary facilities and items that are not direct cost of work-in-place may be shown as separate line items or distributed as general overhead expense.
 7. Update and resubmit the Schedule of Values when Change Orders or Construction Change Directives change the Contract Sum.
- D. Applications for Payment shall be consistent with previous applications and payments as certified by the Owner and paid for by the Owner.
- E. Payment-Application Times: Payment dates are indicated in the Agreement. The period covered by each application is the period indicated in the Agreement.
- F. Payment-Application Forms: Use AIA Document G702 and Continuation Sheets G703 as the form for Applications for Payment.
- G. Application Preparation: Complete every entry, including notarization and execution by a person authorized to sign on behalf of the Contractor. The owner will return incomplete applications without action.
1. Entries shall match data on the Schedule of Values and the Contractor's Construction Schedule. Use updated schedules if revisions were made.
 2. Include amounts of Change Orders and Construction Change Directives issued prior to the last day of the construction period covered by the application.
- H. Transmittal: Submit 3 executed original copies of each Application for Payment to the owner within 24 hours. One copy shall be complete, including waivers of lien and similar attachments.
1. Transmit each copy with a transmittal listing attachments and recording appropriate information related to the application.
- I. Waivers of Mechanics Lien: With each Application for Payment, submit waivers of lien from every entity who may file a lien arising out of the Contract and related to the Work covered by the payment.
1. Submit partial waivers on each item for the amount requested, prior to deduction for retainage, on each item.
 2. When an application shows completion of an item, submit final or full waivers.
 3. Submit each Application for Payment with Contractor's waiver of lien for the period of construction covered by the application.
 - a. Submit final Applications for Payment with final waivers from every entity involved with performance of the Work covered by the application who may file a lien.
 4. Waiver Forms: Submit waivers of lien on forms, and executed in a manner, acceptable to the Owner.
- J. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of the first Application for Payment include the following:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. List of subcontractors.
2. List of principal suppliers and fabricators.
3. Schedule of Values.
4. Contractor's Construction Schedule (preliminary if not final).
5. Submittal Schedule (preliminary if not final).
6. List of Contractor's staff assignments.
7. Copies of building permits.
8. Copies of licenses from governing authorities.
9. Certificates of insurance and insurance policies.
10. Performance and payment bonds.

K. Application for Payment at Substantial Completion: Following issuance of the Certificate of Substantial Completion, submit an Application for Payment. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.

1. Administrative actions and submittals that shall precede or coincide with this application include the following:
 - a. Occupancy permits.
 - b. Warranties and maintenance agreements.
 - c. Maintenance instructions.
 - d. Meter readings.
 - e. Changeover information related to Owner's occupancy.
 - f. Final cleaning.
 - g. Application for reduction of retainage and consent of surety.

L. Final Payment Application: Administrative actions and submittals that must precede or coincide with submittal of the final Application for Payment include the following:

1. Completion of Project closeout requirements.
2. Completion of items specified for completion after Substantial Completion.
3. Transmittal of Project construction records to the Owner.
4. Removal of temporary facilities and services.
5. Change of door locks to Owner's access.

1.2 PRODUCTS (Not Applicable)

1.3 EXECUTION (Not Applicable)

END OF SECTION 01027

SECTION 01040 - COORDINATION

1.1 GENERAL

- A. This Section includes requirements for coordinating construction operations including, but not necessarily limited to, the following:
1. Coordination drawings.
 2. Administrative and supervisory personnel.
 3. Cleaning and protection.

1.2 COORDINATION

- A. Coordinate construction to assure efficient and orderly installation of each part of the Work. Coordinate operations that depend on each other for proper installation, connection, and operation.
1. Schedule operations in the sequence required to obtain the best results where installation of one part depends on installation of other components, before or after its own installation.
 2. Coordinate installation of different components to assure maximum accessibility for maintenance, service, and repair.
 3. Make provisions to accommodate items scheduled for later installation.
- B. Where necessary, prepare memoranda for distribution to each party involved, outlining procedures required for coordination. Include such items as required notices and reports.
1. Prepare similar memoranda for the Owner and separate contractors where coordination of their work is required.
- C. Administrative Procedures: Coordinate scheduling and timing of required procedures with other activities to avoid conflicts and assure orderly progress. Such activities include, but are not limited to, the following:
1. Preparation of schedules.
 2. Delivery and processing of submittals.
 3. Progress meetings.
 4. Project closeout activities.
- D. Conservation: Coordinate construction to assure that operations are carried out with consideration for conservation of energy, water, and materials.
- E. Staff Names: Within 15 days of commencement of construction, submit a list of the Contractor's staff assignments, including the superintendent and other subcontractors at the Project. Identify individuals and their responsibilities. List their addresses and telephone numbers.

1.3 PRODUCTS (Not Applicable)

1.4 EXECUTION

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Inspection of Conditions: Require Installers of major components to inspect substrate and conditions under which Work is to be performed. Do not proceed until unsatisfactory conditions have been corrected.
- B. Clean and protect construction in progress and adjoining materials, during handling and installation. Apply protective covering to assure protection from damage.
- C. Clean and maintain completed construction as necessary through the construction period. Adjust and lubricate operable components to assure operability without damaging effects.
- D. Limiting Exposures: Supervise construction to assure that no part is subject to harmful, dangerous, or damaging exposure. Such exposures include, but are not limited to, the following:
 - 1. Excessive static or dynamic loading.
 - 2. Excessive internal or external pressures.
 - 3. Excessively high or low temperatures.
 - 4. Water or ice.
 - 5. Solvents and chemicals.
 - 6. Abrasion.
 - 7. Soiling, staining, and corrosion.
 - 8. Combustion.
 - 9. Wind.

END OF SECTION 01040

SECTION 01400 - QUALITY CONTROL

1.1 GENERAL

- A. Quality-control services include inspections, tests, and related actions, including reports performed by Contractor, by independent agencies, and by governing authorities.
- B. Contractor Responsibilities: Unless they are the responsibility of another entity, Contractor shall provide inspections and tests specified elsewhere and required by authorities having jurisdiction. Costs for these services are included in the Contract Sum.
 - 1. Where inspections and tests are the Contractor's responsibility, the Contractor shall employ and pay a qualified independent testing agency to perform these services. Costs for these services are included in the Contract Sum.
- C. Retesting: The Contractor is responsible for retesting where results of inspections and tests prove unsatisfactory and indicate noncompliance with requirements.
 - 1. The cost of retesting is the Contractor's responsibility where tests performed indicated noncompliance with requirements.
- D. Auxiliary Services: Cooperate with agencies performing inspections and tests. Provide auxiliary services as requested. Notify the agency in advance of operations to permit assignment of personnel. Auxiliary services include the following:
 - 1. Providing access to the Work.
 - 2. Furnishing incidental labor and facilities to assist inspections and tests.
 - 3. Taking adequate quantities of representative samples of materials that require testing or assisting the agency in taking samples.
 - 4. Providing facilities for storage and curing of test samples.
 - 5. Delivering samples to testing laboratories.
 - 6. Providing preliminary design mix proposed for use for materials mixes that require control by the testing agency.
 - 7. Providing security and protection of samples and test equipment.
- E. Duties of the Testing Agency: The testing agency shall cooperate with the owner and the Contractor in performing its duties. The agency shall provide qualified personnel to perform inspections and tests.
 - 1. The agency shall notify the owner and the Contractor of irregularities or deficiencies observed in the Work during performance of its services.
 - 2. The agency shall not release, revoke, alter, or enlarge requirements or approve or accept any portion of the Work.
 - 3. The agency shall not perform duties of the Contractor.
- F. Coordination: Coordinate activities to accommodate services with a minimum of delay. Avoid removing and replacing construction to accommodate inspections and tests.
 - 1. The Contractor is responsible for scheduling inspections, tests, taking samples, and similar activities.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

G. Submittals: The testing agency shall submit a certified written report, in duplicate, of each inspection and test to the Owner. If the Contractor is responsible for the service, submit a certified written report, in duplicate, of each inspection or test through the Contractor.

1. Submit additional copies of each report to the governing authority, when the authority so directs.
2. Report Data: Reports of each inspection, test, or similar service include, but are not limited to, the following:
 - a. Date of issue.
 - b. Project title and number.
 - c. Name, address, and telephone number of testing agency.
 - d. Dates and locations of samples and tests or inspections.
 - e. Names of individuals making the inspection or test.
 - f. Designation of the Work and test method.
 - g. Identification of product and Specification Section.
 - h. Complete inspection or test data.
 - i. Test results and an interpretation of test results.
 - j. Ambient conditions at the time of sample taking and testing.
 - k. Comments or professional opinion on whether inspected or tested Work complies with requirements.
 - l. Name and signature of laboratory inspector.
 - m. Recommendations on retesting.

H. Qualifications for Service Agencies: Engage inspection and testing service agencies that are prequalified as complying with the American Council of Independent Laboratories' "Recommended Requirements for Independent Laboratory Qualification" and that specialize in the types of inspections and tests to be performed.

1. Each agency shall be authorized by authorities having jurisdiction to operate in the state where the Project is located.

1.2 PRODUCTS (Not Applicable)

1.3 EXECUTION

- A. Repair and Protection: Upon completion of inspection, testing, and sample taking, repair damaged construction. Restore substrates and finishes. Comply with Division 1 Section "Cutting and Patching."
- B. Protect construction exposed by or for quality-control service activities, and protect repaired construction.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for inspection and testing.

END OF SECTION 01400

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 01400 - QUALITY CONTROL

1.1 GENERAL

- A. Quality-control services include inspections, tests, and related actions, including reports performed by Contractor, by independent agencies, and by governing authorities.
- B. Contractor Responsibilities: Unless they are the responsibility of another entity, Contractor shall provide inspections and tests specified elsewhere and required by authorities having jurisdiction. Costs for these services are included in the Contract Sum.
 - 1. Where inspections and tests are the Contractor's responsibility, the Contractor shall employ and pay a qualified independent testing agency to perform these services. Costs for these services are included in the Contract Sum.
- C. Retesting: The Contractor is responsible for retesting where results of inspections and tests prove unsatisfactory and indicate noncompliance with requirements.
 - 1. The cost of retesting is the Contractor's responsibility where tests performed indicated noncompliance with requirements.
- D. Auxiliary Services: Cooperate with agencies performing inspections and tests. Provide auxiliary services as requested. Notify the agency in advance of operations to permit assignment of personnel. Auxiliary services include the following:
 - 1. Providing access to the Work.
 - 2. Furnishing incidental labor and facilities to assist inspections and tests.
 - 3. Taking adequate quantities of representative samples of materials that require testing or assisting the agency in taking samples.
 - 4. Providing facilities for storage and curing of test samples.
 - 5. Delivering samples to testing laboratories.
 - 6. Providing preliminary design mix proposed for use for materials mixes that require control by the testing agency.
 - 7. Providing security and protection of samples and test equipment.
- E. Duties of the Testing Agency: The testing agency shall cooperate with the owner and the Contractor in performing its duties. The agency shall provide qualified personnel to perform inspections and tests.
 - 1. The agency shall notify the owner and the Contractor of irregularities or deficiencies observed in the Work during performance of its services.
 - 2. The agency shall not release, revoke, alter, or enlarge requirements or approve or accept any portion of the Work.
 - 3. The agency shall not perform duties of the Contractor.
- F. Coordination: Coordinate activities to accommodate services with a minimum of delay. Avoid removing and replacing construction to accommodate inspections and tests.
 - 1. The Contractor is responsible for scheduling inspections, tests, taking samples, and similar activities.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

G. Submittals: The testing agency shall submit a certified written report, in duplicate, of each inspection and test to the Owner. If the Contractor is responsible for the service, submit a certified written report, in duplicate, of each inspection or test through the Contractor.

1. Submit additional copies of each report to the governing authority, when the authority so directs.
2. Report Data: Reports of each inspection, test, or similar service include, but are not limited to, the following:
 - a. Date of issue.
 - b. Project title and number.
 - c. Name, address, and telephone number of testing agency.
 - d. Dates and locations of samples and tests or inspections.
 - e. Names of individuals making the inspection or test.
 - f. Designation of the Work and test method.
 - g. Identification of product and Specification Section.
 - h. Complete inspection or test data.
 - i. Test results and an interpretation of test results.
 - j. Ambient conditions at the time of sample taking and testing.
 - k. Comments or professional opinion on whether inspected or tested Work complies with requirements.
 - l. Name and signature of laboratory inspector.
 - m. Recommendations on retesting.

H. Qualifications for Service Agencies: Engage inspection and testing service agencies that are prequalified as complying with the American Council of Independent Laboratories' "Recommended Requirements for Independent Laboratory Qualification" and that specialize in the types of inspections and tests to be performed.

1. Each agency shall be authorized by authorities having jurisdiction to operate in the state where the Project is located.

1.2 PRODUCTS (Not Applicable)

1.3 EXECUTION

- A. Repair and Protection: Upon completion of inspection, testing, and sample taking, repair damaged construction. Restore substrates and finishes. Comply with Division 1 Section "Cutting and Patching."
- B. Protect construction exposed by or for quality-control service activities, and protect repaired construction.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for inspection and testing.

END OF SECTION 01400

SECTION 01500 - CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

1.1 GENERAL

- A. Summary: This Section specifies construction facilities and temporary controls including temporary utilities, support facilities, and security and protection facilities.
- B. Regulations: Comply with industry standards and applicable laws and regulations of authorities having jurisdiction including, but not limited to, the following:
 - 1. Building code requirements.
 - 2. Health and safety regulations.
 - 3. Utility company regulations.
 - 4. Police, fire department, and rescue squad rules.
 - 5. Environmental protection regulations.
- C. Standards: Comply with NFPA 241 "Standard for Safeguarding Construction, Alterations, and Demolition Operations," ANSI A10 Series standards for "Safety Requirements for Construction and Demolition," and NECA Electrical Design Library "Temporary Electrical Facilities."

1.2 PRODUCTS

- A. Equipment: Provide new equipment. If acceptable to the Owner, the Contractor may use undamaged, previously used equipment in serviceable condition. Provide equipment suitable for use intended.
 - 1. Electrical Power Cords: Grounded extension cords. Use hard-service cords where exposed to abrasion and traffic.
 - 2. Lamps and Light Fixtures: General service incandescent lamps. Provide guard cages or tempered-glass enclosures where exposed to breakage. Provide exterior fixtures where exposed to moisture.
 - 3. Fire Extinguishers: Hand-carried, portable, UL-rated, Class A fire extinguishers for temporary offices and similar spaces. In other locations, provide hand-carried, portable, UL-rated, Class ABC, dry-chemical extinguishers or a combination of extinguishers of NFPA-recommended classes for the exposures.
 - a. Comply with NFPA 10 and NFPA 241 for classification, extinguishing agent, and size required by location and class of fire exposure.

1.3 EXECUTION

- A. Installation, General: Use qualified personnel to install temporary facilities. Locate facilities where they will serve the Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required.
 - 1. Provide each facility ready for use when needed to avoid delay. Maintain and modify as required. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. Security and Protection Facilities Installation: Except for use of permanent fire protection as soon as available, do not change over from use of temporary security and protection facilities to permanent facilities until Substantial Completion.
1. Temporary Fire Protection: Until permanent facilities supply fire-protection needs, install and maintain temporary fire-protection facilities of types needed to protect against controllable fire losses. Comply with NFPA 10 and NFPA 241.
 - a. Locate fire extinguishers where convenient and effective for their intended purpose. Maintain unobstructed access to fire extinguishers.
 - b. Store combustible materials in containers in fire-safe locations.
 - c. Smoking prohibit
 - d. Provide supervision of welding operations, combustion-type temporary heating units, and similar sources of fire ignition.
 2. Permanent Fire Protection: At the earliest date, complete installation of the permanent fire-protection facility and place into operation and use. Instruct key personnel on use of facilities.
 3. Environmental Protection: Operate temporary facilities and conduct construction in ways that comply with environmental regulations and minimize the possibility that air, waterways, and subsoil might be contaminated or polluted. Avoid use of tools and equipment that produce harmful noise. Restrict use of noise-making equipment to hours that will minimize complaints.
- C. Operation: Enforce discipline in use of temporary facilities. Limit availability to intended uses to minimize waste and abuse.

END OF SECTION 01500

SECTION 01700 - CONTRACT CLOSEOUT

1.1 GENERAL

- A. Closeout requirements for specific construction activities are included in the appropriate Sections in Divisions 2 through 16.
- B. Substantial Completion: Before requesting inspection for certification of Substantial Completion, complete the following:
 - 1. In the Application for Payment that coincides with, or first follows, the date Substantial Completion is claimed, show 100 percent completion for the Work claimed as substantially complete.
 - a. Include supporting documentation for completion and an accounting of changes to the Contract Sum.
 - 2. Advise the Owner of pending insurance changeover requirements.
 - 3. Submit specific warranties, workmanship bonds, maintenance agreements, final certifications, and similar documents.
 - 4. Submit record drawings, maintenance manuals, final project photographs, damage or settlement surveys, property surveys, and similar final record information.
 - 5. Deliver tools, spare parts, extra stock, and similar items.
 - 6. Changeover locks and transmit keys to the Owner.
 - 7. Complete startup testing of systems and instruction of operation and maintenance personnel.
 - 8. Complete final cleanup requirements, including touchup painting.
 - 9. Touch up and repair and restore marred, exposed finishes.
- C. Inspection Procedures: On receipt of a request for inspection, the Project Manager will proceed or advise the Contractor of unfilled requirements. The Project Manager will prepare the Certificate of Substantial Completion following inspection or advise the Contractor of construction that must be completed or corrected before the certificate will be issued.
 - 1. The Project Manager will repeat inspection when requested and assured that the Work is substantially complete.
 - 2. Results of the completed inspection will form the basis of requirements for final acceptance.
- D. Final Acceptance: Before requesting inspection for certification of final acceptance and final payment, complete the following:
 - 1. Final payment request with releases and supporting documentation. Include insurance certificates where required.
 - 2. Submit a statement, accounting for changes to the Contract Sum.
 - 3. Submit a copy of the final inspection list stating that each item has been completed or otherwise resolved for acceptance.
 - 4. Submit consent of surety to final payment.
 - 5. Submit a final settlement statement.
 - 6. Submit evidence of continuing insurance coverage complying with insurance requirements.
- E. Reinspection Procedure: The owner will reinspect the Work upon receipt of notice that the Work has been completed, except for items whose completion is delayed under circumstances acceptable to the owner.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. Upon completion of reinspection, the owner will prepare a certificate of final acceptance. If the Work is incomplete, the owner will advise the Contractor of Work that is incomplete or obligations that have not been fulfilled but are required.
 2. If necessary, reinspection will be repeated.
- F. Record Document Submittals: Do not use record documents for construction. Protect from loss in a secure location. Provide access to record documents for the owners's reference.
- G. Record Drawings: Maintain a set of prints of Contract Drawings and Shop Drawings. Mark the set to show the actual installation where the installation varies substantially from the Work as originally shown. Mark the drawing most capable of showing conditions fully and accurately. Give attention to concealed elements.
1. Mark sets with red pencil. Use other colors to distinguish between variations in separate categories of the Work.
 2. Organize record drawing sheets into manageable sets. Bind with durable-paper cover sheets; print titles, dates, and other identification on the cover of each set.
- H. Record Specifications: Maintain one copy of the Project Manual, including addenda. Mark to show variations in Work performed in comparison with the text of the Specifications and modifications. Give attention to substitutions and selection of options and information on concealed construction. Note related record drawing information and Product Data.
1. Upon completion of the Work, submit record Specifications to the owner for their records.
- I. Maintenance Manuals: Organize operation and maintenance data into sets of manageable size. Bind in individual, heavy-duty, 2-inch (51-mm), 3-ring, binders, with pocket folders for folded sheet information. Mark identification on front and spine of each binder. Include the following information:
1. Copies of warranties.
- 1.2 PRODUCTS (Not Applicable)
- 1.3 EXECUTION
- A. Operation and Maintenance Instructions: Include a detailed review of the following items:
1. Maintenance manuals.
- B. As part of instruction for operating equipment, demonstrate the following:
1. Startup and shutdown.
 2. Noise and vibration adjustments.
- C. Final Cleaning: Employ experienced cleaners for final cleaning. Clean each surface or unit to the condition expected in a normal, commercial building cleaning and maintenance program. Complete the following operations before requesting inspection for certification of Substantial Completion.
1. Remove labels that are not permanent labels.
 2. Clean exposed finishes to a dust-free condition, free of stains, films, and foreign substances. Leave concrete floors broom clean.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

3. Wipe surfaces of electrical equipment. Remove excess lubrication. Clean light fixtures and lamps.
 4. Clean the site of rubbish, litter, and foreign substances. Sweep paved areas; remove stains, spills, and foreign deposits. Rake grounds to a smooth, even-textured surface.
- D. Removal of Protection: Remove temporary protection and facilities.
- E. Compliance: Comply with regulations of authorities having jurisdiction and safety standards for cleaning. Remove waste materials and dispose of lawfully.

END OF SECTION 01700

SECTION 01740 - WARRANTIES

1.1 GENERAL

- A. Standard product warranties are preprinted written warranties published by individual manufacturers for particular products and are specifically endorsed by the manufacturer to the Owner.
- B. Special warranties are written warranties required by or incorporated in the Contract Documents, either to extend time limits provided by standard warranties or to provide greater rights for the Owner.
- C. Disclaimers and Limitations: Manufacturer's disclaimers and limitations on product warranties do not relieve the Contractor of the warranty on the Work that incorporates the products. Manufacturer's disclaimers and limitations on product warranties do not relieve suppliers, manufacturers, and subcontractors required to countersign special warranties with the Contractor.
- D. Related Damages and Losses: When correcting failed or damaged warranted construction, remove and replace construction that has been damaged as a result of such failure or must be removed and replaced to provide access for correction of warranted construction.
- E. Reinstatement of Warranty: When Work covered by a warranty has failed and been corrected by replacement or rebuilding, reinstate the warranty by written endorsement. The reinstated warranty shall be equal to the original warranty with an equitable adjustment for depreciation.
- F. Replacement Cost: Upon determination that Work covered by a warranty has failed, replace or rebuild the Work to an acceptable condition complying with requirements of the Contract Documents. The Contractor is responsible for the cost of replacing or rebuilding defective Work regardless of whether the Owner has benefited from use of the Work through a portion of its anticipated useful service life.
- G. Owner's Recourse: Expressed warranties made to the Owner are in addition to implied warranties and shall not limit the duties, obligations, rights, and remedies otherwise available under the law. Expressed warranty periods shall not be interpreted as limitations on the time in which the Owner can enforce such other duties, obligations, rights, or remedies.
 - 1. Rejection of Warranties: The Owner reserves the right to reject warranties and to limit selection to products with warranties not in conflict with requirements of the Contract Documents.
 - 2. Where the Contract Documents require a special warranty, or similar commitment, the Owner reserves the right to refuse to accept the Work, until the Contractor presents evidence that entities required to countersign such commitments are willing to do so.
- H. Submit written warranties to the Architect prior to the date certified for Substantial Completion. If the Owner's Certificate of Substantial Completion designates a commencement date for warranties other than the date of Substantial Completion, submit written warranties upon request of the Owner's.
- I. When the Contract Documents require the Contractor, or the Contractor and a subcontractor, supplier or manufacturer to execute a special warranty, prepare a written document that contains appropriate terms and identification, ready for execution by the required parties. Submit a draft to the Owner for approval prior to final execution.
 - 1. Refer to Divisions 2 through 16 Sections for specific content requirements and particular requirements for submitting special warranties.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- J. Bind warranties and bonds in heavy-duty, commercial-quality, durable 3-ring, vinyl-covered loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch (115-by-280-mm) paper.
 - 1. Provide heavy paper dividers with celluloid covered tabs for each separate warranty. Mark the tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product, and the name, address, and telephone number of the Installer.
 - 2. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project title or name, and name of the Contractor.
 - 3. When warranted construction requires operation and maintenance manuals, provide additional copies of each required warranty, as necessary, for inclusion in each required manual.

1.2 PRODUCTS (Not Applicable)

1.3 EXECUTION

- A. Schedule: Provide warranties on products and installations as specified in the following Sections:

END OF SECTION 01740

SECTION 02070 - SELECTIVE DEMOLITION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Demolition and removal of selected portions of a building.
 - 2. Patching and repairs.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 1 Section "Summary of Work" for use of the building and phasing requirements.
 - 2. Division 1 Section "Contract Closeout" for record document requirements.
 - 3. Division 2 Section "Selective Demolition for Interiors" for partial demolition of the interior of a building undergoing alterations and for the removal, salvage, or reuse of materials in new construction.
 - 4. Division 9 Section "Gypsum Board Assemblies" for material and construction requirements for temporary enclosures.

1.3 DEFINITIONS

- A. Remove: Remove and legally dispose of items except those indicated to be reinstalled, salvaged, or to remain the Owner's property.
- B. Remove and Salvage: Items indicated to be removed and salvaged remain the Owner's property. Remove, clean, and pack or crate items to protect against damage. Identify contents of containers and deliver to Owner's designated storage area.
- C. Remove and Reinstall: Remove items indicated; clean, service, and otherwise prepare them for reuse; store and protect against damage. Reinstall items in the same locations or in locations indicated.

1.4 MATERIALS OWNERSHIP

- A. Except for items or materials indicated to be reused, salvaged, reinstalled, or otherwise indicated to remain the Owner's property, demolished materials shall become the Contractor's property and shall be removed from the site with further disposition at the Contractor's option.

1.5 SUBMITTALS

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections, for information only, unless otherwise indicated.
- B. Proposed dust-control measures.
- C. Proposed noise-control measures.
- D. Schedule of selective demolition activities indicating the following:
 - 1. Interruption of utility services.
 - 2. Coordination for shutoff, capping, and continuation of utility services.
 - 3. Use of elevator and stairs.
 - 4. Detailed sequence of selective demolition and removal work to ensure uninterrupted progress of Owner's on-site operations.
 - 5. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.
 - 6. Locations of temporary partitions and means of egress.
- E. Inventory of items to be removed and salvaged.

1.6 QUALITY ASSURANCE

- A. Demolition Firm Qualifications: Engage an experienced firm that has successfully completed selective demolition Work similar to that indicated for this Project.
- B. Regulatory Requirements: Comply with governing EPA notification regulations before starting selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- C. Predemolition Conference: Conduct conference at Project site to comply with preinstallation conference requirements of Division 1 Section "Project Meetings."

1.7 PROJECT CONDITIONS

- A. Owner will occupy portions of the building immediately adjacent to selective demolition area. Conduct selective demolition so that Owner's operations will not be disrupted. Provide not less than 72 hours' notice to Owner of activities that will affect Owner's operations.
- B. Owner assumes no responsibility for actual condition of buildings to be selectively demolished.
 - 1. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- C. Asbestos: It is not expected that asbestos will be encountered in the Work. If any materials suspected of containing asbestos are encountered, do not disturb the materials. Immediately notify the Architect and the Owner.
 - 1. Asbestos will be removed by Owner before start of Work.
- D. Storage or sale of removed items or materials on-site will not be permitted.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1.8 SCHEDULING

- A. Arrange selective demolition schedule so as not to interfere with Owner's on-site operations.

1.9 WARRANTY

- A. Existing Special Warranty: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

PART 2 - PRODUCTS (Not Applicable)

2.1 REPAIR MATERIALS

- A. Use repair materials identical to existing materials.
 - 1. Where identical materials are unavailable or cannot be used for exposed surfaces, use materials that visually match existing adjacent surfaces to the fullest extent possible.
 - 2. Use materials whose installed performance equals or surpasses that of existing materials.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.
- D. When unanticipated mechanical, electrical, or structural elements that conflict with the intended function or design are encountered, investigate and measure the nature and extent of the conflict. Promptly submit a written report to the Architect.
- E. Survey the condition of the building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of the structure or adjacent structures during selective demolition.

3.2 UTILITY SERVICES

- A. Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
 - 1. Do not interrupt existing utilities serving occupied or operating facilities, except when authorized in writing by Owner and authorities having jurisdiction. Provide temporary services during interruptions to existing utilities, as acceptable to Owner and to governing authorities.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- a. Provide not less than 72 hours' notice to Owner if shutdown of service is required during changeover.
- B. Utility Requirements: Locate, identify, disconnect, and seal or cap off indicated utility services serving building to be selectively demolished.
 1. Owner will arrange to shut off indicated utilities when requested by Contractor.
 2. Where utility services are required to be removed, relocated, or abandoned, provide bypass connections to maintain continuity of service to other parts of the building before proceeding with selective demolition.
 3. Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal the remaining portion of pipe or conduit after bypassing.
- C. Utility Requirements: Refer to Division 15 and 16 Sections for shutting off, disconnecting, removing, and sealing or capping utility services. Do not start selective demolition work until utility disconnecting and sealing have been completed and verified in writing.

3.3 PREPARATION

- A. Conduct demolition operations and remove debris to ensure minimum interference with roads, streets, walks, and other adjacent occupied and used facilities.
 1. Do not close or obstruct streets, walks, or other adjacent occupied or used facilities without permission from Owner and authorities having jurisdiction. Provide alternate routes around closed or obstructed traffic ways if required by governing regulations.
- B. Conduct demolition operations to prevent injury to people and damage to adjacent buildings and facilities to remain. Ensure safe passage of people around selective demolition area.
 1. Protect walls, ceilings, floors, and other existing finish work that are to remain and are exposed during selective demolition operations.
 2. Cover and protect furniture, furnishings, and equipment that have not been removed.
- C. Erect and maintain dustproof partitions and temporary enclosures to limit dust and dirt migration.

3.4 SELECTIVE DEMOLITION

- A. Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete Work within limitations of governing regulations and as follows:
 1. Proceed with selective demolition systematically, from higher to lower level.
 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. To minimize disturbance of adjacent surfaces, use hand or small power tools designed for sawing or grinding, not hammering and chopping. Temporarily cover openings to remain.
 3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 4. Dispose of demolished items and materials promptly.
 5. Return elements of construction and surfaces to remain to condition existing before start of selective demolition operations.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

3.5 PATCHING AND REPAIRS

- A. Where repairs to existing surfaces are required, patch to produce surfaces suitable for new materials.
- B. Restore exposed finishes of patched areas and extend finish restoration into adjoining construction to remain in a manner that eliminates evidence of patching and refinishing.
- C. Patch and repair floor and wall surfaces in the new space
 - 1. Patch with durable seams that are as invisible as possible. Comply with specified tolerances.
 - 2. Where patching smooth painted surfaces, extend final paint coat over entire unbroken surface containing the patch after the surface has received primer and second coat.
 - 3. Remove existing floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.
 - 4. Inspect and test patched areas to demonstrate integrity of the installation, where feasible.

3.6 DISPOSAL OF DEMOLISHED MATERIALS

- A. General: Promptly dispose of demolished materials. Do not allow demolished materials to accumulate on-site.
- B. Burning: Do not burn demolished materials.
- C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

3.7 CLEANING

- A. Sweep the building broom clean on completion of selective demolition operation.
- B. Change filters on air-handling equipment on completion of selective demolition operations.

END OF SECTION 02070

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 07920 - JOINT SEALANTS

1.1 GENERAL

- A. Preconstruction Joint-Sealant-Substrate Tests: Submit substrate materials, representative of actual joint surfaces, to joint sealant manufacturer for laboratory testing of joint sealants for adhesion to primed and unprimed substrates and for compatibility with joint substrates and other joint-related materials.
- B. Submittals: In addition to Product Data, submit the following:
 - 1. Samples of each type and color of joint sealant required.
 - 2. Test reports for joint sealants evidencing compliance with requirements.

1.2 PRODUCTS

- A. Elastomeric Sealant Manufacturers: Subject to compliance with requirements, provide sealants by one of the following:
 - 1. Silicone Sealants:
 - a. Bostik Inc.
 - b. Dow Corning.
 - c. NUCO Industries, Inc.
 - d. Polymeric Systems, Inc.
 - e. Sonneborn Building Products Div., ChemRex Inc.
 - f. Tremco.
 - 2. Urethane Sealants:
 - a. W.R. Meadows, Inc.
 - b. Pacific Polymers, Inc.
 - c. Polymeric Systems, Inc.
 - d. Sika Corporation.
 - e. Sonneborn Building Products Div., ChemRex Inc.
 - f. Tremco.
- B. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by testing and field experience.
- C. Colors: Provide colors indicated for exposed joint sealants or, if not indicated, as selected by Architect from manufacturer's full range for this characteristic.
- D. Elastomeric Sealant Standard: Comply with ASTM C 920 and other requirements indicated for each liquid-applied chemically curing sealant of base polymer specified below:
 - 1. Medium-Modulus Neutral-Curing Silicone Sealant: Type S; Grade NS; Class 25; with the additional capability, when tested per ASTM C 719, to withstand 50 percent movement in both extension and compression for a total of 100 percent movement and still comply with other requirements of ASTM C 920; and as follows:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- a. Uses NT, M, G, A, and O.
 - 2. Single-Component Nonsag Urethane Sealant: Type S; Grade NS; and as follows:
 - a. Class 12-1/2.
 - b. Class 25.
 - c. Uses NT, M, G, A, and O.
 - d. Uses NT, M, A, and O.
 - E. Latex Sealant: ASTM C 834.
 - F. Sealant Backings, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
 - G. Cylindrical Sealant Backings: ASTM C 1330, of type indicated below and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance:
 - 1. Type C: Closed-cell material with a surface skin.
 - H. Elastomeric Tubing Sealant Backings: Neoprene, butyl, EPDM, or silicone tubing complying with ASTM D 1056, nonabsorbent to water and gas, and capable of remaining resilient at temperatures down to minus 26 deg F (minus 32 deg C).
 - I. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint.
 - J. Primer: As recommended by joint sealant manufacturer where required for adhesion of sealant to joint substrates indicated.
- 1.3 EXECUTION
- A. General: Comply with joint sealant manufacturer's instructions for products and applications indicated.
 - B. Sealant Installation Standard: Comply with ASTM C 1193.

END OF SECTION 07920

SECTION 08110 - STEEL DOOR FRAMES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes steel doors and frames.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 8 Section "Custom Steel Doors and Frames" for doors manufactured according to the Hollow Metal Manufacturers Association's standards.
 - 2. Division 8 Section "Flush Wood Doors" for solid-core wood doors installed in steel frames.
 - 3. Division 8 Section "Door Hardware" for door hardware and weatherstripping.
 - 4. Division 9 Section "Gypsum Board Assemblies" for spot grouting frames in gypsum board partitions.
 - 5. Division 9 Section "Painting" for field painting primed doors and frames.

1.3 SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product Data for each type of door and frame specified, including details of construction, materials, dimensions, hardware preparation, core, label compliance, sound ratings, profiles, and finishes.
- C. Shop Drawings showing fabrication and installation of steel doors and frames. Include details of each frame type, elevations of door design types, conditions at openings, details of construction, location and installation requirements of door and frame hardware and reinforcements, and details of joints and connections. Show anchorage and accessory items.
- D. Door Schedule: Submit schedule of doors and frames using same reference numbers for details and openings as those on Contract Drawings.
- E. Oversize Construction Certification: For door assemblies required to be fire rated and exceeding limitations of labeled assemblies, submit certification of a testing agency acceptable to authorities having jurisdiction that each door and frame assembly has been constructed to conform to design, materials, and construction equivalent to requirements for labeled construction.

1.4 QUALITY ASSURANCE

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Provide doors and frames complying with ANSI/SDI 100 "Recommended Specifications for Standard Steel Doors and Frames" and as specified.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver doors and frames cardboard-wrapped or crated to provide protection during transit and job storage. Provide additional protection to prevent damage to finish of factory-finished doors and frames.
- B. Inspect doors and frames on delivery for damage. Minor damages may be repaired provided refinished items match new work and are acceptable to Architect; otherwise, remove and replace damaged items as directed.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated in the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Steel Door Frames:
 - a. Amweld Building Products, Inc.
 - b. Benchmark Commercial Doors.
 - c. Ceco Door Products.
 - d. Copco Door Co.
 - e. Curries Co.
 - f. Deansteel Manufacturing Co.
 - g. Fenestra Corp.
 - h. Kewanee Corp.
 - i. Mesker Door, Inc.
 - j. Pioneer Industries.
 - k. Republic Builders Products.
 - l. Steelcraft.

2.2 MATERIALS

- A. Hot-Rolled Steel Sheets and Strip: Commercial-quality carbon steel, pickled and oiled, complying with ASTM A 569 (ASTM A 569M).
- B. Cold-Rolled Steel Sheets: Carbon steel complying with ASTM A 366 (ASTM A 366M), commercial quality, or ASTM A 620 (ASTM A 620M), drawing quality, special killed.
- C. Supports and Anchors: Fabricated from not less than 0.0478-inch- (1.2-mm-) thick steel sheet; 0.0516-inch- (1.3-mm-) thick galvanized steel where used with galvanized steel frames.
- D. Inserts, Bolts, and Fasteners: Manufacturer's standard units. Where items are to be built into exterior walls, hot-dip galvanize complying with ASTM A 153, Class C or D as applicable.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2.3 FRAMES

- A. Provide metal frames for doors, transoms, sidelights, borrowed lights, and other openings, according to ANSI/SDI 100, and of types and styles as shown on Drawings and schedules. Conceal fastenings, unless otherwise indicated. Fabricate frames of minimum 0.0478-inch- (1.2-mm-) thick cold-rolled steel sheet.
 - 1. Fabricate frames with mitered or coped and continuously welded corners.
 - 2. Fabricate frames for interior openings over 48 inches (1220 mm) wide from 0.0598-inch- (1.5-mm-) thick steel sheet.
- B. Door Silencers: Except on weatherstripped frames, drill stops to receive 3 silencers on strike jambs of single-door frames and 2 silencers on heads of double-door frames.
- C. Plaster Guards: Provide minimum 0.0179-inch- (0.45-mm-) thick steel plaster guards or mortar boxes at back of hardware cutouts where mortar or other materials might obstruct hardware operation and to close off interior of openings.

2.4 FABRICATION

- A. Fabricate steel door and frame units to be rigid, neat in appearance, and free from defects, warp, or buckle. Where practical, fit and assemble units in manufacturer's plant. Clearly identify work that cannot be permanently factory assembled before shipment, to assure proper assembly at Project site. Comply with ANSI/SDI 100 requirements.
 - 1. Clearances: Not more than 1/8 inch (3.2 mm) at jambs and heads, except not more than 1/4 inch (6.4 mm) between non-fire-rated pairs of doors. Not more than 3/4 inch (19 mm) at bottom.
 - a. Fire Doors: Provide clearances according to NFPA 80.
- B. Tolerances: Comply with SDI 117 "Manufacturing Tolerances Standard Steel Doors and Frames."
- C. Hardware Preparation: Prepare doors and frames to receive mortised and concealed hardware according to final door hardware schedule and templates provided by hardware supplier. Comply with applicable requirements of SDI 107 and ANSI A115 Series specifications for door and frame preparation for hardware.
 - 1. For concealed overhead door closers, provide space, cutouts, reinforcing, and provisions for fastening in top rail of doors or head of frames, as applicable.
- D. Reinforce doors and frames to receive surface-applied hardware. Drilling and tapping for surface-applied hardware may be done at Project site.
- E. Locate hardware as indicated on Shop Drawings or, if not indicated, according to the Door and Hardware Institute's (DHI) "Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames."

2.5 FINISHES, GENERAL

- A. Comply with NAAMM's "Metal Finishes Manual" for recommendations relative to applying and designating finishes.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2.6 STEEL SHEET FINISHES

- A. Surface Preparation: Solvent-clean surfaces to comply with SSPC-SP 1 to remove dirt, oil, grease, and other contaminants that could impair paint bond. Remove mill scale and rust, if present, from uncoated steel to comply with SSPC-SP 5 (White Metal Blast Cleaning) or SSPC-SP 8 (Pickling).
- B. Factory Priming for Field-Painted Finish: Apply shop primer that complies with ANSI A224.1 acceptance criteria, is compatible with finish paint systems indicated, and has capability to provide a sound foundation for field-applied topcoats. Apply primer immediately after surface preparation and pretreatment.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. General: Install steel doors, frames, and accessories according to Shop Drawings, manufacturer's data, and as specified.
- B. Placing Frames: Comply with provisions of SDI 105, unless otherwise indicated. Set frames accurately in position, plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is completed, remove temporary braces and spreaders, leaving surfaces smooth and undamaged.
 - 1. At existing concrete or masonry construction, install at least 3 completed opening anchors per jamb adjacent to hinge location on hinge jamb and at corresponding heights on strike jamb. Set frames and secure to adjacent construction with bolts and masonry anchorage devices.
 - 2. In metal-stud partitions, install at least 3 wall anchors per jamb at hinge and strike levels. In steel-stud partitions, attach wall anchors to studs with screws.
 - 3. Install fire-rated frames according to NFPA 80.
- C. Door Installation: Fit hollow-metal doors accurately in frames, within clearances specified in ANSI/SDI 100.
 - 1. Fire-Rated Doors: Install with clearances specified in NFPA 80.
 - 2. Smoke-Control Doors: Comply with NFPA 105.

3.2 ADJUSTING AND CLEANING

- A. Prime Coat Touchup: Immediately after erection, sand smooth any rusted or damaged areas of prime coat and apply touchup of compatible air-drying primer.
- B. Protection Removal: Immediately before final inspection, remove protective wrappings from doors and frames.

END OF SECTION 08110

SECTION 08211 - FLUSH WOOD DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Solid-core doors with wood-veneer faces.

1.3 QUALITY ASSURANCE

- A. Source Limitations: Obtain flush wood doors through one source from a single manufacturer.
- B. Quality Standard: Comply with the following standard:
 - 1. NWWDA Quality Standard: NWWDA I.S.1-A, "Architectural Wood Flush Doors."
 - 2. AWI Quality Standard: AWI's "Architectural Woodwork Quality Standards" for grade of door, core, construction, finish, and other requirements.

1.4 DELIVERY, STORAGE, AND HANDLING

- A. Protect doors during transit, storage, and handling to prevent damage, soiling, and deterioration. Comply with requirements of referenced standard and manufacturer's written instructions.
 - 1. Individually package doors in plastic bags or cardboard cartons.
 - 2. Individually package doors in cardboard cartons and wrap bundles of doors in plastic sheeting.

1.5 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install doors until conditions for temperature and relative humidity have been stabilized and will be maintained in storage and installation areas during the remainder of the construction period to comply with requirements of the referenced quality standard for Project's geographical location.

1.6 WARRANTY

- A. General Warranty: Door manufacturer's warranty specified in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by the Contractor under requirements of the Contract Documents.
- B. Door Manufacturer's Warranty: Submit written agreement on door manufacturer's standard form, signed by manufacturer, Installer, and Contractor, agreeing to repair or replace defective doors that have warped (bow, cup, or twist) more than 1/4 inch (6.35 mm) in a 42-by-84-inch (1067-by-2134-mm) section or that show telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch (0.25 mm in a 75-mm) span, or do not comply with tolerances in referenced quality standard.
 - 1. Warranty shall also include installation and finishing that may be required due to repair or replacement of defective doors.
 - 2. Warranty shall be in effect during the following period of time after the date of Substantial Completion:
 - a. Solid-Core Interior Doors: Life of installation.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Flush Wood Doors:
 - a. Algoma Hardwoods Inc.
 - b. Ampco Products, Inc.
 - c. Buell Door Co.
 - d. Chappell Door Co.
 - e. Eagle Plywood & Door Manufacturing, Inc.
 - f. Eggers Industries; Architectural Door Division.
 - g. Graham Manufacturing Corp.
 - h. Mohawk Flush Doors, Inc.
 - i. Oshkosh Architectural Door Co.
 - j. Weyerhaeuser Co.

2.2 DOOR CONSTRUCTION, GENERAL

- A. Doors for Transparent Finish: Comply with the following requirements:
 - 1. Grade: Premium (Grade A faces).
 - 2. Faces: match existing finish and species (OAK)
 - 3. Match within Door Faces: Center balance match.
 - 4. Stiles: Applied wood edges of same species as faces and covering edges of faces.

- 5. Finish: Match existing doors in building

2.3 SOLID-CORE DOORS

- A. Interior Veneer-Faced Doors: Comply with the following requirements:
 - 1. Core: Nonglued- or glued-block core.
 - 2. Construction: Seven plies.

2.4 FABRICATION

- A. Fabricate flush wood doors in sizes indicated for Project site fitting.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine installed door frames before hanging doors.
 - 1. Verify that frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with plumb jambs and level heads.
 - 2. Reject doors with defects.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Hardware: For installation, see Division 8 Section "Door Hardware."
- B. Manufacturer's Written Instructions: Install wood doors to comply with manufacturer's written instructions, referenced quality standard, and as indicated.
- C. Job-Fit Doors: Align and fit doors in frames with uniform clearances and bevels as indicated below; do not trim stiles and rails in excess of limits set by manufacturer or permitted with fire-rated doors. Machine doors for hardware. Seal cut surfaces after fitting and machining.
 - 1. Clearances: Provide 1/8 inch (3.2 mm) at heads, jambs, and between pairs of doors. Provide 1/8 inch (3.2 mm) from bottom of door to top of decorative floor finish or covering. Where threshold is shown or scheduled, provide 1/4 inch (6.4 mm) from bottom of door to top of threshold.
- D. Field-Finished Doors: Refer to the following for finishing requirements:
 - 1. Division 9 Section "Painting."

3.3 ADJUSTING AND PROTECTING

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Refinish or replace doors damaged during installation.
- C. Protect doors as recommended by door manufacturer to ensure that wood doors are without damage or deterioration at the time of Substantial Completion.

END OF SECTION 08211

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 08710--FINISH HARDWARE

PART 1 --GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.

1.2 DESCRIPTION OF WORK

- A. Definition: "Finish Hardware" includes items known commercially as finish hardware which are required for swing, sliding and folding doors, except special types of unique and non-matching hardware specified in the same section as the door and door frame.
- B. Extent of finish hardware required is indicated on drawings and in schedules.
- C. Types of finish hardware required include the following:

- Butt Hinges
- Lock cylinders and keys
- Lock and latch sets
- Door trim units

1.3 RELATED SECTIONS

- A. Division 8 - Steel Doors and Frames.
- B. Division 8 - Flush Wood Doors.

1.4 QUALITY ASSURANCE

- A. Manufacturer: Obtain each type of hardware (latch and locksets, etc.) from a single manufacturer
- B. Supplier: A recognized architectural finish hardware supplier, with warehousing facilities, who has been furnishing hardware in the project's vicinity for a period of not less than 2 years, and who is, or who employs an experienced Architectural Hardware Consultant who is available, at reasonable times during the course of the work, for consultation about project's hardware requirements, to Owner, Architect and Contractor.
- C. Fire-Rated Openings: Provide hardware for fire-rated openings in compliance with NFPA Standard No. 80 and local building code requirements. Provide only hardware which has been tested and listed by UL or an approved testing agency for types and sizes of doors required and complies with requirements of door and door frame labels.
- D. Where emergency exit devices are required on fire-rated doors (with supplementary marking on doors with labels indicating "Fire Door to be Equipped with Fire Exit Hardware") provide labels on exit devices indicating "Fire Exit Hardware"

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- E. This supplier shall be responsible to field check existing openings for proper application of sizes and strikes for all openings.

1.5 REGULATORY REQUIREMENTS

- A. Where indicated to comply with accessibility requirements, comply with Americans with Disabilities Act (ADA), "Accessibilities Guidelines for Buildings and Facilities (ADAAG)," ANSI A117.1, FED-STD-795, "Uniform Federal Accessibility Standards."

1.6 SUBMITTALS

- A. Product Data: Submit manufacturers technical product data for each item of hardware in accordance with Division-1 section "Submittals". Include whatever information may be necessary to show compliance with requirements, and include instructions for installation and for maintenance of operating parts and finish.
- B. Hardware Schedule: Submit final hardware schedule in a vertical format as recognized by the Door and Hardware Institute (DHI). Horizontal schedule format will not be accepted. Coordinate hardware with doors, frames and related work to ensure proper size, thickness, hand, function and finish of hardware.
 - 1. Final Hardware Schedule Content: Based on finish hardware indicated, organize hardware schedule into "hardware sets" indicating complete designations of every item required for each door or opening. Include the following information:
 - a. Type, style, function, size and finish of each hardware item.
 - b. Name and manufacturer of each item.
 - c. Fastenings and other pertinent information.
 - d. Index to include location of hardware set cross-referenced to indications on drawings both on floor plans and in door and frame schedule.
 - e. Explanation of all abbreviations, symbols, codes, etc., contained in schedule.
 - f. Mounting locations for hardware.
 - g. Door and frame sizes and materials.
 - h. Keying information.
 - i. Wiring diagrams with theory of operation.
- C. Submittal Sequence: Submit schedule in accordance to Division 1, particularly where acceptance of hardware schedule must precede fabrication of other work (e.g., hollow metal frames) which is critical in the project construction schedule. Include with schedule the product data, samples, shop drawings of other work affected by finish hardware, and other information essential to the coordinated review of hardware schedule.
- D. Keying Schedule: Submit separate detailed schedule indicating clearly how the Owner's final instructions on keying of locks has been fulfilled.
- E. Samples if Requested: Prior to submittal of the final hardware schedule and prior to final ordering of finish hardware, submit one sample of each type of exposed hardware unit, finish as required, and tagged with full description for coordination with schedule. Return to project in time for installation.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- F. Templates: Furnish hardware templates to each fabricator of doors, frames and other work to be factory-prepared for the installation of hardware. Upon request, check shop drawings of such other work, to confirm that adequate provisions are made for proper location and installation of hardware.

1.7 PRODUCT HANDLING

- A. Tag each item or package separately, with identification related to final hardware schedule, and include basic installation instructions with each item or package.
- B. Inventory hardware jointly with representatives of hardware supplier and hardware installer until each is satisfied that count is correct.
- C. Deliver individually packaged hardware items at the proper times to the proper locations (shop or project site) for installation.
- D. Provide secure lock-up for hardware delivered to the project, but not yet installed. Control handling and installation of hardware items which are not immediately replaceable, so that completion of the work will not be delayed by hardware losses, both before and after installation.

PART 2—PRODUCTS

2.1 SCHEDULED HARDWARE

- A. Requirements for design, grade, function, finish, size and other distinctive qualities of each type of finish hardware is indicated in the Finish Hardware Data Sheet and Hardware Schedule at the end of this section. Products are identified by using hardware designation numbers of the following.

- B. Manufacturer's Product Designations:

| | |
|-------------------|----------------|
| Butt Hinges: | Ives |
| Locksets: | Match Existing |
| Kickplates: | Ives |
| Floor/Wall Stops: | Ives |

2.2 MATERIALS AND FABRICATION

- A. General:
1. Hand of door: Drawings show direction of slide, swing or hand of each door leaf. Furnish each item of hardware for proper installation and operation of door movement as shown.
 2. Manufacturer's Name Plate: Do not use manufacturer's products which have manufacturer's name or trade name displayed in a visible location (omit removable nameplates), except in conjunction with required UL labels and as otherwise acceptable to Architect.
 3. Manufacturer's identification will be permitted on rim of lock cylinders only.
 4. Finish: All hardware finish shall match existing unless otherwise indicated. Closer bodies, covers and arms shall be powder-coated finishes.
 5. Lockset Design: Lever handle design shall match existing.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

6. Fasteners: Provide hardware manufactured to conform to published templates, generally prepared for machine screw installation. Do not provide hardware which has been prepared for self-tapping sheet metal screws, except as specifically indicated.
7. Furnish screws for installation, with each hardware item. Provide Phillips flat-head screws except as otherwise indicated. Finish exposed (exposed under any condition) screws to match hardware finish or, if exposed in surfaces of other work, to match finish of such other work as closely as possible, including "prepared for paint" in surfaces to receive painted finish.
8. Provide concealed fasteners for hardware units which are exposed when door is closed, except to extent no standard units of type specified are available with concealed fasteners. Do not use thru-bolts for installation where bolt head or nut on opposite face is exposed in other work, except where it is not feasible to adequately reinforce the work. In such cases, provide sleeves for each thru-bolt or use sex screw fasteners.
9. Tools and Maintenance Instructions for Maintenance: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of finish hardware.

2.3 HINGES, BUTTS AND PIVOTS

- A. Templates: Except for hinges and pivots to be installed entirely (both leaves) into wood doors and frames, provide only template-produced units.
- B. Screws: Furnish Phillips flat-head or machine screws for installation of units, except furnish Phillips flat-head or wood screws for installation of units into wood. Finish screw heads to match surface of hinges or pivots.
- A. Hinge Pins: Except as otherwise indicated, provide hinge pins as follows:
 1. Steel Hinges: Steel pins.
 2. Non-ferrous Hinges: Stainless steel pins.
 3. Out-swing Corridor Doors: Non-removable pins.
 4. Interior Doors: Non-rising pins.
 5. Tips: Flat button and matching plug, finished to match leaves.
 6. Number of hinges: Provide number of hinges indicated but not less than 3 hinges per door leaf for doors 90" or less in height and one additional hinge for each 30" of additional height.
- B. Furnish hinges in sizes and types as required by architect's details to achieve maximum degree of opening.
- E. Acceptable Manufacturers:
 1. Ives
 2. McKinney
 3. Hager

2.4 LOCK CYLINDERS AND KEYING

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. General: Supplier will meet with Owner to finalize keying requirements and obtain final instructions in writing.
- B. Review the keying system with the Owner and provide a master, grandmaster or great-grandmaster integrated with Owner's existing system. If key pinning charts are required, owner to furnish charts to hardware supplier.
- C. Furnish temporary keyed cores for the construction period, and remove these when directed. The construction cores remain property of the supplier and shall be returned to the supplier when they are removed. Contractor shall install the permanent cores in the presence of the owner's representative.
- D. Metals: Construct lock cylinder parts from brass/bronze, stainless steel or nickel silver.
- E. Comply with Owner's instructions for masterkeying and, except as otherwise indicated, provide individual change key for each lock which is not designated to be keyed alike with a group of related locks.
- F. Permanently inscribe each key and cylinder with Visual Key Control that identifies cylinder manufacturer key symbol, and inscribe key with the notation "DO NOT DUPLICATE".
- G. Key Material: Provide keys of nickel silver only.
- H. Key Quantity:
 - 1. Furnish 3 change keys for each lock.
 - 2. 5 master keys for each master system.
 - 3. 5 grandmaster keys for each grandmaster system.
 - 4. One extra blank for each lock.
 - 5. 3 Control Keys.
 - 6. 6 Construction master keys.
- I. Deliver keys to Owner's representative.

2.5 LOCKS, LATCHES AND BOLTS

- A. Locks shall meet these certifications:
 - 1. Cylindrical Locks - ANSI A156.2 Series 4000, Grade 1 Strength and Operational requirements. Meets A117.1 Accessibility Codes. Latch bolts shall be steel with minimum ½" throw, deadlocking on keyed and exterior functions. ¾" throw anti-friction latchbolt on pairs of fire doors. Strikes: Provide manufacturer's standard wrought box strike for each latch or lock bolt, with curved lip extended to protect frame. Locksets to be tested to exceed 3,000,000 cycles. Lock case shall be steel. Lock shall incorporate one piece spring cage and spindle. Provide 5/8" minimum throw of latch and deadbolt used on pairs of doors. Provide Seven Year Warranty.
 - a. Lock design shall match existing.
- B. Comply with UL requirements for throw of bolts and latch bolts on rated fire openings.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- C. Lock Manufacturers: Subject to compliance with requirements, provide lockset products of the following approved manufacturers:

1. Match existing

- D. Flush Bolt Heads: Minimum of 1/2" diameter rods of brass, bronze or stainless steel, with minimum 12" long rod for doors up to 7'-0" in height. Provide longer rods as necessary for doors exceeding 7'-0" in height.
- E. Provide dust-proof strikes for foot bolts, except where special threshold construction provides non-recessed strike for bolt.

2.6 DOOR TRIM UNITS

- A. Fasteners: Provide manufacturer's standard exposed fasteners for door trim units (kick plates, edge trim, viewers, knockers, mail drops and similar units); either machine screws or self-tapping screws.
- B. Fabricate edge trim of stainless steel, not more than 1/2" nor less than 1/16" smaller in length than door dimension.
- C. Fabricate protection plates (armor, kick or mop) not more than 1-1/2" less than door width on stop side and not more than 1/2" less than door width on pull side, x the height indicated.
- D. Where existing doors are receiving new hardware, provide new protection plates on all doors that have existing plates, if not already specified. New plates are to be of equal or greater size than existing plates.
- E. Metal Plates: Stainless steel, .050" (U.S. 18 ga.).
- F. Acceptable Manufacturers:
1. Ives
 2. Rockwood
 3. Quality

2.7 DOOR SILENCERS

All hollow metal frames shall have grey resilient type silencers. Quantity (3) on single doors and quantity (2) on pairs of doors.

PART 3--EXECUTION

3.1 INSTALLATION

- A. Hardware specified under this section for aluminum doors will be coordinated and delivered in a timely manner to aluminum door manufacturer for installation on aluminum doors prior to delivery to project. This coordination will not impede delivery of storefront or securing exterior of building during construction.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. Mount hardware units at heights indicated in "Recommended Locations for Builders Hardware for Standard Steel Doors and Frames" by the Door and Hardware Institute, except as specifically indicated or required to comply with governing regulations, and except as may be otherwise directed by Architect.
- C. Install each hardware item in compliance with the manufacturer's instructions and recommendations. Wherever cutting and fitting is required to install hardware onto or into surfaces which are later to be painted or finished in another way, coordinate removal, storage and reinstallation or application of surface protections with finishing work specified in the Division-9 sections. Do not install surface-mounted items until finishes have been completed on the substrate.
- D. Set units level, plumb and true to line and location. Adjust and reinforce the attachment substrate as necessary for proper installation and operation.
- E. Drill and countersink units which are not factory-prepared for anchorage fasteners. Space fasteners and anchors in accordance with industry standards.
- F. Set thresholds for exterior doors in full bed of butyl-rubber or polyisobutylene mastic sealant.

3.2 ADJUST AND CLEAN

- A. Adjust and check each operating item of hardware and each door, to ensure proper operation or function of every unit. Replace units which cannot be adjusted to operate freely and smoothly as intended for the application made.
- B. Clean adjacent surfaces soiled by hardware installation.
- C. Final Adjustment: Wherever hardware installation is made more than one month prior to acceptance or occupancy of a space or area, return to the work during the week prior to acceptance or occupancy, and make final check and adjustment of all hardware items in such space or area. Clean operating items as necessary to restore proper function and finish of hardware and doors. Adjust door control devices to compensate for final operation of heating and ventilating equipment.
- D. Instruct Owner's Personnel in proper adjustment and maintenance of hardware and hardware finishes, during the final adjustment of hardware.

1.3 HARDWARE SCHEDULE

HW SET: 01

DOOR NUMBER:

| | | | |
|------|------|------|------|
| 100A | 100B | 104A | 105A |
|------|------|------|------|

EACH TO HAVE:

| | | | | |
|---|----|---------------|--------------------------------|---------|
| 3 | EA | HINGE | 5BB1 4.5 X 4.5 | IVE |
| 1 | EA | ENTRANCE LOCK | MATCH EXISTING ENTRANCE/OFFICE | SCH |
| 1 | EA | KICK PLATE | 8400 10" X 2" LDW | IVE |
| 1 | EA | WALL STOP | WS401CCV | IVE |
| 3 | EA | SILENCER | SR64 | GRY IVE |

FINISH HARDWARE

08710-7

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

HW SET: 02

DOOR NUMBER:

108A 108B

EACH TO HAVE:

| | | | | |
|---|----|-------------|------------------------|---------|
| 3 | EA | HINGE | 5BB1 4.5 X 4.5 | IVE |
| 1 | EA | PASSAGE SET | MATCH EXISTING PASSAGE | SCH |
| 1 | EA | KICK PLATE | 8400 10" X 2" LDW | IVE |
| 1 | EA | WALL STOP | WS401CCV | IVE |
| 3 | EA | SILENCER | SR64 | GRY IVE |

SECTION 09255 - GYPSUM BOARD ASSEMBLIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Nonload-bearing steel framing members for gypsum board assemblies.
 - 2. Gypsum board assemblies attached to steel framing.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 7 Section "Mineral Fiber Board Fireproofing" for board-type fireproofing concealed behind gypsum board assemblies.
 - 2. Division 7 Section "Firestopping" for firestopping systems and fire-resistance-rated joint sealants.

1.3 DEFINITIONS

- A. Gypsum Board Construction Terminology: Refer to ASTM C 11 and GA-505 for definitions of terms for gypsum board assemblies not defined in this Section or in other referenced standards.

1.4 ASSEMBLY PERFORMANCE REQUIREMENTS

- A. Sound Transmission Characteristics: For gypsum board assemblies with STC ratings, provide materials and construction identical to those of assemblies whose STC ratings were determined according to ASTM E 90 and classified according to ASTM E 413 by a qualified independent testing agency.
- B. Fire Resistance: Provide gypsum board assemblies with fire-resistance ratings indicated.

1.5 SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product Data for each type of product specified.
- C. Product certificates signed by manufacturers of gypsum board assembly components certifying that their products comply with specified requirements.

1.6 QUALITY ASSURANCE

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Single-Source Responsibility for Steel Framing: Obtain steel framing members for gypsum board assemblies from a single manufacturer, unless otherwise indicated.
- B. Single-Source Responsibility for Panel Products: Obtain each type of gypsum board and other panel products from a single manufacturer.
- C. Single-Source Responsibility for Finishing Materials: Obtain finishing materials from either the same manufacturer that supplies gypsum board and other panel products or from a manufacturer acceptable to gypsum board manufacturer.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials in original packages, containers, or bundles bearing brand name and identification of manufacturer or supplier.
- B. Store materials inside under cover and keep them dry and protected against damage from weather, direct sunlight, surface contamination, corrosion, construction traffic, and other causes. Neatly stack gypsum panels flat to prevent sagging.

1.8 PROJECT CONDITIONS

- A. Environmental Conditions, General: Establish and maintain environmental conditions for applying and finishing gypsum board to comply with ASTM C 840 requirements or gypsum board manufacturer's recommendations, whichever are more stringent.
- B. Room Temperatures: For nonadhesive attachment of gypsum board to framing, maintain not less than 40 deg F (4 deg C). For adhesive attachment and finishing of gypsum board, maintain not less than 50 deg F (10 deg C) for 48 hours before application and continuously after until dry. Do not exceed 95 deg F (35 deg C) when using temporary heat sources.
- C. Ventilation: Ventilate building spaces as required to dry joint treatment materials. Avoid drafts during hot, dry weather to prevent finishing materials from drying too rapidly.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated in the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Steel Framing and Furring:
 - a. Clark Steel Framing, Inc.
 - b. Consolidated Systems, Inc.
 - c. Dale Industries, Inc.
 - d. Dietrich Industries, Inc.
 - e. Marino/Ware (formerly Marino Industries Corp.).
 - f. National Gypsum Co.; Gold Bond Building Products Division.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2. Grid Suspension Assemblies:

- a. Armstrong World Industries, Inc.
- b. Chicago Metallic Corp.
- c. USG Interiors, Inc.
- d. Worthington Steel Company (formerly National Rolling Mills).

3. Gypsum Board and Related Products:

- a. Domtar Gypsum.
- b. Georgia-Pacific Corp.
- c. National Gypsum Co.; Gold Bond Building Products Division.
- d. United States Gypsum Co.

C. Available Products: Subject to compliance with requirements, products that may be incorporated in the Work where proprietary gypsum wallboard is indicated include, but are not limited to, the following:

D. Products: Subject to compliance with requirements, provide one of the following products where proprietary gypsum wallboard is indicated:

1. Gyprock Fireguard C Gypsum Board; Domtar Gypsum.
2. Firestop Type C; Georgia-Pacific Corp.
3. Fire-Shield G; National Gypsum Co.; Gold Bond Building Products Division.
4. SHEETROCK Brand Gypsum Panels, FIRECODE C Core; United States Gypsum Co.

2.2 STEEL FRAMING FOR WALLS AND PARTITIONS

A. General: Provide steel framing members complying with the following requirements:

1. Protective Coating: Manufacturer's standard corrosion-resistant coating.
2. Protective Coating: ASTM A 653, G 40 (ASTM A 653M, Z 90) hot-dip galvanized coating for framing members attached to and within 10 feet (3 m) of exterior walls.

B. Steel Studs and Runners: ASTM C 645, with flange edges of studs bent back 90 degrees and doubled over to form 3/16-inch- (5-mm-) wide minimum lip (return), and complying with the following requirements for minimum thickness of base (uncoated) metal and for depth:

Steel Studs:

1. Thickness: 20 ga unless noted otherwise as indicated on documents.
 - a. For head runner, sill runner, jamb, and cripple studs at door and other openings.
 - b. Depth: 3-5/8 inches (92.1 mm), unless otherwise

Runners:

1. Thickness: 20 ga unless noted otherwise as indicated on documents.
 - a. Depth: 3-5/8 inches (92.1 mm), unless otherwise indicated.

C. Deflection Track: Manufacturer's standard top runner designed to prevent cracking of gypsum board applied to interior partitions resulting from deflection of the structure above fabricated from steel sheet complying with ASTM A 653 (ASTM A 653M) or ASTM A 568 (ASTM A 568M). Thickness as indicated for studs, and width to accommodate depth of studs, and of the following configuration:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. Top runner with 2-1/2-inch- (63.5-mm-) deep flanges that either have V-shaped offsets that compress when pressure is applied from construction above or have slots 1 inch (25.4 mm) o.c. that allow fasteners attached to studs through the slots to accommodate structural movement by slipping.
 - a. Available Products: Subject to compliance with requirements, products that may be incorporated in the Work include, but are not limited to, the following:
 - b. Products: Subject to compliance with requirements, provide one of the following:
 - 1) Superior Flex Track System (SFT); Delta Star, Inc.
 - 2) SLP-TRK; Metal-Lite, Inc.
- D. Deflection Track: Top runner designed to allow partition heads to expand and contract with movement of structure above while maintaining continuity of the assembly. Comply with requirements of ASTM C 645 except configuration, of thickness indicated for studs and width to accommodate depth of studs indicated with flanges offset at midpoint to accommodate gypsum board thickness.
 1. Available Product: Subject to compliance with requirements, a product that may be incorporated in the Work includes, but is not limited to, "Fire Trak" manufactured by Fire Trak Corp.
- E. Steel Flat Strap and Backing Plate: Steel sheet for blocking and bracing complying with ASTM A 653 (ASTM A 653M) or ASTM A 568 (ASTM A 568M), length and width as indicated, and with a minimum base metal (uncoated) thickness as follows:
 1. Thickness: 0.0598 inch (1.5 mm) where indicated.
- F. Fasteners for Metal Framing: Provide fasteners of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel framing and furring members securely to substrates involved; complying with the recommendations of gypsum board manufacturers for applications indicated.

2.3 GYPSUM BOARD PRODUCTS

- A. General: Provide gypsum board of types indicated in maximum lengths available that will minimize end-to-end butt joints in each area indicated to receive gypsum board application.
 1. Widths: Provide gypsum board in widths of 48 inches (1219 mm).
- B. Gypsum Wallboard: ASTM C 36 and as follows:
 1. Type: Type X where for all assemblies.
 2. Type: Proprietary type as required for specific fire-resistance-rated assemblies.
 3. Edges: Tapered.
 4. Thickness: 5/8 inch (15.9 mm)

2.4 TRIM ACCESSORIES

- A. Accessories for Interior Installation: Cornerbead, edge trim, and control joints complying with ASTM C 1047 and requirements indicated below:
 1. Material: Formed metal or plastic, with metal complying with the following requirement:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- a. Steel sheet zinc coated by hot-dip process or rolled zinc.
2. Shapes indicated below by reference to Fig. 1 designations in ASTM C 1047:
 - a. Cornerbead on outside corners, unless otherwise indicated.
 - b. LC-bead with both face and back flanges; face flange formed to receive joint compound. Use LC-beads for edge trim, unless otherwise indicated.
 - c. L-bead with face flange only; face flange formed to receive joint compound. Use L-bead where indicated.
 - d. U-bead with face and back flanges; face flange formed to be left without application of joint compound. Use U-bead where indicated.
 - e. One-piece control joint formed with V-shaped slot and removable strip covering slot opening.
- B. Accessories for Exterior Installations: Cornerbead, edge trim, and control joints formed from steel sheet zinc coated by hot-dip process or rolled zinc complying with ASTM C 1047, in shapes indicated below by reference to Fig. 1 designations in ASTM C 1047.
 1. Cornerbead on outside corners, unless otherwise indicated.
 2. Edge trim complying with shape LC-bead per Fig. 1, unless otherwise indicated.

2.5 JOINT TREATMENT MATERIALS

- A. General: Provide joint treatment materials complying with ASTM C 475 and the recommendations of both the manufacturers of sheet products and of joint treatment materials for each application indicated.
- B. Joint Tape for Gypsum Board: Paper reinforcing tape, unless otherwise indicated.
- C. Drying-Type Joint Compounds for Gypsum Board: Factory-packaged vinyl-based products complying with the following requirements for formulation and intended use.
 1. Ready-Mixed Formulation: Factory-mixed product.
 - a. Taping compound formulated for embedding tape and for first coat over fasteners and face flanges of trim accessories.
 - b. Topping compound formulated for fill (second) and finish (third) coats.
 - c. All-purpose compound formulated for both taping and topping compounds.

2.6 ACOUSTICAL SEALANT

- A. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834 and the following requirements:
 1. Product is effective in reducing airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.
- B. Acoustical Sealant for Concealed Joints: Manufacturer's standard nondrying, nonhardening, nonskinning, nonstaining, gunnable, synthetic-rubber sealant recommended for sealing interior concealed joints to reduce transmission of airborne sound.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- C. Available Products: Subject to compliance with requirements, acoustical sealants that may be incorporated in the Work include, but are not limited to, the following:
- D. Products: Subject to compliance with requirements, provide one of the following:
 - 1. Acoustical Sealant for Exposed and Concealed Joints:
 - a. PL Acoustical Sealant; ChemRex, Inc.; Contech Brands.
 - b. AC-20 FTR Acoustical and Insulation Sealant; Pecora Corp.
 - c. SHEETROCK Acoustical Sealant; United States Gypsum Co.

2.7 MISCELLANEOUS MATERIALS

- A. General: Provide auxiliary materials for gypsum board construction that comply with referenced standards and recommendations of gypsum board manufacturer.
- B. Spot Grout: ASTM C 475, setting-type joint compound recommended for spot-grouting hollow metal door frames.
- C. Steel drill screws complying with ASTM C 1002 for the following applications:
 - 1. Fastening gypsum board to steel members less than 0.033 inch (0.84 mm) thick.
- D. Steel drill screws complying with ASTM C 954 for fastening gypsum board to steel members from 0.033 to 0.112 inch (0.84 to 2.84 mm) thick.
- E. Sound-Attenuation Blankets: Unfaced mineral-fiber blanket insulation produced by combining mineral fibers of type described below with thermosetting resins to comply with ASTM C 665 for Type I (blankets without membrane facing).
 - 1. Mineral-Fiber Type: Fibers manufactured from glass.

PART 3 -

3.1 EXAMINATION

- A. Examine substrates to which gypsum board assemblies attach or abut, installed hollow metal frames, cast-in-anchors, and structural framing, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of assemblies specified in this Section. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.2 INSTALLING STEEL FRAMING, GENERAL

- A. Steel Framing Installation Standard: Install steel framing to comply with ASTM C 754 and with ASTM C 840 requirements that apply to framing installation.
- B. Install supplementary framing, blocking, and bracing at terminations in gypsum board assemblies to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction. Comply with details indicated and with recommendations of gypsum board manufacturer or, if none available, with United States Gypsum Co.'s "Gypsum Construction Handbook."

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- C. Isolate steel framing from building structure at locations indicated to prevent transfer of loading imposed by structural movement. Comply with details shown on Drawings.
 - 1. Where building structure abuts ceiling perimeter or penetrates ceiling.
 - 2. Where partition framing and wall furring abut structure, except at floor.
 - a. Install deflection track top runner to attain lateral support and avoid axial loading.
 - b. Install deflection and firestop track top runner at fire-resistance-rated assemblies where indicated.
 - 1) Attach jamb studs at openings to tracks using manufacturer's standard stud clip.

3.3 INSTALLING STEEL FRAMING FOR WALLS AND PARTITIONS

- A. Install runners (tracks) at floors, ceilings, and structural walls and columns where gypsum board stud assemblies abut other construction.
 - 1. Where studs are installed directly against exterior walls, install asphalt felt strips or foam gaskets between studs and wall.
- B. Installation Tolerances: Install each steel framing and furring member so that fastening surfaces do not vary more than 1/8 inch (3 mm) from the plane formed by the faces of adjacent framing.
- C. Extend partition framing full height to structural supports or substrates above suspended ceilings, except where partitions are indicated to terminate at suspended ceilings. Continue framing over frames for doors and openings and frame around ducts penetrating partitions above ceiling to provide support for gypsum board.
 - 1. For STC-rated and fire-resistance-rated partitions that extend to the underside of floor/roof slabs and decks or other continuous solid structural surfaces to obtain ratings, install framing around structural and other members extending below floor/roof slabs and decks, as needed, to support gypsum board closures needed to make partitions continuous from floor to underside of solid structure.
- D. Install steel studs and furring in sizes and at spacings indicated.
 - 1. Single-Layer Construction: Space studs 16 inches (406 mm) o.c., unless otherwise indicated.
- E. Install steel studs so flanges point in the same direction and leading edge or end of each gypsum board panel can be attached to open (unsupported) edges of stud flanges first.
- F. Frame door openings to comply with GA-219, and with applicable published recommendations of gypsum board manufacturer, unless otherwise indicated. Attach vertical studs at jambs with screws either directly to frames or to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.
 - 1. Install 2 studs at each jamb, unless otherwise indicated.
 - 2. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch (12.7-mm) clearance from jamb stud to allow for installation of control joint.
 - 3. Extend jamb studs through suspended ceilings and attach to underside of floor or roof structure above.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- G. Frame openings other than door openings to comply with details indicated or, if none indicated, as required for door openings. Install framing below sills of openings to match framing required above door heads.

3.4 APPLYING AND FINISHING GYPSUM BOARD, GENERAL

- A. Gypsum Board Application and Finishing Standards: Install and finish gypsum panels to comply with ASTM C 840 and GA-216.
- B. Install sound-attenuation blankets, where indicated, prior to installing gypsum panels unless blankets are readily installed after panels have been installed on one side.
- C. Install ceiling board panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in the central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.
- D. Install gypsum panels with face side out. Do not install imperfect, damaged, or damp panels. Butt panels together for a light contact at edges and ends with not more than 1/16 inch (1.5 mm) of open space between panels. Do not force into place.
- E. Locate both edge or end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Avoid joints other than control joints at corners of framed openings where possible.
- F. Attach gypsum panels to steel studs so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.
- G. Attach gypsum panels to framing provided at openings and cutouts.
- H. Form control and expansion joints at locations indicated and as detailed, with space between edges of adjoining gypsum panels, as well as supporting framing behind gypsum panels.
- I. Cover both faces of steel stud partition framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases that are braced internally.
 - 1. Except where concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. (0.7 sq. m) in area.
 - 2. Fit gypsum panels around ducts, pipes, and conduits.
 - 3. Where partitions intersect open concrete coffers, concrete joists, and other structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by coffers, joists, and other structural members; allow 1/4- to 3/8-inch- (6.4- to 9.5-mm-) wide joints to install sealant.
- J. Isolate perimeter of nonload-bearing gypsum board partitions at structural abutments, except floors, as detailed. Provide 1/4- to 1/2-inch- (6.4- to 12.7-mm-) wide spaces at these locations and trim edges with U-bead edge trim where edges of gypsum panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- K. Space fasteners in gypsum panels according to referenced gypsum board application and finishing standard and manufacturer's recommendations.
 - 1. Space screws a maximum of 12 inches (304.8 mm) o.c. for vertical applications.

3.5 GYPSUM BOARD APPLICATION METHODS

- A. Single-Layer Application: Install gypsum wallboard panels as follows:
 - 1. On partitions/walls, apply gypsum panels horizontally (perpendicular to framing), unless parallel application is required for fire-resistance-rated assemblies. Use maximum-length panels to minimize end joints.
 - a. Stagger abutting end joints not less than one framing member in alternate courses of board.
- B. Single-Layer Fastening Methods: Apply gypsum panels to supports as follows:
 - 1. Fasten with screws.

3.6 INSTALLING TRIM ACCESSORIES

- A. General: For trim accessories with back flanges, fasten to framing with the same fasteners used to fasten gypsum board. Otherwise, fasten trim accessories according to accessory manufacturer's directions for type, length, and spacing of fasteners.
- B. Install cornerbead at external corners.
- C. Install edge trim where edge of gypsum panels would otherwise be exposed. Provide edge trim type with face flange formed to receive joint compound, except where other types are indicated.
 - 1. Install LC-bead where gypsum panels are tightly abutted to other construction and back flange can be attached to framing or supporting substrate.
 - 2. Install L-bead where edge trim can only be installed after gypsum panels are installed.
 - 3. Install U-bead where indicated.
 - 4. Install aluminum trim and other accessories where indicated.
- D. Install control joints at locations indicated.

3.7 FINISHING GYPSUM BOARD ASSEMBLIES

- A. General: Treat gypsum board joints, interior angles, flanges of cornerbead, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration.
- B. Prefill open joints, rounded or beveled edges, and damaged areas using setting-type joint compound.
- C. Apply joint tape over gypsum board joints, except those with trim accessories having flanges not requiring tape.
- D. Apply joint tape over gypsum board joints and to flanges of trim accessories as recommended by trim accessory manufacturer.
- E. Levels of Gypsum Board Finish: Provide the following levels of gypsum board finish per GA-214.
 - 1. Level 4 for gypsum board surfaces, unless otherwise indicated.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- F. Use one of the following joint compound combinations as applicable to the finish levels specified:
- G. Use the following joint compound combination as applicable to the finish levels specified:
- H. For Level 4 gypsum board finish, embed tape in joint compound and apply first, fill (second), and finish (third) coats of joint compound over joints, angles, fastener heads, and accessories. Touch up and sand between coats and after last coat as needed to produce a surface free of visual defects and ready for decoration.
- I. Embedding and First Coat: Ready-mixed, drying-type, all-purpose or taping compound. Fill (Second) Coat: Ready-mixed, drying-type, all-purpose or topping compound. Finish (Third) Coat: Ready-mixed, drying-type, all-purpose or topping compound.

3.8 FIELD QUALITY CONTROL

- A. Above-Ceiling Observation: Architect will conduct an above-ceiling observation prior to installation of gypsum board ceilings and report any deficiencies in the Work observed. Do not proceed with installation of gypsum board to ceiling support framing until deficiencies have been corrected.
 - 1. Notify Architect one week in advance of the date and the time when the Project, or part of the Project, will be ready for an above-ceiling observation.

3.9 CLEANING AND PROTECTION

- A. Promptly remove any residual joint compound from adjacent surfaces.
- B. Provide final protection and maintain conditions, in a manner acceptable to Installer, that ensure gypsum board assemblies are without damage or deterioration at the time of Substantial Completion.

END OF SECTION 09255

SECTION 09511 - ACOUSTICAL PANEL CEILINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes ceilings consisting of acoustical panels and exposed suspension systems.

1.3 SUBMITTALS

- A. Product Data: For each type of product specified.
- B. Coordination Drawings: Drawn to scale and coordinating penetrations and ceiling-mounted items. Show the following:
 - 1. Ceiling suspension system members.
 - 2. Method of attaching suspension system hangers to building structure.
 - 3. Ceiling-mounted items including light fixtures; air outlets and inlets; speakers; sprinklers; and special moldings at walls, column penetrations, and other junctures of acoustical ceilings with adjoining construction.
- C. Samples for Initial Selection: Manufacturer's color charts consisting of actual acoustical panels or sections of acoustical panels, suspension systems, and moldings showing the full range of colors, textures, and patterns available for each type of ceiling assembly indicated.
- D. Samples for Verification: Full-size units of each type of ceiling assembly indicated; in sets for each color, texture, and pattern specified, showing the full range of variations expected in these characteristics.
 - 1. 6-inch- (150-mm-) square samples of each acoustical panel type, pattern, and color.
 - 2. Full-size samples of each acoustical panel type, pattern, and color.
 - 3. Set of 12-inch- (300-mm-) long samples of exposed suspension system members, including moldings, for each color and system type required.
- E. Qualification Data: For firms and persons specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- F. Product Test Reports: Indicate compliance of acoustical panel ceilings and components with requirements based on comprehensive testing of current products.
- G. Research/Evaluation Reports: Evidence of acoustical panel ceiling's and components' compliance with building code in effect for Project, from a model code organization acceptable to authorities having jurisdiction.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced installer who has completed acoustical panel ceilings similar in material, design, and extent to that indicated for this Project and with a record of successful in-service performance.
- B. Source Limitations for Ceiling Units: Obtain each acoustical ceiling panel from one source with resources to provide products of consistent quality in appearance and physical properties without delaying the Work.
- C. Source Limitations for Suspension System: Obtain each suspension system from one source with resources to provide products of consistent quality in appearance and physical properties without delaying the Work.
 - 1. Obtain both acoustical ceiling panels and suspension system from the same manufacturer.
- D. Fire-Test-Response Characteristics: Provide acoustical panel ceilings that comply with the following requirements:
 - 1. Fire-response tests were performed by UL, ITS/Warnock Hersey, or another independent testing and inspecting agency that is acceptable to authorities having jurisdiction and that performs testing and follow-up services.
 - 2. Surface-burning characteristics of acoustical panels comply with ASTM E 1264 for Class A materials as determined by testing identical products per ASTM E 84.
 - 3. Fire-resistance-rated assemblies, which are indicated by design designations from UL's "Fire Resistance Directory," from ITS/Warnock Hersey's "Directory of Listed Products," or from the listings of another testing and inspecting agency, are identical in materials and construction to those tested per ASTM E 119.
 - 4. Products are identified with appropriate markings of applicable testing and inspecting agency.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels and suspension system components to Project site in original, unopened packages and store them in a fully enclosed space where they will be protected against damage from moisture, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical panels carefully to avoid chipping edges or damaging units in any way.

1.6 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weatherproof, wet-work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

1.7 COORDINATION

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Coordinate layout and installation of acoustical panels and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system, and partition assemblies.

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.
 - 1. Acoustical Ceiling Units: Full-size units equal to 15.0 percent of amount installed.
 - 2. Suspension System Components: Quantity of each exposed component equal to 15.0 percent of amount installed.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Products: Subject to compliance with requirements, provide one of the products indicated for each designation in the Acoustical Panel Ceiling Schedule at the end of Part 3.

2.2 ACOUSTICAL PANELS, GENERAL

- A. Acoustical Panel Standard: Provide manufacturer's standard panels of configuration indicated that comply with ASTM E 1264 classifications as designated by types, patterns, acoustical ratings, and light reflectances, unless otherwise indicated.
 - 1. Mounting Method for Measuring Noise Reduction Coefficient: Type E-400; plenum mounting in which face of test specimen is 15-3/4 inches (400 mm) away from test surface per ASTM E 795.
- B. Acoustical Panel Colors and Patterns: Match appearance characteristics indicated for each product type.
 - 1. Where appearance characteristics of acoustical panels are indicated by referencing ASTM E 1264 pattern designations and not manufacturers' proprietary product designations, provide products selected by Architect from each manufacturer's full range of products that comply with requirements indicated for type, pattern, color, light reflectance, acoustical performance, edge detail, and size.
- C. Antimicrobial Treatment: Provide acoustical panels treated with manufacturer's standard antimicrobial solution consisting of a synergistic blend of substituted ammonium salts of alkylated phosphoric acids admixed with free alkylated phosphoric acid that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria.
- D. Panel Characteristics: Comply with requirements indicated in the Acoustical Panel Ceiling Schedule at the end of Part 3, including those referencing ASTM E 1264 classifications.

2.3 METAL SUSPENSION SYSTEMS, GENERAL

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Metal Suspension System Standard: Provide manufacturer's standard direct-hung metal suspension systems of types, structural classifications, and finishes indicated that comply with applicable ASTM C 635 requirements.
- B. Metal Suspension System Characteristics: Comply with requirements indicated in the Acoustical Panel Ceiling Schedule at the end of Part 3.
- C. Finishes and Colors, General: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes. Provide manufacturer's standard factory-applied finish for type of system indicated.
- D. Attachment Devices: Size for five times design load indicated in ASTM C 635, Table 1, Direct Hung, unless otherwise indicated.
 - 1. Postinstalled Fasteners: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hangers of type indicated, and with capability to sustain, without failure, a load equal to 10 times that imposed by ceiling construction, as determined by testing per ASTM E 1190, conducted by a qualified testing and inspecting agency.
- E. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
 - 1. Zinc-Coated Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
 - 2. Nickel-Copper-Alloy Wire: ASTM B 164, nickel-copper-alloy UNS No. N04400.
 - 3. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635, Table 1, Direct Hung) will be less than yield stress of wire, but provide not less than 0.106-inch- (2.69-mm-) diameter wire.
- F. Hanger Rods: Mild steel, zinc coated or protected with rust-inhibitive paint.
- G. Flat Hangers: Mild steel, zinc coated or protected with rust-inhibitive paint.
- H. Angle Hangers: Angles with legs not less than 7/8 inch (22 mm) wide; formed with 0.04-inch- (1-mm-) thick, galvanized steel sheet complying with ASTM A 653/A 653M, G90 (Z275) coating designation; with bolted connections and 5/16-inch- (8-mm-) diameter bolts.
- I. Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that fit acoustical panel edge details and suspension systems indicated; formed from sheet metal of same material and finish as that used for exposed flanges of suspension system runners.
 - 1. For lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.
 - 2. For circular penetrations of ceiling, provide edge moldings fabricated to diameter required to fit penetration exactly.
 - 3. For narrow-face suspension systems, provide suspension system and manufacturer's standard edge moldings that match width and configuration of exposed runners.

2.4 ACOUSTICAL SEALANT

- A. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834 and the following requirements:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. Product is effective in reducing airborne sound transmission through perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.
- B. Acoustical Sealant for Concealed Joints: Manufacturer's standard nondrying, nonhardening, nonskinning, nonstaining, gunnable, synthetic-rubber sealant recommended for sealing interior concealed joints to reduce airborne sound transmission.
- C. Products: Subject to compliance with requirements, provide one of the following:
 1. Acoustical Sealant for Exposed and Concealed Joints:
 - a. PL Acoustical Sealant; Chemrex, Inc., Contech Brands.
 - b. AC-20 FTR Acoustical and Insulation Sealant; Pecora Corp.
 - c. SHEETROCK Acoustical Sealant; United States Gypsum Co.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage, and other conditions affecting performance of acoustical panel ceilings.
 1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Coordination: Furnish layouts for cast-in-place anchors, clips, and other ceiling anchors whose installation is specified in other Sections.
 1. Furnish cast-in-place anchors and similar devices to other trades for installation well in advance of time needed for coordinating other work.
- B. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.

3.3 INSTALLATION

- A. General: Install acoustical panel ceilings to comply with publications referenced below per manufacturer's written instructions and CISCA's "Ceiling Systems Handbook."
 1. Standard for Ceiling Suspension System Installations: Comply with ASTM C 636.
 2. Standard for Ceiling Suspension Systems Requiring Seismic Restraint: Comply with ASTM E 580.
 3. CISCA's Guidelines for Systems Requiring Seismic Restraint: Comply with CISCA's "Guidelines for Seismic Restraint of Direct-Hung Suspended Ceiling Assemblies--Seismic Zones 3 & 4."
 4. U.B.C.'s "Metal Suspension Systems for Acoustical Tile and for Lay-in Panel Ceilings": U.B.C. Standard 25-2.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. Suspend ceiling hangers from building's structural members and as follows:
1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 3. Splay hangers only where required and, if permitted with fire-resistance-rated ceilings, to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
 4. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
 5. Secure wire hangers to ceiling suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure; that are appropriate for substrate; and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
 6. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both structure to which hangers are attached and type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
 7. Do not support ceilings directly from permanent metal forms or floor deck.
 8. Do not attach hangers to steel roof deck. Attach hangers to structural members.
 9. Space hangers not more than 48 inches (1200 mm) o.c. along each member supported directly from hangers, unless otherwise indicated; and provide hangers not more than 8 inches (200 mm) from ends of each member.
- C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.
- D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.
 2. Screw attach moldings to substrate at intervals not more than 16 inches (400 mm) o.c. and not more than 3 inches (75 mm) from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet (3 mm in 3.6 m). Miter corners accurately and connect securely.
 3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- E. Install suspension system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- F. Install acoustical panels with undamaged edges and fitted accurately into suspension system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
1. Arrange directionally patterned acoustical panels as follows:
 - a. As indicated on reflected ceiling plans.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2. Paint cut panel edges remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.
3. Protect lighting fixtures and air ducts to comply with requirements indicated for fire-resistance-rated assembly.

3.4 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

3.5 ACOUSTICAL PANEL CEILING SCHEDULE

- A. Cast Mineral-Base Acoustical Panels for Acoustical Panel Ceiling:
Products:
 - a. Manufacturer: Armstrong or equal
 - b. Tile: 24" x 24" square lay-in (Match Existing)
 - c. Grid: Square Lay-I for 15/16" Exposed Tee System

END OF SECTION 09511

SECTION 09653 - RESILIENT WALL BASE AND ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:

- 1. Resilient wall base.

1.3 SUBMITTALS

- A. Product Data: For each type of product specified.
- B. Samples for Initial Selection: Manufacturer's standard sample sets consisting of sections of units showing the full range of colors and patterns available for each type of product indicated.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced installer to perform work of this Section who has specialized in installing resilient products similar to those required for this Project and with a record of successful in-service performance.
- B. Source Limitations: Obtain each type and color of product specified from one source with resources to provide products of consistent quality in appearance and physical properties without delaying the Work.
- C. Fire-Test-Response Characteristics: Provide products with the following fire-test-response characteristics as determined by testing identical products per test method indicated below by a testing and inspecting agency acceptable to authorities having jurisdiction.
 - 1. Critical Radiant Flux: 0.45 W/sq. cm or greater when tested per ASTM E 648.
 - 2. Smoke Density: Maximum specific optical density of 450 or less when tested per ASTM E 662.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver products to Project site in manufacturer's original, unopened cartons and containers, each bearing names of product and manufacturer, Project identification, and shipping and handling instructions.
- B. Store products in dry spaces protected from the weather, with ambient temperatures maintained between 50 and 90 deg F (10 and 32 deg C).
- C. Move products into spaces where they will be installed at least 48 hours before installation, unless longer conditioning period is recommended in writing by manufacturer.

1.6 PROJECT CONDITIONS

- A. Maintain a temperature of not less than 70 deg F (21 deg C) or more than 95 deg F (35 deg C) in spaces to receive resilient products for at least 48 hours before installation, during installation, and for at least 48 hours after installation, unless manufacturer's written recommendations specify longer time periods. After postinstallation period, maintain a temperature of not less than 55 deg F (13 deg C) or more than 95 deg F (35 deg C).
- B. Do not install products until they are at the same temperature as the space where they are to be installed.
- C. For resilient products installed on traffic surfaces, close spaces to traffic during installation and for time period after installation recommended in writing by manufacturer.
- D. Coordinate resilient product installation with other construction to minimize possibility of damage and soiling during remainder of construction period. Install resilient products after other finishing operations, including painting, have been completed.

1.7 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.
 - 1. Furnish not less than 10 linear feet (3 linear m) for each 500 linear feet (150 linear m) or fraction thereof, of each different type, color, pattern, and size of resilient product installed.
 - 2. Deliver extra materials to Owner.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, those indicated in the Resilient Wall Base and Accessory Schedule at the end of Part 3.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. Products: Subject to compliance with requirements, provide one of the products indicated for each designation in the Resilient Wall Base and Accessory Schedule at the end of Part 3.

2.2 RESILIENT WALL BASE

- A. Rubber Wall Base: Products complying with resilient wall base and accessories section 3.5 of this specification section.

2.3 RESILIENT ACCESSORIES

- A. Rubber Accessories: Products complying with requirements specified in the Resilient Wall Base and Accessory Schedule.

2.4 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based formulation provided or approved by resilient product manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by manufacturer to suit resilient products and substrate conditions indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where installation of resilient products will occur, with Installer present, for compliance with manufacturer's requirements, including those for maximum moisture content. Verify that substrates and conditions are satisfactory for resilient product installation and comply with requirements specified. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. General: Comply with manufacturer's written installation instructions for preparing substrates indicated to receive resilient products.
- B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.
- C. Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.

- D. Broom and vacuum clean substrates to be covered immediately before installing resilient products. After cleaning, examine substrates for moisture, alkaline salts, carbonation, or dust. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.3 INSTALLATION

- A. General: Install resilient products according to manufacturer's written installation instructions.
- B. Apply resilient wall base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
 - 1. Install wall base in lengths as long as practicable without gaps at seams and with tops of adjacent pieces aligned.
 - 2. Tightly adhere wall base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
 - 3. Do not stretch base during installation.
 - 4. Form outside corners on job, from straight pieces of maximum lengths possible, without whitening at bends. Shave back of base at points where bends occur and remove strips perpendicular to length of base that are only deep enough to produce a snug fit without removing more than half the wall base thickness.
 - 5. Form inside corners on job, from straight pieces of maximum lengths possible, by cutting an inverted V-shaped notch in toe of wall base at the point where corner is formed. Shave back of base where necessary to produce a snug fit to substrate.
- C. Place resilient products so they are butted to adjacent materials and bond to substrates with adhesive. Install reducer strips at edges of flooring that would otherwise be exposed.

3.4 CLEANING AND PROTECTING

- A. Perform the following operations immediately after installing resilient products:
 - 1. Remove adhesive and other surface blemishes using cleaner recommended by resilient product manufacturers.
 - 2. Sweep or vacuum horizontal surfaces thoroughly.
 - 3. Do not wash resilient products until after time period recommended by resilient product manufacturer.
 - 4. Damp-mop or sponge resilient products to remove marks and soil.
- B. Protect resilient products against mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by resilient product manufacturer.
 - 1. Apply protective floor polish to vinyl resilient products installed on floors and stairs that are free from soil, visible adhesive, and surface blemishes, if recommended by manufacturer.
 - a. Use commercially available product acceptable to resilient product manufacturer.

- b. Coordinate selection of floor polish with Owner's maintenance service.
- 2. Cover resilient products installed on floors and stairs with undyed, untreated building paper until inspection for Substantial Completion.
- C. Clean resilient products not more than 4 days before dates scheduled for inspections intended to establish date of Substantial Completion in each area of Project. Clean products according to manufacturer's written recommendations.
 - 1. Before cleaning, strip protective floor polish that was applied to vinyl products on floors and stairs after completing installation only if required to restore polish finish and if recommended by resilient product manufacturer.
 - 2. After cleaning, reapply polish on vinyl products on floors to restore protective floor finish according to resilient product manufacturer's written recommendations. Coordinate with Owner's maintenance program.

3.5 RESILIENT WALL BASE AND ACCESSORY SCHEDULE

- A. Rubber Wall Base: Where designated, provide rubber wall base complying with the following:
 - 1. Color and Pattern: Roppe 700 series or approved equal by others, color as selected by project manager to match existing building color.
 - 2. Style: 4" straight edge at all locations

END OF SECTION 09653

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 09680 - CARPET

1.1 GENERAL

A. Submittals: As follows:

1. Product Data for each type of product indicated.
2. Samples for each product required.
3. Product schedule using same room and product designations indicated on Drawings and in schedules.
4. Maintenance data for carpet to include in maintenance manuals specified in Division 1.

B. Extra Materials: Furnish 15 percent of amount installed, but not less than 10 sq. yd. (8.3 sq. m).

1.2 PRODUCTS

A. Carpet : **Interface Entropy**

- | | |
|-----------------------|--------------------------------|
| 1. Color and Pattern: | As selected by Project manager |
| Pattern Loop | Looped or Looped Pile |
| Fiber Brand: | Antron Lumina |
| Dye Method: | Solution Dye |
| Adhesive: | Series 2000 Re-attachable |
| Protective Treatment: | Protect |
| Primary Backing: | Synthetic Back |
| Pile Weight: | 20 oz/ sq.yd. |
| Pile Thickness: | .143" |
| Density: | 5035 |
| Gauge: | 12" |
| Flaming Mode: | (ASTM E-648): |
| Smoke Density: | ASTM E 662 – Less than 450 |
| Warranty: | As per State Requirements |

1.3 EXECUTION

- A. Examine substrates, areas, and conditions for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet performance. Verify that substrates and conditions are satisfactory for carpet installation and comply with requirements specified.
1. Concrete Subfloors: Verify that concrete slabs comply with ASTM F 710 and slabs are dry and free of curing compounds, sealers, hardeners, and other materials that may interfere with adhesive bond. Determine adhesion and dryness characteristics by performing bond and moisture tests recommended by **carpet manufacturer**

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. Preparation: Comply with CRI 104, Section 6.2, "Site Conditions; Floor Preparation," and carpet manufacturer's written installation instructions for preparing substrates indicated to receive carpet installation.
- C. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.
- D. Remove coatings, including curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents.
- E. Comply with carpet manufacturer's written recommendations for seam locations and direction of carpet; maintain uniformity of carpet direction and lay of pile. At doorways, center seams under the door in closed position.
- F. Cut and fit carpet to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet manufacturer.
- G. Extend carpet into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- H. Install pattern as per manufactures recommendations
- I. Perform the following operations immediately after installing carpet:
 - 1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet manufacturer.
 - 2. Remove yarns that protrude from carpet surface.
 - 3. Vacuum carpet using commercial machine with face-beater element.
- J. Protect installed carpet to comply with CRI 104, Section 15, "Protection of Indoor Installations."

END OF SECTION 09680

SECTION 09900 - PAINTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes surface preparation and field painting of the following:
 - 1. Surface preparation, priming, and finish coats specified in this Section are in addition to shop priming and surface treatment specified in other Sections.
- B. Paint exposed surfaces, except where the paint schedules indicate that a surface or material is not to be painted or is to remain natural. If the paint schedules do not specifically mention an item or a surface, paint the item or surface the same as similar adjacent materials or surfaces whether or not schedules indicate colors. If the schedules do not indicate color or finish, the Architect will select from standard colors and finishes available.
 - 1. Painting includes field painting of exposed bare and covered pipes and ducts (including color coding), hangers, exposed steel and iron work, and primed metal surfaces of mechanical and electrical equipment.
- C. Do not paint prefinished items, concealed surfaces, finished metal surfaces, operating parts, and labels.
 - 1. Prefinished items include the following factory-finished components:
 - a. Finished mechanical and electrical equipment.
 - b. Light fixtures.
 - c. Distribution cabinets.
 - d. Aluminum window frames and doors
 - 2. Concealed surfaces include walls or ceilings in the following generally inaccessible spaces:
 - a. Foundation spaces.
 - b. Furred areas.
 - c. Ceiling plenums.
 - d. Utility tunnels.
 - e. Pipe spaces.
 - f. Duct shafts.
 - 3. Finished metal surfaces include the following:
 - a. Anodized aluminum.
 - b. Stainless steel.
 - c. Chromium plate.
 - d. Copper.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- e. Bronze and brass.
- 4. Operating parts include moving parts of operating equipment and the following:
 - a. Valve and damper operators.
 - b. Linkages.
 - c. Sensing devices.
 - d. Motor and fan shafts.
- 5. Labels: Do not paint over Underwriters Laboratories (UL), Factory Mutual (FM), or other code-required labels or equipment name, identification, performance rating, or nomenclature plates.
- D. Related Sections include the following:
 - 1. Division 8 Section "Steel Doors and Frames" for shop priming steel doors and frames.
 - 2. Division 9 Section "Gypsum Board Assemblies" for surface preparation for gypsum board.

1.3 DEFINITIONS

- A. General: Standard coating terms defined in ASTM D 16 apply to this Section.
 - 1. Flat refers to a lusterless or matte finish with a gloss range below 15 when measured at an 85-degree meter.
 - 2. Eggshell refers to low-sheen finish with a gloss range between 5 and 20 when measured at a 60-degree meter.
 - 3. Satin refers to low-sheen finish with a gloss range between 15 and 35 when measured at a 60-degree meter.
 - 4. Semigloss refers to medium-sheen finish with a gloss range between 30 and 65 when measured at a 60-degree meter.
 - 5. Full gloss refers to high-sheen finish with a gloss range more than 65 when measured at a 60-degree meter.

1.4 SUBMITTALS

- A. Product Data: For each paint system specified. Include block fillers and primers.
 - 1. Material List: Provide an inclusive list of required coating materials. Indicate each material and cross-reference specific coating, finish system, and application. Identify each material by manufacturer's catalog number and general classification.
 - 2. Manufacturer's Information: Provide manufacturer's technical information, including label analysis and instructions for handling, storing, and applying each coating material proposed for use.
 - 3. Certification by the manufacturer that products supplied comply with local regulations controlling use of volatile organic compounds (VOCs).
- B. Samples for Initial Selection: Manufacturer's color charts showing the full range of colors available for each type of finish-coat material indicated.
 - 1. After color selection, the Architect will furnish color chips for surfaces to be coated.
- C. Samples for Verification: Of each color and material to be applied, with texture to simulate actual conditions, on representative Samples of the actual substrate.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. Provide stepped Samples, defining each separate coat, including block fillers and primers. Use representative colors when preparing Samples for review. Resubmit until required sheen, color, and texture are achieved.
 2. Provide a list of materials and applications for each coat of each sample. Label each sample for location and application.
 3. Submit Samples on the following substrates for the Architect's review of color and texture only:
 - a. Stained or Natural Wood: Provide two 4-by-8-inch (100-by-200-mm) samples of natural- or stained-wood finish on actual wood surfaces.
- D. Qualification Data: For firms and persons specified in the "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.

1.5 QUALITY ASSURANCE

- A. Applicator Qualifications: Engage an experienced applicator who has completed painting system applications similar in material and extent to that indicated for this Project with a record of successful in-service performance.
- B. Source Limitations: Obtain block fillers, primers, and undercoat materials for each coating system from the same manufacturer as the finish coats.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to the Project Site in manufacturer's original, unopened packages and containers bearing manufacturer's name and label, and the following information:
 1. Product name or title of material.
 2. Product description (generic classification or binder type).
 3. Manufacturer's stock number and date of manufacture.
 4. Contents by volume, for pigment and vehicle constituents.
 5. Thinning instructions.
 6. Application instructions.
 7. Color name and number.
 8. VOC content.
- B. Store materials not in use in tightly covered containers in a well-ventilated area at a minimum ambient temperature of 45 deg F (7 deg C). Maintain containers used in storage in a clean condition, free of foreign materials and residue.
 1. Protect from freezing. Keep storage area neat and orderly. Remove oily rags and waste daily. Take necessary measures to ensure that workers and work areas are protected from fire and health hazards resulting from handling, mixing, and application.

1.7 PROJECT CONDITIONS

- A. Apply water-based paints only when the temperature of surfaces to be painted and surrounding air temperatures are between 50 and 90 deg F (10 and 32 deg C).
- B. Apply solvent-thinned paints only when the temperature of surfaces to be painted and surrounding air temperatures are between 45 and 95 deg F (7.2 and 35 deg C).

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- C. Do not apply paint in snow, rain, fog, or mist; or when the relative humidity exceeds 85 percent; or at temperatures less than 5 deg F (3 deg C) above the dew point; or to damp or wet surfaces.
 - 1. Painting may continue during inclement weather if surfaces and areas to be painted are enclosed and heated within temperature limits specified by manufacturer during application and drying periods.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers Names: The following manufacturers are referred to in the paint schedules by use of shortened versions of their names, which are shown in parentheses:
 - 1. Devoe & Raynolds Co. (Devoe).
 - 2. Fuller-O'Brien Paints (Fuller).
 - 3. Glidden Co. (The) (Glidden).
 - 4. Benjamin Moore & Co. (Moore).
 - 5. PPG Industries, Inc. (PPG).
 - 6. Pratt & Lambert, Inc. (P & L).
 - 7. Sherwin-Williams Co. (S-W).
 - 8. Kwal-Howells
 - 9. Others as pre-approved.

2.2 PAINT MATERIALS, GENERAL

- A. Material Compatibility: Provide block fillers, primers, undercoats, and finish-coat materials that are compatible with one another and the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.
- B. Material Quality: Provide manufacturer's best-quality paint material of the various coating types specified. Paint-material containers not displaying manufacturer's product identification will not be acceptable.
 - 1. Proprietary Names: Use of manufacturer's proprietary product names to designate colors or materials is not intended to imply that products named are required to be used to the exclusion of equivalent products of other manufacturers. Furnish manufacturer's material data and certificates of performance for proposed substitutions.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with the Applicator present, under which painting will be performed for compliance with paint application requirements.
 - 1. Do not begin to apply paint until unsatisfactory conditions have been corrected and surfaces receiving paint are thoroughly dry.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2. Start of painting will be construed as the Applicator's acceptance of surfaces and conditions within a particular area.

- B. Coordination of Work: Review other Sections in which primers are provided to ensure compatibility of the total system for various substrates. On request, furnish information on characteristics of finish materials to ensure use of compatible primers.

3.2 PREPARATION

- A. General: Remove hardware and hardware accessories, plates, machined surfaces, lighting fixtures, and similar items already installed that are not to be painted. If removal is impractical or impossible because of the size or weight of the item, provide surface-applied protection before surface preparation and painting.
 1. After completing painting operations in each space or area, reinstall items removed using workers skilled in the trades involved.
- B. Cleaning: Before applying paint or other surface treatments, clean the substrates of substances that could impair the bond of the various coatings. Remove oil and grease before cleaning.
 1. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces.
- C. Surface Preparation: Clean and prepare surfaces to be painted according to manufacturer's written instructions for each particular substrate condition and as specified.
 1. Provide barrier coats over incompatible primers or remove and reprime.
 2. Ferrous Metals: Clean ungalvanized ferrous-metal surfaces that have not been shop coated; remove oil, grease, dirt, loose mill scale, and other foreign substances. Use solvent or mechanical cleaning methods that comply with the Steel Structures Painting Council's (SSPC) recommendations.
 - a. Blast steel surfaces clean as recommended by paint system manufacturer and according to requirements of SSPC-SP 10.
 - b. Treat bare and sandblasted or pickled clean metal with a metal treatment wash coat before priming.
 - c. Touch up bare areas and shop-applied prime coats that have been damaged. Wire-brush, clean with solvents recommended by paint manufacturer, and touch up with the same primer as the shop coat.
 3. Galvanized Surfaces: Clean galvanized surfaces with nonpetroleum-based solvents so surface is free of oil and surface contaminants. Remove pretreatment from galvanized sheet metal fabricated from coil stock by mechanical methods.
- D. Materials Preparation: Mix and prepare paint materials according to manufacturer's written instructions.
 1. Maintain containers used in mixing and applying paint in a clean condition, free of foreign materials and residue.
 2. Stir material before application to produce a mixture of uniform density. Stir as required during application. Do not stir surface film into material. If necessary, remove surface film and strain material before using.
 3. Use only thinners approved by paint manufacturer and only within recommended limits.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- E. Tinting: Tint each undercoat a lighter shade to simplify identification of each coat when multiple coats of the same material are applied. Tint undercoats to match the color of the finish coat, but provide sufficient differences in shade of undercoats to distinguish each separate coat.

3.3 APPLICATION

- A. General: Apply paint according to manufacturer's written instructions. Use applicators and techniques best suited for substrate and type of material being applied.
1. Do not paint over dirt, rust, scale, grease, moisture, scuffed surfaces, or conditions detrimental to formation of a durable paint film.
 2. Provide finish coats that are compatible with primers used.
 3. The term "exposed surfaces" includes areas visible when permanent or built-in fixtures, convactor covers, covers for finned-tube radiation, grilles, and similar components are in place. Extend coatings in these areas, as required, to maintain the system integrity and provide desired protection.
 4. Paint surfaces behind movable equipment and furniture the same as similar exposed surfaces. Before the final installation of equipment, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
 5. Paint interior surfaces of ducts with a flat, nonspecular black paint where visible through registers or grilles.
 6. Paint back sides of access panels and removable or hinged covers to match exposed surfaces.
 7. Sand lightly between each succeeding enamel or varnish coat.
- B. Scheduling Painting: Apply first coat to surfaces that have been cleaned, pretreated, or otherwise prepared for painting as soon as practicable after preparation and before subsequent surface deterioration.
1. The number of coats and the film thickness required are the same regardless of application method. Do not apply succeeding coats until the previous coat has cured as recommended by the manufacturer. If sanding is required to produce a smooth, even surface according to manufacturer's written instructions, sand between applications.
 2. Omit primer on metal surfaces that have been shop primed and touchup painted.
 3. If undercoats, stains, or other conditions show through final coat of paint, apply additional coats until paint film is of uniform finish, color, and appearance. Give special attention to ensure edges, corners, crevices, welds, and exposed fasteners receive a dry film thickness equivalent to that of flat surfaces.
 4. Allow sufficient time between successive coats to permit proper drying. Do not recoat surfaces until paint has dried to where it feels firm, does not deform or feel sticky under moderate thumb pressure, and where application of another coat of paint does not cause the undercoat to lift or lose adhesion.
- C. Application Procedures: Apply paints and coatings by brush, roller, spray, or other applicators according to manufacturer's written instructions.
1. Brushes: Use brushes best suited for the type of material applied. Use brush of appropriate size for the surface or item being painted.
 2. Rollers: Use rollers of carpet, velvet back, or high-pile sheep's wool as recommended by the manufacturer for the material and texture required.
 3. Spray Equipment: Use airless spray equipment with orifice size as recommended by the manufacturer for the material and texture required.
- D. Minimum Coating Thickness: Apply paint materials no thinner than manufacturer's recommended spreading rate. Provide the total dry film thickness of the entire system as recommended by the manufacturer.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- E. Mechanical and Electrical Work: Painting of mechanical and electrical work is limited to items exposed in equipment rooms and in occupied spaces.
- F. finish coats, apply a prime coat of material, as recommended by the manufacturer, to material that is required to be painted or finished and that has not been prime coated by others. Recoat primed and sealed surfaces where evidence of suction spots or unsealed areas in first coat appears, to ensure a finish coat with no burn through or other defects due to insufficient sealing.
- G. Transparent (Clear) Finishes: Use multiple coats to produce a glass-smooth surface film of even luster. Provide a finish free of laps, runs, cloudiness, color irregularity, brush marks, orange peel, nail holes, or other surface imperfections.
 - 1. Provide satin finish for final coats.
- H. Completed Work: Match approved samples for color, texture, and coverage. Remove, refinish, or repaint work not complying with requirements.

3.4 FIELD QUALITY CONTROL

- A. The Owner reserves the right to invoke the following test procedure at any time and as often as the Owner deems necessary during the period when paint is being applied:
 - 1. The Owner will engage the services of an independent testing agency to sample the paint material being used. Samples of material delivered to the Project will be taken, identified, sealed, and certified in the presence of the Contractor.
 - 2. The testing agency will perform appropriate tests for the following characteristics as required by the Owner:
 - a. Quantitative material analysis.
 - b. Abrasion resistance.
 - c. Apparent reflectivity.
 - d. Flexibility.
 - e. Washability.
 - f. Absorption.
 - g. Accelerated weathering.
 - h. Dry opacity.
 - i. Accelerated yellowness.
 - j. Recoating.
 - k. Skinning.
 - l. Color retention.
 - m. Alkali and mildew resistance.
 - 3. The Owner may direct the Contractor to stop painting if test results show material being used does not comply with specified requirements. The Contractor shall remove noncomplying paint from the site, pay for testing, and repaint surfaces previously coated with the rejected paint. If necessary, the Contractor may be required to remove rejected paint from previously painted surfaces if, on repainting with specified paint, the 2 coatings are incompatible.

3.5 CLEANING

- A. Cleanup: At the end of each workday, remove empty cans, rags, rubbish, and other discarded paint materials from the site.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. After completing painting, clean glass and paint-spattered surfaces. Remove spattered paint by washing and scraping. Be careful not to scratch or damage adjacent finished surfaces.

3.6 PROTECTION

- A. Protect work of other trades, whether being painted or not, against damage by painting. Correct damage by cleaning, repairing or replacing, and repainting.
- B. Provide "Wet Paint" signs to protect newly painted finishes. Remove temporary protective wrappings provided by others to protect their work after completing painting operations.
 1. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in PDCA PI.

3.7 INTERIOR PAINT SCHEDULE

- A. Gypsum Board: Provide the following finish systems over interior gypsum board surfaces where designated by architect:
 1. Low-Luster, Acrylic-Enamel Finish: 2 finish coats over a primer.
 - a. Primer: Latex-based, interior primer applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.2 mils (0.031 mm).
 - 1) Devoe: 50801 Wonder-Tones Interior Vinyl Latex Primer-Sealer.
 - 2) Fuller: 220-20 Pro-Tech Interior Latex Wall Primer and Sealer.
 - 3) Glidden: 5111 Spred Ultra Latex Primer-Sealer.
 - 4) Moore: Regal First Coat Interior Latex Primer & Underbody #216.
 - 5) PPG: 17-10 Quick-Drying Interior Latex Primer-Sealer.
 - 6) P & L: Z/F 1004 Suprime "4" Interior Latex Wall Primer.
 - 7) Kwal-Howells: 0880 Latex Sealer
 - b. First and Second Coats: Low-luster (eggshell or satin), acrylic-latex, interior enamel applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 2.8 mils (0.071 mm).
 - 1) Devoe: 34XX Wonder-Tones Interior Latex Eggshell Enamel.
 - 2) Fuller: 212-XX AA Enamel Acrylic Latex Eggshell Enamel.
 - 3) Glidden: 4100 Series Spred Ultra Eggshell Latex Wall & Trim Paint.
 - 4) Moore: Moore's Regal AquaVelvet #319.
 - 5) PPG: 89 Line Manor Hall Eggshell Latex Wall and Trim Enamel.
 - 6) P & L: Z/F 4000 Series Accolade Interior Velvet.
 - 7) Kwal-Howells: 1902 Latex Low Sheen Enamel
 2. Semigloss, Acrylic-Enamel Finish: 2 finish coats over a primer.
 - a. Primer: Latex-based, interior primer applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.2 mils (0.031 mm).
 - 1) Devoe: 50801 Wonder-Tones Interior Vinyl Latex Primer-Sealer.
 - 2) Fuller: 220-20 Pro-Tech Latex Wall Primer Sealer, White.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- 3) Glidden: 5111 Spred Ultra Latex Primer-Sealer.
 - 4) Moore: Regal First Coat Interior Latex Primer & Underbody #216.
 - 5) PPG: 17-10 Quick-Drying Interior Latex Primer-Sealer.
 - 6) P & L: Z/F 1001 Suprime "1" 100 Percent Acrylic Multi-Purpose Primer.
 - 7) Kwal-Howells: 0880 Latex Sealer
- b. First and Second Coats: Semigloss, acrylic-latex, interior enamel applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 2.6 mils (0.066 mm).
- 1) Devoe: 39XX Wonder-Tones Semi-Gloss Interior Latex Enamel.
 - 2) Fuller: 214-XX AA Enamel Interior Acrylic Latex Semi-Gloss Enamel.
 - 3) Glidden: 8200 Series Spred Ultra Latex Semi-Gloss Enamel.
 - 4) Moore: Moore's Regal AquaGlo Vinyl-Acrylic Latex Enamel #333.
 - 5) PPG: 88-110 Satinhide Interior Enamel Wall & Trim Lo-Lustre Semi-Gloss Latex.
 - 6) P & L: Z/F 4100 Series Accolade Interior Semi-Gloss.
 - 7) Kwal-Howells: 2900 Acrylic Enamel
- B. Woodwork and Hardboard: Provide the following paint finish systems over new, interior wood surfaces:
- C. Stained Woodwork: Provide the following stained finishes over new, interior woodwork:
1. Waterborne, Satin-Varnish Finish: 2 finish coats of a waterborne, clear-satin varnish over a sealer coat and a waterborne, interior wood stain. Wipe wood filler before applying stain.
 - a. Filler Coat: Paste-wood filler applied at spreading rate recommended by the manufacturer.
 - 1) Devoe: None required.
 - 2) Moore: Benwood Paste Wood Filler #238.
 - 3) PPG: None required.
 - 4) P & L: None required.
 - b. Stain Coat: Waterborne, interior wood stain applied at spreading rate recommended by the manufacturer.
 - 1) Devoe: 41XX WoodWorks Waterborne Interior Stain.
 - 2) Moore: Benwood Penetrating Stain #234.
 - 3) PPG: 77-302 Rez Interior Semi-Transparent Stain.
 - 4) P & L: Z 197 Acrylic Latex Stain Interior.
 - c. Sealer Coat: Clear sanding sealer applied at spreading rate recommended by the manufacturer.
 - 1) Devoe: 4200 WoodWorks Waterborne Quick-Dry Clear Sealer.
 - 2) Moore: None recommended.
 - 3) PPG: 77-30 Rez Interior Quick-Drying Sealer and Finish.
 - 4) P & L: Z 7520 Latex Sanding Sealer.
 - d. First and Second Finish Coats: Waterborne, varnish finish applied at spreading rate recommended by the manufacturer.
 - 1) Devoe: 4300 WoodWorks Waterborne Crystal Clear Finish, Satin.
 - 2) Moore: Stays Clear Acrylic Polyurethane #423, Satin.
 - 3) PPG: 77-49 Rez Satin Acrylic Clear Polyurethane.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

4) P & L: Z 17 Acrylic Latex Varnish, Satin.

D. Natural-Finish Woodwork: Provide the following natural finishes over new, interior woodwork:

1. Waterborne, Satin-Varnish Finish: 2 finish coats of a waterborne, clear-satin varnish over a sanding sealer. Wipe wood filler before applying stain.
 - a. Filler Coat: Paste-wood filler applied at spreading rate recommended by the manufacturer.
 - 1) Devoe: None required.
 - 2) Moore: Benwood Paste Wood Filler #238.
 - 3) PPG: None required.
 - 4) P & L: None required.
 - b. Sealer Coat: Clear sanding sealer applied at spreading rate recommended by the manufacturer.
 - 1) Devoe: 4200 WoodWorks Waterborne Quick-Dry Clear Sealer.
 - 2) Moore: None recommended.
 - 3) PPG: 77-30 Rez Interior Quick-Drying Sealer and Finish.
 - 4) P & L: Z 7520 Latex Sanding Sealer.
 - c. First and Second Finish Coats: Waterborne, varnish finish applied at spreading rate recommended by the manufacturer.
 - 1) Devoe: 4300 WoodWorks Waterborne Crystal Clear Finish, Satin.
 - 2) Moore: Stays Clear Acrylic Polyurethane #423, Satin.
 - 3) PPG: 77-49 Rez Satin Acrylic Clear Polyurethane.
 - 4) P & L: Z 17 Acrylic Latex Varnish, Satin.

E. Ferrous Metal: Provide the following finish systems over ferrous metal:

1. Semigloss, Alkyd-Enamel Finish: One finish coat over an enamel undercoater and a primer.
 - a. Primer: Quick-drying, rust-inhibitive, alkyd-based or epoxy-metal primer, as recommended by the manufacturer for this substrate, applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.5 mils (0.038 mm).
 - 1) Devoe: 13101 Mirrolac Rust Penetrating Metal Primer.
 - 2) Fuller: 621-04 Blox-Rust Alkyd Metal Primer.
 - 3) Glidden: 5207 Glid-Guard Tank & Structural Primer, White.
 - 4) Moore: IronClad Retardo Rust-Inhibitive Paint #163.
 - 5) PPG: 6-208 Speedhide Interior/Exterior Rust Inhibitive Steel Primer.
 - 6) P & L: S 4551 Tech-Gard High Performance Rust Inhibitor Primer.
 - 7) S-W: Kem Kromik Metal Primer B50N2/B50W1.
 - b. Undercoat: Alkyd, interior enamel undercoat or semigloss, interior, alkyd-enamel finish coat, as recommended by the manufacturer for this substrate, applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.2 mils (0.031 mm).
 - 1) Devoe: 26XX Velour Interior Alkyd Semi-Gloss Enamel.
 - 2) Fuller: 220-07 Interior Alkyd Enamel Undercoat.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- 3) Glidden: UH 8400 Ultra Traditional Alkyd Semi-Gloss Enamel.
 - 4) Moore: Moore's Alkyd Enamel Underbody #217.
 - 5) PPG: 6-6 Speedhide Interior Quick-Drying Enamel Undercoater.
 - 6) P & L: S/D 1011 Suprime "11" Interior Alkyd Wood Primer.
 - 7) S-W: ProMar 200 Interior Alkyd Semi-Gloss Enamel B34W200.
- c. Finish Coat: Odorless, semigloss, alkyd, interior enamel applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.4 mils (0.036 mm).
- 1) Devoe: 26XX Velour Interior Alkyd Semi-Gloss Enamel.
 - 2) Fuller: 110-XX Fullerglo Alkyd Semi-Gloss Enamel.
 - 3) Glidden: UH 8400 Ultra Traditional Alkyd Semi-Gloss Enamel.
 - 4) Moore: Satin Impervo #235.
 - 5) PPG: 27 Line Wallhide Low Odor Interior Enamel Wall and Trim Semi-Gloss Oil.
 - 6) P & L: S/D 5700 Cellu-Tone Alkyd Satin Enamel.
 - 7) S-W: Classic 99 Interior/Exterior Semi-Gloss Alkyd Enamel A-40 Series.
2. Full-Gloss, Alkyd-Enamel Finish: 2 finish coats over an enamel undercoater and a primer.
- a. Primer: Quick-drying, rust-inhibitive, alkyd-based or epoxy-metal primer, as recommended by the manufacturer for this substrate, applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.5 mils (0.038 mm).
- 1) Devoe: 13101 Mirrolac Rust Penetrating Metal Primer.
 - 2) Fuller: 621-04 Blox-Rust Alkyd & Structural Metal Primer.
 - 3) Glidden: 5207 Glid-Guard Tank & Structural Primer, White.
 - 4) Moore: IronClad Retardo Rust-Inhibitive Paint #163.
 - 5) PPG: 6-208 Speedhide Interior/Exterior Rust Inhibitive Steel Primer.
 - 6) P & L: S 4551 Tech-Gard High Performance Rust Inhibitor Primer.
 - 7) S-W: Kem Kromik Metal Primer B50N2/B50W1.
- b. Undercoat: Alkyd, interior enamel undercoat or full-gloss, interior, alkyd-enamel finish coat, as recommended by the manufacturer for this substrate, applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.2 mils (0.031 mm).
- 1) Devoe: 70XX Mirrolac Interior/Exterior Alkyd-Urethane Gloss Enamel.
 - 2) Fuller: 220-07 Interior Alkyd Enamel Undercoat.
 - 3) Glidden: 4500 Series Glid-Guard Alkyd Industrial Enamel.
 - 4) Moore: Moore's Alkyd Enamel Underbody #217.
 - 5) PPG: 6-6 Speedhide Interior Quick-Drying Enamel Undercoater.
 - 6) P & L: S/D 1001 Suprime "11" Interior Alkyd Wood Primer.
 - 7) S-W: Industrial Enamel B-54 Series.
- c. Finish Coat: Full-gloss, alkyd, interior enamel applied at spreading rate recommended by the manufacturer to achieve a total dry film thickness of not less than 1.2 mils (0.031 mm).
- 1) Devoe: 70XX Mirrolac Interior/Exterior Alkyd-Urethane Gloss Enamel.
 - 2) Fuller: 312-XX EPA Compliant Heavy-Duty Enamel.
 - 3) Glidden: 4500 Series Glid-Guard Alkyd Industrial Enamel.
 - 4) Moore: Impervo Enamel #133.
 - 5) PPG: 54 Line Pittsburgh Paints Gloss-Oil Interior/Exterior Enamels.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- 6) P & L: S/D 1100 Series Effecto Enamel.
- 7) S-W: Industrial Enamel B-54 Series.
- 8) Enamel.
- 9) P & L: Z/F 1003 Suprime "3" Interior/Exterior Latex Metal Primer.
- 10) S-W: Galvite Paint B50W3.

END OF SECTION 09900

SECTION 10100 - VISUAL DISPLAY BOARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Porcelain enamel markerboards.

1.3 SUBMITTALS

- A. Shop Drawings: For each type of visual display board required.
 - 1. Include dimensioned elevations. Show location of joints between individual panels where unit dimensions exceed maximum panel length.
 - 2. Include sections of typical trim members.
 - 3. Show anchors, grounds, reinforcement, accessories, layout, and installation details.
- B. Samples for Verification: Of the following products, showing color and texture or finish selected. Where finishes involve normal color and texture variations, include Sample sets showing the full range of variations expected. Prepare Samples from the same material to be used for the Work.
 - 1. Visual Display Boards: Sample panels not less than 8-1/2 by 11 inches (215 by 280 mm), mounted on the substrate indicated for the final Work. Include a panel for each type, color, and texture required.
 - 2. Aluminum Trim and Accessories: Samples of each finish type and color, on 6-inch- (150-mm-) long sections of extrusions and not less than 4-inch (100-mm) squares of sheet or plate. Include Sample sets showing the full range of color variations expected.

1.4 QUALITY ASSURANCE

- A. Source Limitations: Obtain visual display boards through one source from a single manufacturer.
- B. Product Options: Drawings indicate size, profiles, and dimensional requirements of visual display boards and are based on the products indicated. Other manufacturers' products with equal performance characteristics may be considered. Refer to Division 1 Section "Substitutions."
 - 1. Do not modify intended aesthetic effects, as judged solely by Architect, except with Architect's approval and only to the extent needed to comply with performance requirements. Where modifications are proposed, submit comprehensive explanatory data to Architect for review.
- C. Fire-Test-Response Characteristics: Provide tackboards with the following surface-burning characteristics as determined by testing assembled materials composed of facings and backings identical

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

to those required in this Section per ASTM E 84 by a testing and inspecting agency acceptable to authorities having jurisdiction.

1. Flame Spread: 25 or less.
2. Smoke Developed: 10 or less.

1.5 PROJECT CONDITIONS

- A. Field Measurements: Verify field measurements before preparation of Shop Drawings and before fabrication to ensure proper fitting. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
 1. Allow for trimming and fitting where taking field measurements before fabrication might delay the Work.
 2. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating chalkboards without field measurements. Coordinate wall construction to ensure actual dimensions correspond to established dimensions.

1.6 WARRANTY

- A. General Warranty: The special porcelain enamel chalkboard warranty specified in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by the Contractor under requirements of the Contract Documents.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
- B. Manufacturer: Subject to compliance with requirements, provide products by one of the following:
 1. Porcelain Enamel Markerboards:
 - a. Best-Rite Chalkboard Co.
 - b. Carolina Chalkboard Co.
 - c. Claridge Products and Equipment, Inc.
 - d. Ghent Manufacturing, Inc.
 - e. Greensteel, Inc.
 - f. Lemco, Inc.
 - g. Marsh Chalkboard Company.
 - h. Nelson Adams Company.

2.2 MATERIALS

- A. Markerboards: Balanced, high-pressure-laminated, porcelain enamel markerboard of 3-ply construction consisting of face sheet, core material, and backing.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. Face Sheet: 0.024-inch- (0.61-mm-), "Vitracite," porcelain enamel clad, Type 1, stretcher-leveled aluminized-steel face sheet, as manufactured by Claridge Products and Equipment. Fuse porcelain enamel coating to steel at approximately 1000 deg F (540 deg C).
 - a. Cover Coat: Provide manufacturer's standard, light-colored, special writing surface with gloss finish intended for use with erasable dry markers.
2. Core: 3/8-inch- (9.5-mm-) thick, particleboard core material complying with requirements of ANSI A208.1, Grade 1-M-1.
3. Backing Sheet: 0.018-inch- (0.46-mm-) thick, galvanized steel sheet backing.
4. Laminating Adhesive: Manufacturer's standard, moisture-resistant, thermoplastic-type adhesive.

2.3 ACCESSORIES

- A. Metal Trim and Accessories: Fabricate frames and trim of not less than 0.062-inch- (1.57-mm-) thick, extruded-aluminum alloy, size and shape as indicated, to suit type of installation. Provide straight, single-length units. Keep joints to a minimum. Miter corners to a neat, hairline closure.
 1. Where size of visual display boards or other conditions require support in addition to normal trim, provide structural supports or modify trim as indicated or as selected by Architect from manufacturer's standard structural support accessories to suit conditions indicated.
 2. Field-Applied Trim: Manufacturer's standard snap-on trim with no visible screws or exposed joints.
 3. Chalktray: Manufacturer's standard, continuous, solid, extrusion-type, aluminum chalktray with ribbed section and smoothly curved exposed ends for each chalkboard.
 4. Map Rail: Furnish map rail at top of each unit, complete with the following accessories:
 - a. Display Rail: Provide continuous cork display rail approximately 1 or 2 inches (25 or 50 mm) wide, as indicated, integral with map rail.
 - b. End Stops: Provide one end stop at each end of map rail.
 - c. Map Hooks: Provide 2 map hooks with flexible metal clips for every 48 inches (1220 mm) of map rail or fraction thereof.

2.4 FINISHES

- A. General: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations relative to applying and designating finishes.
- B. Finish designations prefixed by AA conform to the system established by the Aluminum Association for designating aluminum finishes.
- C. Class II, Clear Anodic Finish: AA-M12C22A31 (Mechanical Finish: nonspecular as fabricated; Chemical Finish: etched, medium matte; Anodic Coating: Architectural Class II, clear coating 0.010 mm or thicker) complying with AAMA 607.1.

PART 3 - EXECUTION

3.1 EXAMINATION

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Examine wall surfaces, with Installer present, for compliance with requirements and other conditions affecting installation of visual display boards.
 - 1. Surfaces to receive markerboards shall be free of dirt, scaling paint, and projections or depressions that would affect smooth, finished surfaces of markerboards.
 - 2. Do not proceed with installation until unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Deliver factory-built visual display boards completely assembled in one piece without joints, where possible. If dimensions exceed panel size, provide 2 or more pieces of equal length as acceptable to Architect. When overall dimensions require delivery in separate units, prefit components at the factory, disassemble for delivery, and make final joints at the site. Use splines at joints to maintain surface alignment.
- B. Install units in locations and at mounting heights indicated and according to manufacturer's written instructions. Keep perimeter lines straight, plumb, and level. Provide grounds, clips, backing materials, adhesives, brackets, anchors, trim, and accessories necessary for complete installation.
- C. Coordinate Project-site-assembled units with grounds, trim, and accessories. Join parts with a neat, precision fit.

3.3 ADJUSTING AND CLEANING

- A. Verify that accessories required for each unit have been properly installed and that operating units function properly.
- B. Clean units according to manufacturer's written instructions.

END OF SECTION 10100

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16001 - ELECTRICAL GENERAL PROVISIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification sections, apply to work of this section.
- B. Architectural, Structural, Mechanical and other applicable documents also apply to work of this section.

1.2 DESCRIPTION OF WORK:

- A. The contract documents indicate the extent of electrical work. Provide all labor, materials, equipment, supervision and service necessary for a complete electrical system as described in division 16.

1.3 RELATED SECTIONS:

- A. Other Divisions relating to electrical work apply to the work of this section. See other applicable Divisions including, but not necessarily limited to:

- 1. Division 1 - General and Supplementary Conditions
- 2. Division 2 - Existing Conditions
- 3. Division 3 - Concrete
- 4. Division 5 - Metals
- 5. Division 6 - Wood, Plastics, and Composites
- 6. Division 7 - Thermal and Moisture Protection
- 7. Division 8 - Openings
- 8. Division 9 - Finishes
- 9. Division 15 - Mechanical
- 10. Division 16 - Electrical

1.4 INTERPRETATIONS OF DRAWINGS AND SPECIFICATIONS:

- A. Prior to bidding the job, submit requests for clarification in writing to the Architect/Engineer prior to issuance of the final addendum.
- B. After signing the contract, provide all materials, labor, and equipment to meet the intent, purpose, and function of the contract documents.
- C. The following terms used in Division 16 documents are defined as follows:
 - 1. "Provide" - Means furnish, install, and connect, unless otherwise indicated.
 - 2. "Furnish" - Means purchase new and deliver in operating order to project site.
 - 3. "Install" - Means to physically install the items in-place.
 - 4. "Connect" - Means make final electrical connections for a complete operating piece of equipment. This includes providing conduit, wire, terminations, etc. as applicable.
 - 5. "Or Equivalent" - Means to provide equivalent equipment. Such equipment must be approved by the Engineer prior to bidding.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1.5 EXAMINATION OF SITE:

- A. Visit the site and verify existing field conditions prior to submitting bid.
- B. All costs arising from site conditions and/or preparation shall be included in the base bid. No additional charges will be allowed due to inadequate site inspection.

1.6 QUALITY ASSURANCE:

- A. Perform work in accordance with all governing codes, rules, and regulations including the following minimum codes (latest editions or as otherwise accepted by the Authorities Having Jurisdiction):
 - 1. National Electric Code (NEC)
 - 2. International Building Code (IBC)
 - 3. International Fire Code (IFC)
 - 4. International Mechanical Code (IMC)
 - 5. International Plumbing Code (IPC)
 - 6. American Disability Act (ADA)
 - 7. National Electrical Safety Code (NESC)
 - 8. Local Codes and Ordinances
- B. Comply with all standards where applicable for equipment and materials including the following minimum standards:
 - 1. Underwriter's Laboratories (UL)
 - 2. American Society for testing Materials (ASTM)
 - 3. Certified Ballast Manufacturers (CBM)
 - 4. Insulated Cable Engineers Association (ICEA)
 - 5. National Electrical Manufacturer's Institute (NEMA)
 - 6. American National Standards Institute (ANSI)
 - 7. Electrical Testing Laboratories (ETL)
 - 8. National Fire Protection Association (NFPA)
 - 9. Institute of Electrical and Electronics Engineers (IEEE)
 - 10. American Institute of Electrical Engineer's Electrical Power
 - 11. Systems and Grounding in Commercial Construction
 - 12. Illuminating Engineers Society (IES)
- C. Provide new electrical equipment conforming to all requirements as set forth in the above standards. Provide UL labeled equipment where such label is applicable.
- D. Comply with all state and local codes and ordinances. When conflicts occur among codes, standards, drawings, and/or specifications, the most stringent requirements shall govern.
- E. Obtain all permits, inspections, etc. required by authority having jurisdiction. Include all fees in bid. Provide a certificate of approval to the owner's representative from the inspection authority at completion of the work.
- F. Provide only first-class workmanship from competent workers, conforming to the best electrical construction practices.
- G. The contractor shall have a current state contracting license applicable to type of work to be performed under this contract.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1.7 SUBMITTALS:

- A. Shop Drawings: After the contract is awarded, but prior to manufacture or installation of any equipment, submit eight (8) complete sets of shop drawings. Partially complete sets of shop drawings are not acceptable. Submit all shop drawings in one complete submittal package. Prior to submitting shop drawings, review and certify that they are in compliance with the contract documents; Sign all approved shop drawings. Allow a minimum of two weeks for architect/engineer to review shop drawings. Refer to architectural general provision section for additional requirements.
- B. Provide equipment catalog "cut sheets", brochures and/or drawings which clearly describe the proposed equipment. Include plans, elevations, sections, isometrics, and detailed engineering and dimensional information as applicable including equipment room layouts. Electrical room layouts are required to show all electrical equipment locations for all projects that include electrical rooms. Do not submit catalog sheets which describe several different items in addition to those items to be used, unless all relevant information is clearly identified. Bind each information set in three ring binder or binders of sufficient size or sizes to enclose all information. Organize all information by section. Provide separate tabbed covers for each section of Divisions 16 indicating section number for each section requiring submittals.
- C. Include on front cover of binder or binders the name and location of the project, architect, electrical engineer, general contractor, electrical contractor, subcontractors, supplier/vendor, order number, volume, date, and any other applicable information. Certify that shop drawings are submitted in accordance with the contract documents with a written statement indicating compliance. Submittals will be reviewed and comments produced two times maximum. Additional reviews will be billed at current rates.

1.8 OPERATION AND MAINTENANCE MANUALS:

- A. Submit four (4) complete sets of operating instruction and maintenance manuals for all equipment and materials provided under Divisions 16 prior to the Substantial Completion Inspection.
- B. Provide manufacturer's recommended operating and maintenance instructions, cleaning and servicing requirements, serial and model number of each piece of equipment, complete list of replacement parts, performance curves and data, wiring diagrams, warranties, and vendor's name, address, and phone numbers. Do not submit information which describes several different items in addition to those items to be used, unless all relevant information is clearly identified. Assemble all data in completely indexed volume or volumes. Engrave the job title, and name, address, and phone numbers of the contractor on the front cover and on the spine. Incomplete O&M manuals will be returned to the contractor for corrections / additions.

1.9 RECORD DRAWINGS:

- A. Maintain on a daily basis a complete set of "Red-Lined Drawings", reflecting an accurate record of all work including addendums, revisions, and changes. Indicate precise dimensioned locations of all concealed work and equipment, including concealed or embedded conduit, junction boxes, etc. Record all "Red-Lined Drawing" information on a set of full sized prints of the contract drawings.
- B. Certify the "Red Lined Drawings" for correctness. Indicate on each drawing the name of the general and electrical contractors with signatures of each representative responsible for the work.
- C. The electrical engineering design firm will create record (as-built) drawings from the certified red-lined drawings; however, the general and electrical contractors retain the responsibility for the accuracy of the record drawings.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1.10 WARRANTY:

- A. Ensure that the electrical system installed under this contract is in proper working order and in compliance with drawings, specifications, and/or authorized changes and is free from electrical defects. Without additional charge, replace or repair, to satisfaction of the owner's representative, except from ordinary wear and tear, any part of the installation which may fail or be determined unacceptable within a period of one (1) year after final acceptance or as otherwise indicated in individual sections, but in no case less than one year. Warranty incandescent and fluorescent lamps only for a period of two months from the date of substantial completion.
- B. Provide complete warranty information for each item including beginning of warranty period, duration of warranty, names, addresses, and telephone numbers and procedures for filing a claim and obtaining warranty services. Written warranties and guarantees are to be submitted separately as:
 - 1. Originals bound in a binder clearly identified with the title, "WARRANTIES AND GUARANTEES," the project name, the project number, and the Contractor's business name.
 - 2. Electronic documents in *.pdf format.

PART 2 – PRODUCTS

2.1 GENERAL:

- A. All materials shall be new and shall bear the manufacturer's name, trade name, and the approved testing laboratory such as the UL label in every case where a standard has been established for that particular material. Used materials are acceptable only if specifically indicated on drawings.

2.2 SUBSTITUTION OF MATERIALS:

- A. Provide only specified products or products approved by addendum. Substitutions will be considered if two copies of the proposal is received at the architect's/engineer's office eight (8) working days prior to the bid day. Include in the proposal the specified and proposed catalog numbers of the equipment under consideration and a catalog cut sheet(s) with pictorial and descriptive information. Certify that the equipment proposed is equal to that specified, that it has the same electrical and physical characteristics, compatible dimensions, and meets the functional intent of the contract documents.
- B. It is the responsibility of the contractor to make all substituted equipment comply with the intent of the contract documents and bear all cost associated with conflicts arising from the use of substituted equipment.
- C. Provide samples if so required by the architect or engineer before or after bid day.

2.3 SPARE PARTS:

- A. Provide spare parts as specified in Divisions 16 sections. Deliver all spare parts to owner's representative prior to substantial completion.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

PART 3 – EXECUTION

3.1 GENERAL:

- A. Workmanship: Provide only first class workmanship from competent workers. Defective materials or workmanship will not be allowed on the project. Provide competent supervision for the work to be accomplished. Keep same foreman on the job, unless a change is authorized by the engineer.
- B. Coordination: Prior to construction, layout electrical work and coordinate work with other trades. Sequence, coordinate, and integrate installation of materials and equipment for efficient flow of the work. Coordinate the installation of required supporting devices and sleeves to be set in poured-in-place concrete and other structural components, as they are constructed. Install electrical equipment to facilitate maintenance and repair or replacement of equipment components. Coordinate the installation of electrical materials and equipment above ceilings with suspension system, mechanical equipment and systems, and structural components. Coordinate with all utilities including power, communication, and data installations.
- C. Provide cutting, drilling, channeling, etc. only as necessary for proper completion of the work. Do not cut structural members unless authorization is issued in writing by the architect/engineer.
- D. Repairs: Repair damage to building, grounds, or utilities as a result of work under this contract at no additional cost to the owner.
- E. Dimensioning: Electrical drawings indicate locations for electrical equipment only in their approximate location, unless specifically dimensioned. Do not scale electrical drawings for dimensional information. Refer to architectural drawings and shop drawings where applicable for locations of all electrical equipment. Field verify all dimension on the job site.
- F. Provide block-outs, sleeves, demolition work, etc., required for installation of work specified in this division.
- G. Standards: Provide electrical installation in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.
- H. All workmen doing work of any nature on State of Utah projects must at all times carry their electrician's license with them and show it upon request. The acceptable ratio of apprentice to journeyman electricians on the job is 1:1.

3.2 REQUESTS FOR INFORMATION:

- A. When it is clearly apparent that information is not adequately described in the construction documents or when a coordination problem exists, submit a request for information (RFI) through proper contractual channels. The electrical engineering design firm will provide a response through its contractual channel. Although verbal direction may be given to expedite changes, responses are not considered part of the contract documents until a change order has been issued and signed by the Owner or his designated representative. The Contractor shall bear all costs associated with proceeding on any change order that has not been approved by the Owner or his designated representative.
- B. It is not the electrical engineering design firm's responsibility to answer questions that could clearly be answered by a thorough review of the construction documents. Should an RFI be issued by the Contractor where information was available, the electrical engineering firm will bill the contractor at the following rates:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

| | | |
|----|----------------------------|----------------|
| 1. | Principal | \$135.00 / Hr. |
| 2. | Engineer | \$100.00 / Hr. |
| 3. | Designer | \$ 75.00 / Hr. |
| 4. | Construction Administrator | \$ 70.00 / Hr. |
| 5. | Drafting | \$ 60.00 / Hr. |
| 6. | Clerical | \$ 45.00 / Hr. |

- C. Any damages caused by construction delays due to frivolous RFI's, will be born solely by the Contractor.

3.3 SAFETY PRECAUTIONS:

- A. Provide all necessary guards or construction barriers and take all necessary precautions to insure the safety of life and property.

3.4 CLEAN:

- A. Clean up all equipment, conduit, fittings, wire, packing cartons, plastic, and other debris that is a direct result of the installation of the work of this division, both during the execution, and at the conclusion, of the project. Keep the site clean and safe during the progress of the work. Clean fixtures, interior and exterior of all equipment, and raceways prior to final acceptance. Vacuum interior of all electrical panels and equipment. Correct any damaged equipment. Touch-up or repaint if necessary.

3.5 TEMPORARY POWER:

- A. Make arrangements with the proper institution authority for all temporary electricity.
- B. Provide temporary power, complete with metering and wiring for lighting and power outlets for construction tools and equipment. Report the initial meter reading to the owner/institution, or otherwise as may be directed.
- C. Service shall be provided with a main disconnect and all 20 ampere receptacles protected by 20 amp GFI, single-pole breakers. No attempt is made herein to specify construction power requirements for equipment in detail. Provide all electrical equipment and wiring as required.
- D. As soon as permanent power and metering is available, the temporary power supply shall be disconnected and removed from the project site.
- E. All temporary wiring shall meet the requirements of NEC Article 305 and the State Industrial Commission.

3.6 POWER OUTAGES:

- A. All power outages required for execution of this work shall occur during non-standard working hours and at the convenience of the owner. Any electrical service interruption will be coordinated at least 7 days in advance of the power shut-off. Include all costs for overtime work in bid. Coordinate all outages and proceed only after receiving authorization from the owner's representative. Keep all outages to an absolute minimum.

3.7 STORAGE AND PROTECTION OF MATERIALS:

- A. Provide storage space for storage of materials and apparatus and assume complete responsibility for all losses due to any cause whatsoever. Lost or damaged materials will be replaced at no additional cost to owner. Do not store materials and apparatus in any public thoroughfare or in any area on the site where

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

such storage would constitute a hazard to persons in the vicinity. Protect completed work, work underway, and apparatus against loss or damage.

3.8 EXCAVATING FOR ELECTRICAL WORK:

- A. Verification: Prior to excavating, locate and protect existing utilities and other underground work in a manner which will ensure that no damage or service interruption will result from excavating and backfilling. Observe all State and Local codes prior to excavating. Do not disturb walls, footings, and other structural members in any way.
- B. Protection: Provide barricades, warning signs, and illumination to protect persons from injury at excavations. Provide temporary coverings and heat as necessary to protect bottoms of excavations from freezing and frost action. Do not install electrical work on frozen excavation bases or subbases.
- C. Coordination: Do not excavate for electrical work until the work is ready to proceed without delay.
- D. Excavated Materials: Temporarily store excavated materials near excavation in manner which will not interfere with or damage excavation or other work. Dispose of and remove excavated materials which are either in excess of quantity needed for backfilling or do not comply with the requirements for backfill material.
- E. Burial Depths: Burial depths must comply with NEC Section 300-5 (or State of Utah requirements, whichever is more stringent), unless noted otherwise on drawings.
- F. Excavation Permits: Obtain all shut-down and excavation permits as may be required for proper completion of the work.

3.9 BACKFILL MATERIALS:

- A. For buried conduits or cables (other than below slab-on-grade, or concrete-encased), provide 2" thickness of well-graded sand on all sides of conduits or cables.
- B. For trench backfill to within 6" of final grade, provide soil material suitable for compacting to required densities.
- C. For top 6" of excavation, provide top soil.
- D. Backfill excavations in 8" high courses of backfill material, uniformly compacted to the following densities (percent of maximum density, ASTM D 1557), using power-driven hand-operated compaction equipment:
 - 1. Lawn/Landscaped Areas: 85 percent for cohesive soils, 95 percent for cohesionless soils.
 - 2. Paved Areas, other than roadways: 90 percent for cohesive soils, 95 percent for cohesionless soils.
- E. Where subsidence is observable at electrical work excavations during project warranty period, remove surface, add backfill material, compact, and replace surface treatment. Restore surface to original condition.

3.10 ROOF PENETRATIONS:

- A. Where raceways and/or cables penetrate roofing, provide 26 gauge galvanized iron roof jack, sized to fit tightly to raceway and/or cable for weather-tight seal, and with flange extending a minimum of 9" under roofing on all sides. Seal opening between raceway and roof jack with approved sealant. Coordinate all

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

work with division 7.

3.11 FIRE PENETRATION SEALS:

- A. Seal all raceway and/or cable penetrations through fire-rated floors, wall, and ceilings to prevent the spread of smoke, fire, toxic gas or water through the penetration either before, during or after fire. Provide penetration sealants and fittings of ratings to match the rating of the penetrated materials so that the original fire rating of the floor or wall is maintained as required by Article 300-21 of the NEC.
- B. Sealant Systems: Provide sealants, wall wraps, partitions, caps, and other accessories complying with UL 1479 (ASTM E-814) from the following where applicable:
 - 1. 3M Fire Barrier Sealing Penetration System
 - 2. Chase Foam Fire Stop System
 - 3. Thomas and Betts Flame Safe Fire Stop System
 - 4. Nelson Fire Stop Products
- C. Fittings: Where applicable, provide OZ Type CFSF/I and CAFSF/I fire seal fittings for conduit and cable penetrations through concrete and masonry wall, floor, slabs, and similar structures.
- D. Install sealants and fittings in accordance with all manufacturer's written instructions.

3.12 LABELING:

- A. Engraved black plastic laminated, with white-core labels, 1/16" thick, shall be permanently attached on both the interior and exterior the following electrical equipment:
 - 1. Branch panels
 - 2. Switchgear
 - 3. Disconnect switches
 - 4. Motor starter and controls junction boxes (power and auxiliary)
 - 5. Push buttons
 - 6. Thermal switches
 - 7. Time switches
 - 8. Motor control centers
 - 9. Transformer
 - 10. Similar equipment.
 - 11. Lighting contactors and associated switches
 - 12. Junction boxes larger than 4x4x1/2.
- B. The labels shall have 1/4" high, engraved letters, such as EF-1, AC-1, Panel A, etc.
- C. Label for motor starters and/or thermal overload switches shall include heater size and F.L.A.
- D. Labels shall be red where serving emergency loads.

3.13 CONCRETE BASES:

- A. Housekeeping Pads: Unless otherwise noted, provide 4" high reinforced concrete bases for all floor-mounted or floor-standing electrical equipment, including but not necessarily limited to the following:
 - 1. Transformers
 - 2. Switchgear
 - 3. Motor control centers

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

4. Generators
 5. Battery racks
 6. Similar Equipment
- B. Extend bases 6" beyond equipment or mounting rails on all sides or as shown on the drawings. Not withstanding this requirement, coordinate with equipment manufacturer, shop drawings, and height of base to ensure compliance with NEC 380-82.
- C. Concrete bases: Refer to Section 16551 – exterior area lighting.
- D. Transformer Pads: Provide and locate properly sized concrete pads for power company furnished pad mounted transformers in accordance with power company clearance requirements.

3.14 TESTS:

- A. Notify engineer prior to all testing specified herein at least three business days prior to testing. Engineer shall observe all tests to insure the proper operation of the electrical system.

3.15 PROJECT FINALIZATION AND START-UP:

- A. Upon completion of the work, have each factory representative and/or subcontractor assist in start-up and testing of their respective systems.
- B. Have each representative give personal instructions on operating and maintenance of their equipment to the owner's maintenance and/or operation personnel.
- C. Have representatives certify each system with a written statement indicating that they have performed start-up and final check out of their respective systems.

3.16 FINAL REVIEW:

- A. Have the project foreman accompany their reviewing parties and remove coverplates, panel covers, access panels, etc. as requested, to allow review of the entire electrical system.

END OF SECTION 16001

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16070 - ELECTRICAL CONNECTIONS FOR EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to electrical connections.

1.2 DESCRIPTION OF WORK:

- A. Extent of electrical connections for equipment include all final electrical connections for all equipment having electrical requirements including, but not necessarily limited to the following:
 - 1. Equipment specified under all divisions of the contract. Refer to other divisions for specific electrical requirements.
 - 2. Owner-furnished equipment
 - 3. Kitchen Equipment
 - 4. Etc.

1.3 QUALITY ASSURANCE:

- A. STANDARDS: Refer to Section 16001 - Electrical General Provisions as applicable.
- B. SHOP DRAWINGS: Not required.

PART 2 - PRODUCTS

2.1 GENERAL:

- A. Provide all materials for electrical connections including, but not necessarily limited to the following:
 - 1. Raceways
 - 2. Fittings
 - 3. Conductors
 - 4. Cords
 - 5. Cord caps
 - 6. Wiring devices
 - 7. Pressure connectors
 - 8. Lugs (CU-AL)
 - 9. Electrical insulating tape
 - 10. Heat-shrinkable tubing
 - 11. Cable ties
 - 12. Wire nuts
 - 13. Other items and accessories as required.
- B. Crimp on or slip-on type splicing materials designed to be used without wire stripping are not acceptable.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- C. Power Distribution Blocks: Provide Square D Type LB or Equivalent.
- D. Refer to other Division 16 sections for specification of electrical materials as applicable.

PART 3 - EXECUTION

3.1 GENERAL:

- A. Make electrical connections in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA Standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 CONNECTIONS:

A. Permanently Installed Fixed Equipment:

- 1. Install conductors in flexible conduit from junction box to equipment control panel or connection point.
- 2. Where such installations are subject to moisture, install in liquid-tight flexible conduit.

B. Movable equipment:

- 1. Provide wiring devices, cord caps, and multi-conductor cables as required.

C. Other methods as required by the NEC and/or as required by special equipment or field conditions.

- D. Power Distribution Blocks: Unless noted otherwise on drawings, provide power distribution blocks only for tapping of feeders and branch circuits. Locate in junction box or gutter in NEMA ratings to suit application.

3.3 MANUFACTURER'S INSTRUCTIONS:

- A. Obtain manufacturer's instruction and wiring diagram regarding electrical connections of each piece of equipment and provide connections in accordance therewith.

3.4 VERIFICATION OF LOAD CHARACTERISTICS:

- A. Verify electrical load characteristics of all equipment prior to rough-in. Review respective shop drawings of all other Divisions and Owner's equipment manuals. Report any variances from electrical characteristics noted in the contract documents to the Architect/Engineer prior to rough-in.
- B. Value of rough-in work, electrical equipment, etc. installed and/or purchased by the contractor not meeting equipment requirements shall be credited back to the owner.

END OF SECTION 16070

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16072 - ELECTRICAL SUPPORTS AND SEISMIC RESTRAINTS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY:

- A. This Section includes the following:
 - 1. Hangers and supports for electrical equipment and systems.
 - 2. Seismic restraints for electrical equipment and systems.
 - 3. Construction requirements for concrete bases.

1.3 DEFINITIONS:

- A. IBC: International Building Code.
- B. Seismic Restraint: A structural support element such as a metal framing member, a cable, an anchor bolt or stud, a fastening device, or an assembly of these items used to transmit seismic forces from an item of equipment or system to building structure and to limit movement of item during a seismic event.

1.4 SUBMITTALS:

- A. Product Data: Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of electrical support and seismic-restraint component used.
 - 1. Tabulate types and sizes of seismic restraints, complete with report numbers and rated strength in tension and shear as evaluated by an agency acceptable to authorities having jurisdiction.
 - 2. Annotate to indicate application of each product submitted and compliance with requirements.
- B. Shop Drawings: Indicate materials and dimensions and identify hardware, including attachment and anchorage devices, signed and sealed by a qualified professional engineer. Include the following:
 - 1. Fabricated Supports: Representations of field-fabricated supports not detailed on Drawings.
 - 2. Seismic Restraints: Detail anchorage and bracing not defined by details or charts on Drawings. Include the following:
 - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads.
 - b. Details: Detail fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events.
 - c. Preapproval and Evaluation Documentation: By an agency acceptable to authorities having jurisdiction, showing maximum ratings of restraint items and the basis for approval (tests or calculations).
- C. Coordination Drawings: Show coordination of seismic bracing for electrical components with other systems and equipment in the vicinity, including other supports and seismic restraints.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- D. Welding certificates.
 - E. Qualification Data: For professional engineer and testing agency.
 - F. Field quality-control test reports.
- 1.5 QUALITY ASSURANCE:
- A. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
 - B. Testing of Seismic Anchorage Devices: Comply with testing requirements in Part 3.
 - C. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."

PART 2 - PRODUCTS

- 2.1 MANUFACTURERS:
- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, manufacturers specified.
- 2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS:
- A. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed under this Project, with a minimum structural safety factor of five times the applied force.
 - B. Steel Slotted Support Systems: Comply with MFMA-3, factory-fabricated components for field assembly.
 - 1. Available Manufacturers:
 - a. Cooper B-Line; a division of Cooper Industries.
 - b. ERICO International Corporation.
 - c. Allied Support Systems; Power-Strut Unit.
 - d. GS Metals Corp.
 - e. Michigan Hanger Co., Inc.; O-Strut Div.
 - f. National Pipe Hanger Corp.
 - g. Thomas & Betts Corporation.
 - h. Unistrut; Tyco International, Ltd.
 - i. Wesanco, Inc.
 - 2. Finishes:
 - a. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-3.
 - 3. Channel Dimensions: Selected for structural loading and applicable seismic forces.
 - C. Raceway and Cable Supports: As described in NECA 1.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- D. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- E. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for non-armored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be malleable iron.
- F. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- G. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
 - 1. Verify suitability of fasteners in subparagraph below for use in lightweight concrete or concrete slabs less than 4 inches (100 mm) thick.
 - 2. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - a. Available Manufacturers:
 - 1) Hilti, Inc.
 - 2) ITW Construction Products.
 - 3) MKT Fastening, LLC.
 - 4) Simpson Strong-Tie Co. Inc.
 - 3. In the following subparagraph, use stainless steel anchors in corrosive environments.
 - 4. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
 - a. Available Manufacturers:
 - 1) Cooper B-Line; a division of Cooper Industries.
 - 2) Empire Tool and Manufacturing Co., Inc
 - 3) Hilti, Inc.
 - 4) ITW Construction Products.
 - 5) MKT Fastening, LLC.
 - 6) Powers Fasteners.
 - 5. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
 - 6. Through Bolts: Structural type, hex head, high strength. Comply with ASTM A 325.
 - 7. Toggle Bolts: All-steel springhead type.
 - 8. Hanger Rods: Threaded steel.

2.3 SEISMIC-RESTRAINT COMPONENTS:

- A. Rated Strength, Features, and Application Requirements for Restraint Components: As defined in reports by an agency acceptable to authorities having jurisdiction.
 - 1. Structural Safety Factor: Strength in tension, shear, and pullout force of components used shall be at least five times the maximum seismic forces to which they will be subjected.
- B. Angle and Channel-Type Brace Assemblies: Steel angles or steel slotted-support-system components; with accessories for attachment to braced component at one end and to building structure at the other end.
- C. Cable Restraints: ASTM A 603, zinc-coated, steel wire rope attached to steel or stainless-steel thimbles,

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

brackets, swivels, and bolts designed for restraining cable service.

1. Available Manufacturers:
 - a. Amber/Booth Company, Inc.
 - b. Loos & Co., Inc.
 - c. Mason Industries, Inc.
2. Seismic Mountings, Anchors, and Attachments: Devices as specified in Part 2 "Support, Anchorage, and Attachment Components" Article, selected to resist seismic forces.
3. Hanger Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections to hanger rod, of design recognized by an agency acceptable to authorities having jurisdiction.
4. Bushings for Floor-Mounted Equipment Anchors: Neoprene units designed for seismically rated rigid equipment mountings, and matched to type and size of anchor bolts and studs used.
5. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for seismically rated rigid equipment mountings, and matched to type and size of attachment devices used.

2.4 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES:

- A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.
- B. Materials: Comply with requirements in Division 5 Section "Metal Fabrications" for steel shapes and plates.

PART 3 - EXECUTION

3.1 APPLICATION

- A. Comply with NECA 1 for application of hangers and supports for electrical equipment and systems, except if requirements in this Section are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for raceways as within 12 inches of coupling, fitting, and box, at each 90 degrees bend, minimum of two supports per ten foot run. Minimum rod size shall be 1/4 inch (6 mm) in diameter.
- C. Multiple Raceways: Install trapeze-type supports fabricated with steel slotted or other support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
 1. Secure raceways and cables to these supports with single-bolt conduit clamps, or as otherwise required by an agency acceptable to authorities having jurisdiction.

3.2 SUPPORT AND SEISMIC-RESTRAINT INSTALLATION:

- A. Comply with NECA 1 for installation requirements, except as specified in this Article.
- B. Raceway Support Methods: In addition to methods described in NECA 1, raceways may be supported by openings through structure members, as permitted in NFPA 70.
- C. Install seismic-restraint components using methods approved by the evaluation service providing required submittals for component.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- D. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static and seismic loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb (90 kg).
 - E. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
 - 1. To Wood: Fasten with lag screws or through bolts.
 - 2. To New Concrete: Bolt to concrete inserts.
 - 3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 4. To Existing Concrete: Expansion anchor fasteners.
 - 5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches (100 mm) thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches (100 mm) thick.
 - 6. To Steel: Beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69 Spring-tension clamps.
 - 7. To Light Steel: Sheet metal screws.
 - 8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that meet seismic-restraint strength and anchorage requirements.
 - F. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.
 - G. Do not drill or core cut holes for anchors or use powder-activated fasteners in post-tension slabs, joists, and beams.
- 3.3 INSTALLATION OF FABRICATED METAL SUPPORTS:
- A. Comply with installation requirements in Division 5 Section "Metal Fabrications" for site-fabricated metal supports.
 - B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
 - C. Field Welding: Comply with AWS D1.1/D1.1M.
- 3.4 CONCRETE BASES:
- A. Concrete Bases: Anchor equipment to concrete base according to equipment manufacturer's written instructions and seismic criteria at Project.
 - B. Construct concrete bases of dimensions indicated but not less than 4 inches (100 mm) larger in both directions than supported unit, and so expansion anchors will be a minimum of 10 bolt diameters from edge of the base.
 - 1. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch (450-mm) centers around full perimeter of the base.
 - 2. Install epoxy-coated anchor bolts for supported equipment that extend through concrete base, and

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- anchor into structural concrete floor.
- 3. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
- 4. Install anchor bolts to elevations required for proper attachment to supported equipment.
- 5. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
- 6. Use 3000-psi (20.7-MPa), 28-day compressive-strength concrete. Concrete materials, reinforcement, and placement requirements are specified in Division 3 Section "Cast-in-Place Concrete."

3.5 INSTALLATION OF SEISMIC-RESTRAINT COMPONENTS:

- A. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- B. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- C. Restraint Cables: Provide slack within maximums recommended by manufacturer.
- D. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, upper truss chords of bar joists, or at concrete members.

3.6 FIELD QUALITY CONTROL:

- A. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Testing: Test pullout resistance of seismic anchorage devices.
 - 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
 - 2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
 - 3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
 - 4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
 - 5. Test to 90 percent of rated proof load of device.
 - 6. If a device fails test, modify all installations of same type and retest until satisfactory results are achieved.
- C. Record test results.

END OF SECTION 16072

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16080 - ELECTRICAL DEMOLITION

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to electrical demolition.

1.2 DESCRIPTION OF WORK:

- A. Extent of electrical demolition work is indicated by drawings.
- B. Electrical demolition items are shown to give a basic description of the extent of demolition work, but may not be inclusive.
- C. Do not assume that the electrical drawings reflect as-built conditions. Visit and observe the project prior to submitting bid and determine extent of electrical demolition work.

1.3 QUALITY ASSURANCE:

- A. Standards: Refer to Section 16001 - Electrical General Provisions as applicable.

PART 2 – PRODUCTS - Not used.

PART 3 – EXECUTION

3.1 GENERAL:

- A. Demolition work shall be laid out in advance to eliminate unnecessary cutting, drilling, channeling, etc. Where such cutting, drilling, or channeling becomes necessary, perform with care, use skilled mechanics of the trades involved. Cutting work of other contractors shall be done only with the consent of that contractor. Cutting of structural members is not permitted. Repair damage to building and equipment as a result of electrical demolition work under this contract at no additional cost to owner.
- B. Obtain permission from the architect before penetrating any ceiling, floor, and wall surfaces.

3.2 METHODS:

- A. Disconnect and remove any/all fixtures, devices, equipment, etc. required for proper completion of the work whether shown or not.
- B. Relocate, rewire, and/or reconnect any/all fixtures, devices, equipment, etc. that for any reason obstructs construction.
- C. Maintain circuit integrity and continuity of all existing circuits/feeders, and systems that interfere with or

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

are interrupted by remodel work, unless those circuits/feeders are to be abandoned completely. Maintain all circuits and systems in operation during construction. Provide temporary panels, temporary wiring and conduits, etc. as required.

- D . Leave all existing fixtures, devices, equipment, etc. In portions of the building not being remodeled, in working condition.
- E . Remove and dispose of all raceways, conductors, boxes, devices, equipment, etc., that are not to be reused. Terminate at accessible junction box by providing proper knockout closure, tape conductors, and label as "spare" with circuit no., Zone no., or other characteristic identifying source.
- F . Existing raceways may be reused, if in place, where in compliance with the contract documents and the National Electrical Code. Upgrade and/or provide new conduit supports where necessary for all raceways being reused. Insure integrity of existing raceways before re-use.
- G . Return to owner all light fixtures which are to be removed. Dispose of all light fixtures if so directed by owner in accordance with local environmental laws and policies. Those fixtures indicated for re-use shall be thoroughly cleaned, repaired as required, re-lamped, and installed as indicated. When storing fixtures for reuse, store in area and/or provide protective covering that will keep construction dust and materials off fixtures.
- H . Completely remove all telephone or data cables which are to be removed back to source or as directed by owner.
- I . Disconnect and remove all sound system equipment including speakers, amplifiers, etc. And return to owner. Completely remove and dispose of all associated conduit and wire.

3.3 PATCHING AND REPAIR:

- A . Finished Surfaces: The electrical contractor is responsible for patching and repair of all existing interior surfaces pertaining to the installation of work under this Division, unless specifically noted elsewhere in the contract documents. Where patching and repair is necessary, surfaces shall be finished (painted, etc.) to match the adjacent materials, finished, and colors. Requirements of other Divisions such as Division 9 - finishes shall apply.
- B . Hard Surfaces: Whenever excavation or trenching is required for the installation of electrical work, it shall be the responsibility of the electrical contractor to make repairs and/or replacements of hard finish surfaces such as concrete, asphalt, etc. Requirements of other Divisions such as Division 2 - Existing Conditions shall apply.

3.4 CONCEALING:

- A . All raceways shall be concealed within the ceilings, walls, and floors, except in locations where exposed raceways are specifically permitted, such as equipment rooms and unfinished storage areas.
- B . Surface-mounted raceways or systems shall be permitted only where approved by Architect/Engineer.

END OF SECTION 16080

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16110 - CONDUIT RACEWAYS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 sections making reference to conduit raceways.

1.2 DESCRIPTION OF WORK:

- A. Extent of raceways is indicated by drawings and schedules.
- B. Types of raceways in this section include the followings:
 - 1. Rigid Metal Conduit
 - 2. PVC Externally Coated Rigid Steel Conduit
 - 3. Intermediate Metal Conduit
 - 4. Electrical Metallic Tubing
 - 5. Flexible Metal Conduit
 - 6. Liquid-tight Flexible Metal Conduit
 - 7. Rigid Non-metallic Conduit

1.3 QUALITY ASSURANCE:

- A. Standards: Refer to Section 16001 - Electrical General Provisions as applicable. Provide conduit raceway installation in accordance with recommendations of the American Iron and Steel Institute "Design Manual on Steel Electrical Raceways", latest edition.
- B. Manufacturers: Firms regularly engaged in the manufacture of raceway of types and sizes required, whose products have been in satisfactory service for not less than three (3) years.
- C. Shop Drawings: Not required.

PART 2 – PRODUCTS

2.1 CONDUITS:

- A. Rigid Metal Conduit (RMC): Provide zinc-coated, hot-dipped galvanized, rigid metallic conduit in accordance with Federal Specification WW-C-0581 and ANSI C80.1.
- B. PVC Externally Coated Rigid Metal Conduit: Provide hot-dipped galvanized, rigid metallic conduit externally coated with Polyvinyl Chloride (PVC) in accordance with ANSI C80.1 and NEMA Std. Pub. No. RN 1.
- C. Intermediate Metal Conduit (IMC): Provide hot-dipped galvanized, intermediate metal conduit in accordance with Federal Specification WW-C-581.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- D. Electric Metallic Tubing (EMT): Provide electric metal tubing in accordance with Federal Specification WW-C-563 and ANSI C80.3.
- E. Flexible Metal Conduit: Provide zinc-coated, flexible metal conduit in accordance with Federal Specification WW-C-566.
- F. Liquid-Tight Flexible Metal Conduit: Provide liquid-tight, flexible metal conduit, constructed of single strip, flexible continuous, interlocked, and double-wrapped steel, galvanized inside and outside, coated with liquid-tight jacket of flexible Polyvinyl Chloride (PVC).
- G. Rigid Non-Metallic Conduit: Provide rigid non-metallic conduit (PVC) in accordance with ANSI/NEMA TC 2, Type 1 for concrete encasement, Type 2 for direct burial.

2.2 FITTINGS:

- A. Rigid Metal Conduit, Intermediate Metal Conduit, and PVC Externally Coated Rigid Metal Conduit: Provide fully-threaded, malleable steel fittings, rain-tight and concrete-tight as applicable. Provide double locknuts and metal bushings at all conduit terminations. Install OZ Type B bushings on conduits 1-1/4" and larger.
- B. Electric Metallic Tubing: Provide insulated throat, non-indenter, set screw, malleable steel fittings. Screws must have a full set. Provide concrete-tight compression-type fittings in suspended slabs. All EMT fittings shall be fabricated from steel. Die-cast fittings or fittings made from pot metal shall not be allowed. Indenter type fittings are not acceptable. Install OZ Type B bushings on conduits 1" and larger.
- C. Flexible Metal Conduit: Provide flexible metal conduit fittings in accordance with Federal Specification W-F-406, Type 1, Class 1, and Style A. Commercial "greenfield" not less than 1/2" diameter or as otherwise specified on drawings is acceptable.
- D. Liquid-Tight Flexible Metal Conduit: Provide liquid-tight flexible metal conduit fittings in accordance with Federal Specification W-F-406, Type 1, Class 3, Style G.
- E. Non-Metallic Conduit: Provide non-metallic conduit fittings (PVC) in accordance with ANSI/NEMA TC 3 to match conduit types and materials.
- F. Expansion Fittings: OZ Type AX, or equivalent to suit application.
- G. Sealing Bushings: Provide OZ Type FSK, WSK, or CSMI as required by application. Provide OZ Type CSB internal sealing bushings.
- H. Cable Supports: Provide OZ cable supports for vertical risers, type as required by application.

2.3 SIZES:

- A. Provide conduits in sizes as indicated in contract documents or as otherwise specified herein, but not less than 3/4".

PART 3 – EXECUTION

3.1 GENERAL:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Install raceway and accessories in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA Standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 LOCATIONS:

- A. Rigid Metal Conduit and Fittings: Use for conduit bends greater than 22 degrees where buried below grade or slab on grade. Install RMC where raceway passes vertically through slab-on-grade. Where raceways penetrate building, manholes, or vault walls and floors below grade, provide RMC for a minimum distance of 10' on the exterior side of the floor or wall. Use RMC for exposed runs where conduit is subject to moisture, weather, or mechanical injury. Use in hazardous locations in accordance with all NEC requirements.
- B. Intermediate Metal Conduit and Fittings: Use for exposed runs where conduit is subject to moisture, weather, or mechanical injury. Use in hazardous locations in accordance with all NEC requirements.
- C. Electric Metal Tubing and Fittings: Use for above-grade feeders, branch circuits, and signal and control circuit, unless specifically noted otherwise on drawings. Install in suspended slabs subject to local code requirements and fire rating considerations.
- D. Flexible Metal Conduit and Fittings: Use as whips for lighting fixtures, fixed equipment where not exposed to weather or moisture, other devices where required by NEC, and as requested by the Engineer. Maximum length not to exceed 6', unless specifically approved by the Electrical Engineer.
- E. Liquid-Tight Flexible Metal Conduit and Fittings: Use for connection to motor terminal boxes, fixed equipment where subject to moisture or weather, and other equipment subject to movement or vibration. Maximum length not to exceed 6', unless specified otherwise.
- F. Rigid Non-Metallic Conduit and Fittings: Use for below-grade service entrances, feeders, branch circuits, and signal and control circuit, unless specifically noted otherwise on drawings. Do not use above grade.

3.3 METHODS:

- A. Maintain a minimum of 12" clearance between steam or hot water lines or other hot surfaces. Where such clearance is impractical, insulate conduit with approved materials.
- B. Install conduits parallel with or at right angles to lines of the structure. Route conduits symmetrically where possible.
- C. Field bends and offsets shall be made without flattening, kinking, rippling or destroying the smooth internal bore or surface of the conduit and to not less than NEC minimum radius. Conduit that shows signs of rippling or kinking shall not be installed. Conduits installed with wrinkles or kinks or otherwise in an unworkmanlike manner shall be replaced at no additional cost to owner.
- D. Precaution shall be exercised to prevent accumulation of water, dirt or concrete in the conduits during the execution of the project. Conduits in which water or foreign matter has been permitted to accumulate shall be thoroughly cleaned or the conduits runs replaced where such accumulation cannot be removed by methods approved the engineer.
- E. Any conduit which pierces airtight spaces or plenums shall be sealed to prevent air leakage with mastic acceptable to the Architect.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

3.4 CONCEALING:

- A. All raceways shall be concealed within the ceilings, walls, and floors, except in locations where exposed raceways are specifically permitted, such as equipment rooms and unfinished storage areas. In equipment rooms, if lighting raceways are run exposed, installation shall not be done until piping and duct work layout has been determined in order that lighting boxes may be located so as to avoid being covered by overhead ducts and piping. If lighting raceways in equipment rooms are concealed in the structural ceiling slab, after mechanical work is complete, exposed conduit extensions shall be run to locate lighting fixtures where they are not obscured by work of other trades.

3.5 BURIED CONDUITS:

- A. Comply with all burial depths as defined in NEC Section 300-5. Bury all conduits at least 24" below grade, unless specifically indicated otherwise on drawings. Provide magnetic 6" wide "Yellow Warning" ribbon 12" directly above conduit and 6" below finished grade measured from the top of the conduit or duct bank. Where multiple small lines are buried in a common trench and do not exceed an overall width of 16", install a single marker.
- B. Slope all conduits toward manholes or pull boxes for proper drainage. Use weep holes. Gravel drainage pockets are not permitted.
- C. Coat all metal conduits with an approved asphaltic compound or wrap with two layers of PVC tape.
- D. Under Concrete Slab on Grade: Horizontal conduit must be installed a minimum of 2" below the bottom of the concrete slab. Conduits should not be installed in concrete slabs.
- E. Concrete Encasement: Where concrete-encasement is indicated on drawings, provide ductbank construction using red 3000 psi at 28 day strength concrete. Provide minimum 4" cover on all sides of exterior conduits. Provide conduit spacers where applicable. Coat all metal conduits with an approved asphaltic compound or wrap with two layers of PVC tape.
- F. Where conduits are extended for future use, cap and clearly mark.

3.6 ELECTRICAL CONTINUITY:

- A. Provide electrically continuous conduit systems throughout.

3.7 FIELD CUTS AND THREADS:

- A. Cut all conduits square. Remove all sharp or rough edges and ream all burrs, inside and outside. Provide clean sharp threads on RMC and IMC.
- B. Engage at least five full threads on all RMC and IMC fittings. Before couplings or fittings are attached, apply one coat of red lead or zinc chromate to male threads of RMC or IMC. Apply coat of red lead, zinc chromate or special compound recommended by manufacture to conduit where conduit protective coating is damaged.

3.8 CONDUIT ENDS:

- A. Cap all spare conduits. Cap or plug conduit ends during construction to prevent entrance of foreign material.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

3.9 SPARE CONDUITS:

- A. Provide five (5) 3/4" empty conduits from panel stubbed into accessible ceiling space and five (5) 3/4" conduits into accessible floor space. When floor is not accessible, provide six (6) 3/4" empty conduits from panel stubbed into accessible ceiling space. Cap and label all conduits.
- B. Install a 200 lb. polypropylene pull cord in each empty conduit run.

3.10 HAZARDOUS LOCATIONS:

- A. Install RMC and IMC in all hazardous locations as defined by the NEC. Provide suitable fittings, seal-offs, boxes, etc. to comply with all NEC requirements and/or as shown on the drawings. Provide inspection fittings with hazardous location rated drains to prevent water from accumulating in conduit runs.

3.11 CLEANING:

- A. Pull mandril and swab through all conduits before installing conductors.

END OF SECTION 16110

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16120 - CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to conductors and cables.

1.2 DESCRIPTION OF WORK:

- A. This section includes building wires and cables and associated connectors, splices, and terminations for wiring systems rated 600 V and less.
- B. Types of conductors and cables in this section include the following:
 - 1. Copper Conductors.
- C. Applications for conductors and cables required for project include:
 - 1. Feeders.
 - 2. Branch Circuits.

1.3 SUBMITTALS:

- A. Product Data: For each type of conductor and/or cable indicated.
- B. Field Quality-Control Test Reports: From Contractor. Refer to Section 16001 – General Electrical Provisions.

1.4 QUALITY ASSURANCE:

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 GENERAL:

- A. Manufacturers: In other Part 2 articles where subparagraph titles below introduce lists, provide products by the manufacturer specified, subject to compliance with requirements.
- B. Ambient Conditions: Conductors used for branch circuits in areas where the ambient conditions exceed 30 degree C. shall be provided with insulation approved for that temperature.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- C. Wire Sizes: As indicated on electrical drawings or as specified herein, but in no case less than No. 12 AWG.

2.2 COPPER CONDUCTORS:

A. Manufacturers:

1. American Insulated Wire Corporation; a Leviton Company.
2. General Cable Corporation.
3. Senator Wire & Cable Company.
4. Southwire Company.

- B. Refer to Part 3 "Conductor and Cable Applications" Article for application requirements.

C. References and Ratings:

1. ICEA S-95-658 / NEMA WC70.
2. ASTM.
3. UL Standard 83.
4. UL Standard 1063 (MTW).
5. Federal Specification J-C-30B.
6. NEC.

- D. Conductor Material: Copper.

- E. Stranding: Solid conductor for No. 12 AWG, stranded for No. 10 AWG and larger.

- F. Conductor Insulation Types: Thermoplastic-insulated, Type THHN / THWN-2.

2.3 CONNECTORS AND SPLICES:

A. Manufacturers:

1. AMP Incorporated/Tyco International.
2. Hubbell/Anderson.
3. O-Z/Gedney; EGS Electrical Group LLC.
4. 3M Company; Electrical Products Division.

- B. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

- C. Splices for wire sizes #10 and smaller shall be screw-on type similar to scotch or ideal wing nut connectors. Crimp-on splices designed to be used without wire stripping are not acceptable.

PART 3 – EXECUTION

3.1 GENERAL:

- A. Install conductors, cables, and accessories as indicated, in compliance with manufacturer's written instruction, applicable requirements of NEC, NECA's "Standards of Installation", and in accordance with recognized industry practices to ensure that products fulfill requirements.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

3.2 CONDUCTOR AND CABLE APPLICATIONS:

A. Branch Circuits:

1. Exposed, including in crawlspaces: Copper conductors in raceway.
2. Concealed in ceilings, walls, and partitions: Copper conductors in raceways.
3. Concealed in concrete and below slabs-on-grade: Copper conductors in raceway.

B. Class 1 Control Circuits: Copper conductors in raceway.

3.3 INSTALLATION:

A. Conceal cables in finished walls, ceilings, and floors, unless otherwise indicated.

B. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.

C. Use pulling means; including fish tape, cable, rope, and basket-weave wire/cable grips that will not damage cables or raceway.

D. When raceway is not required, install concealed cables parallel and perpendicular to surfaces of structural members, and follow surface contours where possible.

E. Support cables according to other applicable specification sections.

F. Seal around cables penetrating fire-rated elements to comply with applicable fire stop specification sections.

G. Color Coding: Color code secondary service, feeder, and branch circuit conductors. Colors shall remain consistent throughout the project and shall match existing coding system where applicable.

1. Conductor sizes No. 6 AWG and smaller: Colored insulation.
2. Conductors sizes No. 4 AWG and larger: 2 inch (51 mm) band of Colored adhesive marking tape applied at all terminations, junction boxes, and pull boxes.
3. Branch circuit switched-legs and travelers: Colored insulation (in colors other than those indicated below).
4. Color-code 120/208V system conductors:
 - a) Phase A: Black.
 - b) Phase B: Red.
 - c) Phase C: Blue.
 - d) Neutral: White.
 - e) Ground: Green.
 - f) Isolated Ground: Green with yellow tracer.
5. Color-code 120/240V system conductors:
 - a) Phase A: Black.
 - b) Phase B: Red.
 - c) Neutral: White.
 - d) Ground: Green.
 - e) Isolated Ground: Green with yellow tracer.

3.4 HOMERUN CIRCUITS:

A. Homerun circuits may be combined in common conduits at the option of the contractor in compliance

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

with the following:

1. Three-Phase Installations: Not more than three single-phase circuits with common neutral in one conduit, unless specifically noted otherwise, if each circuit is from a different phase (a, b, or c).
2. Single-Phase Installations: Not more than two single-phase circuits with common neutral in one conduit, unless specifically noted otherwise, if each circuit is from a different phase (a or b).

3.5 NEUTRAL CONDUCTORS:

- A. LIGHTING CIRCUITS: Where multiple circuits serving lighting are run in a single raceway (see paragraph above for allowable number of circuits per conduit), a common neutral shall be allowed. When any one circuit is serving fluorescent lighting loads, provide an oversized neutral conductor. Size the neutral conductor one size (AWG) larger than the largest phase conductor.
- B. OUTLET CIRCUITS: Where multiple circuits serving electrical outlets are run in a single raceway (see paragraph above for allowable number of circuits per conduit), a shared common neutral is allowed.

3.6 VOLTAGE DROP:

- A. Provide branch circuit conductors in sizes such that voltage drop for branch circuits do not exceed 3 percent at the farthest outlet. Provide service, feeder, and branch circuit conductors so that the voltage drop on the entire electrical system does not exceed 5 percent at the farthest outlet. This shall be strictly followed regardless of the conductor sizes indicated on the electrical drawings. Increase conductor sizes (and conduits where necessary to comply with NEC conduit fill requirements) as necessary to accommodate this requirement. Calculations shall be based on the following:

1. Lighting Branch Circuits: Connected load plus 25% spare.
2. Appliance and Equipment Branch Circuits: Nameplate or NEC required load.
3. 120V Convenience Outlet Branch Circuits: 12 amps minimum, but in no case less than NEC loading requirements. Use the following schedule:

| <u>Distance (feet)</u> | <u>Wire Size (AWG)</u> |
|------------------------|------------------------|
| 0-80 | #12 |
| 81-125 | #10 |
| 126-200 | #8 |
| 201-320 | #6 |

4. Use the NEC method to calculate voltage drop.

3.7 CONNECTIONS:

- A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- B. Make splices and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches (150 mm) of slack. Use pig tails when wiring outlets.

3.8 FIELD QUALITY CONTROL:

- A. Testing: Perform the following field quality-control testing:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. Visual and Mechanical Inspection:
 - a) Inspect cables for physical damage and proper connection in accordance with the electrical construction documents.
 - b) Test cable mechanical connections to manufacturer's recommended values with a calibrated torque wrench.
 - c) Check cable color coding for compliance with electrical specifications.
 2. Electrical Tests:
 - a) Perform insulation resistance test on each conductors for feeders 100 amps and greater with respect to ground and adjacent conductors. Applied potential shall be 1000 volts dc for 1 minute.
 - b) Perform continuity test to insure proper cable connection.
 3. Test Values:
 - a) Minimum insulation resistance values shall not be less than two megohms.
- B. Test Reports: Prepare a written report and submit to the Electrical Engineer at the completion of the project. The report shall include the following:
1. Test procedures used.
 2. Test results that comply with requirements.
 3. Test results that do not comply with requirements and corrective action taken to achieve compliance with requirements.

END OF SECTION 16120

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16135 - ELECTRICAL BOXES AND FITTINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to electrical boxes and fittings.

1.2 DESCRIPTION OF WORK:

- A. Extent of electrical boxes and fittings work is indicated by drawings and schedules.
- B. Types of electrical boxes and fittings in this section include the following:
 - 1. Outlet Boxes
 - 2. Junction Boxes
 - 3. Pull Boxes
 - 4. Conduit Bodies
 - 5. Bushings
 - 6. Locknuts
 - 7. Knockout Closures
 - 8. Miscellaneous Boxes and Fittings

1.3 QUALITY ASSURANCE:

- A. Standards: Refer to Section 16001 - Electrical General Provisions as applicable.
- B. Manufacturers: Firms regularly engaged in the manufacture of boxes and fittings required, whose products have been in satisfactory service for not less than three years.
- C. Shop Drawings: Submit shop drawings on floor boxes only where required.

PART 2 - PRODUCTS

2.1 INTERIOR OUTLET BOXES:

- A. General: Provide one piece, galvanized or cadmium-plated, flat-rolled, sheet steel interior outlet boxes of types, shapes, and sizes to suit respective location and installation. Construct with stamped knockouts on back and sides and with threaded screw holes. Provide corrosion-resistant screws for securing boxes, covers, and wiring devices. Size all junction boxes in accordance with NEC Table 370-16(a), with a minimum box size of 4" x 4" x 1-1/2". Where three raceway entries are made, provide outlet boxes with a minimum depth of 2-1/8". Where four or more raceway entries are made, provide outlet boxes with a minimum depth of 4-11/16". Gangable boxes shall not be used.
- B. Switch, Telephone, and Receptacle Outlets: Provide outlet boxes not less than 4" square, with adapting tile or plaster covers where necessary to set flush with finished surfaces. Where three raceway entries

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

are made, provide outlet boxes with a minimum depth of 2-1/8". Gang boxes shall be used where more than one switch or device is located at one point. Sectional Boxes are not acceptable. In masonry walls where tile or plaster ring cannot be used, install a single-gang 3-1/2" deep box minimum, unless otherwise noted. Where four or more raceway entries are made, provide outlet boxes with a minimum depth of 4-11/16".

C. Lighting Outlets:

1. Lay-in Grid: Outlets for recessed fixtures in acoustical tile ceilings shall be located to center on a single tile or at the intersection of four tiles.
2. Surface-mounted: Provide 4" square octagonal outlet boxes for surface-mounted, ceiling fixture outlets. Mount each box independently of the conduit on standard 3/8" stud or approved box hanger where applicable. Include backing and supports as required to carry 200 lbs. Where three or more raceway entrances are made, use a minimum box depth of 2-1/8".

2.2 WEATHERPROOF OUTLET BOXES:

- A. Provide corrosion-resistant, cast-metal weatherproof outlet boxes, of types, shapes, and sizes, with threaded conduit ends, cast metal coverplates with spring-hinged waterproof caps, face plate gaskets, and corrosion-resistant fasteners.

2.3 JUNCTION AND PULL BOXES:

- A. Provide code-gauge sheet steel junction and pull boxes, with removable screw-on covers and welded seams, of types, shapes, and sizes to suit each respective location and installation. Size all junction and pull boxes in accordance with NEC 370-28. Provide stainless steel nuts, bolts, screws, and washer.

2.4 CONDUIT BODIES:

- A. Provide galvanized, cast-metal conduit bodies of type, shapes, and sizes to suit respective locations and installation. Construct with threaded conduit entrance ends and removable covers. Provide corrosion-resistant screws.
- B. Aluminum boxes and fitting shall not be permitted.

2.5 CONDUIT CONNECTIONS:

- A. Box connectors 3/4" and larger shall be insulated, throat-type or equal type plastic bushings. Provide double locknuts and insulating plastic bushings for RMC and IMC terminating at panels and boxes.
- B. Where RMC penetrates building, manholes, or vault walls and floors below grade, provide sealing bushings with external membrane clamps as applicable. Provide segmented internal sealing bushings in all raceways penetrating building walls and slabs below grade, and in all above grade raceway penetrations susceptible to moisture migration into building through raceway. Where RMC terminates in manhole, vault, or pull box, provide insulated grounding bushings. Also see Section 16135 – Electrical Boxes and Fittings.
- C. Install OZ type "B" connectors for all conduits 1" and larger.
- D. Provide cable supports in all vertical risers in accordance with NEC 300-19.

2.6 EXPANSION FITTINGS:

- A. Provide expansion joint fittings in all conduit runs crossing structural expansion joints, whether above-

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

grade, in slab-on-grade, or in suspended slabs. Provide OZ type "AX" or approved equivalent, size to the raceway.

2.7 ACCESSORIES:

- A. Provide all accessories including, but not necessarily limited to, bushings, knockout closures, locknuts, offset connectors, etc. of types, shapes, and sizes to suit respective locations and installation. Construct of corrosion-resistant steel.

PART 3 – EXECUTION

3.1 GENERAL:

- A. Install electrical boxes and fittings in accordance with manufacturer's written instruction, applicable requirements of the NEC, NEMA Standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 METHODS:

- A. Where outlet boxes are subject to weather or moisture, install weatherproof outlet boxes.
- B. Remove knockouts only for entering conduits. Provide knockout closures to cap unused knockout holes where blanks are mistakenly removed.
- C. Do not use condulets in place of elbows or junction boxes. Condulets in sizes 2" or larger shall not be used, unless specifically approved by the electrical engineer.
- D. Install boxes and conduit bodies in readily accessible locations. Install recessed boxes with faces of boxes or rings flush with finished surfaces. Seal all openings between outlet box and adjacent surfaces with plaster, grout, or similar suitable material.
- E. For stud construction, install boxes with rigid supports using metal bar hangers, or 2" X 4", 1" X 6" wood bridging between studs with screws. Welding or nailing boxes directly to metal joist and studs is not acceptable. Boxes set opposite in common wall shall have at least 10" of conduit between them. Securely fasten outlet boxes to structural surfaces to which attached.
- F. For concrete or masonry construction, solidly embed electrical boxes in concrete and masonry. Provide box supports as required to keep outlet boxes flush with finished surfaces.
- G. Coordinate location of all outlet boxes with millwork, back splashes, tackboards, etc.
- H. Install junction boxes or condulets in conduit runs as required at 100 foot maximum intervals on long runs. This shall apply to concrete junction boxes in grade and junction boxes within the building.
- I. Provide electrical connections for installed boxes.

3.3 IDENTIFICATION:

- A. Mark circuit number on exterior side of junction boxes located in ceilings such that circuits numbers are readily identifiable. For outlet boxes in wall, mark circuit numbers on interior sides of outlet boxes.
- B. Identification labels shall be as follows:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

| | |
|-----------------|---------------------------|
| Normal Power | Black with White letters |
| Emergency Power | Red with White Letters |
| UPS | Orange with White Letters |

END OF SECTION 16135

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16140 - WIRING DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to wiring devices.

1.2 DESCRIPTION OF WORK:

- A. Extent of wiring device work is indicated by drawings and schedules.
- B. Types of electrical wiring devices in this section include the following:
 - 1. Toggle Switches
 - 2. Receptacles
 - 3. Occupancy Sensors

1.3 QUALITY ASSURANCE:

- A. STANDARDS: Refer to Section 16001 - Electrical General Provisions as applicable.
- B. SHOP DRAWINGS:
 - 1. Submit manufacturer's data on all electrical wiring devices.
 - 2. Where occupancy sensors are required, provide scaled drawing showing manufacturer's recommended locations.

PART 2 - PRODUCTS

2.1 GENERAL:

- A. Provide factory-fabricated wiring devices, in types, and electrical ratings for applications indicated and complying with NEMA standards Pub No. WD 1. nylon construction, 20 amp rating minimum.
- B. Provide wiring devices in colors selected by Architect/Engineer. Provide red receptacle outlets and toggle switches where devices are circuited to emergency power. Provide orange receptacle outlets where devices are circuited to UPS power.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2.2 TOGGLE SWITCHES:

- A. Provide toggle switches from one of the following manufacturers (Fed-Spec):

| <u>Manufacturer</u> | <u>1-Pole</u> | <u>3-Way</u> | <u>4-Way</u> | <u>W/Pilot</u> |
|---------------------|---------------|--------------|--------------|----------------|
| Hubbell | HBL1221 | 1223 | 1224 | 1221-PL |
| Pass & Seymour | 20AC1 | 20AC3 | 20AC4 | 20AC1-RPL |
| Leviton | 1221 | 1222 | 1223 | 1221-PLR |
| Cooper | 2221 | 2223 | 2224 | 2221-PL |
| Bryant | 4901 | 4903 | 4904 | 4901-PL |

- B. Abbreviations are defined as follows:

- 1-Pole - Single-Pole Toggle Switch
- 3-Way - Three-Way Toggle Switch
- 4-Way - Four-Way Toggle Switch
- W/Pilo - Single-Pole Toggle Switch with Pilot Light

- C. Must be back and side wired, and have color-coded covers, Brass terminal screws, back wire ground clamp, and self-grounding clip.

2.3 RECEPTACLES:

- A. Provide duplex receptacles from one of the following manufacturers:

| <u>Manufacturer</u> | <u>CO</u> | <u>GFCI</u> | <u>IG</u> |
|---------------------|-----------|-------------|-----------|
| Hubbell | 5362 | GF5362 | 5362IG |
| Pass & Seymour | 5362 | 2091-S | IG6300 |
| Leviton | 5362 | 8899 | 5362-IG |
| Cooper | 5362 | VGF20 | IG5362 |
| Bryant | 5362 | GFR53FT | 5362IG |

- B. Abbreviations are defined as follows:

- CO- Convenience Outlet Duplex Receptacle
- GFCI- Ground Fault Circuit Interrupter duplex Receptacle
- IG- Isolated Ground Duplex Receptacle

2.4 DIMMERS:

- A. Fluorescent: Provide single-pole, AC dimmers for fluorescent fixtures, 60 hertz, 120 or 277 volt as applicable, with slide-to-off continuously adjustable slider control. Construct with continuously adjustable trim potentiometer for adjustment of low end dimming. Dimmers to be integral part of a fluorescent dimming system consisting of dimming ballast and lighting controls made by the same manufacturers. Refer to section 16510 – Interior Building Lighting. Provide dimmers from one of the following:

- B.
- Lutron (Nova T Series)
 - Levitron (IllumaTech Series)

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2.5 COVERPLATES:

- A. Wall Plates: Provide coverplates for all wiring devices. In all finished areas, provide nylon or high impact resistant thermoplastic coverplates in colors as selected by Architect. Provide red coverplates for all receptacle outlets and toggle switches that are circuited to emergency power. Provide orange coverplates for all isolated ground receptacle outlets. Provide stainless steel coverplates in commercial kitchens and food preparation areas. Provide ganged coverplates for all switches and/or dimmers. Provide pre-marked coverplates for special purpose outlet indicating voltage, amperages, and phase. Provide raised stamped, galvanized, steel plates in all unfinished areas. Provide weather-proof coverplates for outlets exposed to weather and moisture.
- B. Weather-Protecting Device Enclosure: Where required for compliance with NEC 410-67 (receptacles installed outdoors for use other than with portable tools or equipment), provide weather-tight device covers which provide complete protection with the cord and cap inserted into the wiring device. Provide units which mount on either single or double gang devices. Provide device enclosures manufactured by one of the following:
 - 1. Intermatic WP1020 or WP1030
 - 2. Hubbell WP826MP
 - 3. Pass & Seymore

2.6 OCCUPANCY SENSORS:

- A. General: Provide self-contained, ultrasonic motion detectors providing volumetric coverage without gaps within the detection area. Provide sensors in voltage and wattage ratings required to suit application. Provide sensors from one of the following manufacturers:
 - 1. Lithonia
 - 2. Novitas
 - 3. The Watt Stopper
 - 4. Hubbell
 - 5. Leviton
- B. Occupancy sensors specified on drawings are manufactured by the Watt Stopper. The manufacturers indicated above are acceptable provided that they meet the functional performance of those specified. Prior approval for these manufacturers is not required; however, if it is determined that the proposed occupancy sensors do not meet functional performance of the specified occupancy sensors, the Contractor shall provide the specified occupancy sensors at no additional cost to Owner.

PART 3 – EXECUTION

3.1 GENERAL:

- A. Install wiring devices and accessories in accordance with manufacturer's written instruction, applicable requirements of the NEC, NEMA Standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to insure that products fulfill requirements.

3.2 METHODS:

- A. Install wiring devices only in electrical boxes which are clean and free from excess building materials, dirt, and debris. Do not install wiring devices until painting work is completed.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. Replace receptacles and/or coverplates which are damaged, stained, or burned.
- 3.3 GFCI RECEPTACLES:
- A. Provide separate neutral conductor from panel to each GFCI receptacle circuits.
 - B. Install GFCI receptacles for all receptacles installed in restrooms, outdoors, or within six feet of any sink. All receptacles in kitchens shall be GFCI protected.
 - C. Do not wire standard receptacles on the load side of GFCI receptacle - Install GFCI receptacles.
- 3.4 DIMMERS:
- A. Provide separate neutral conductor for each phase of the branch circuit on which dimmers are installed.
 - B. Provide dimmers in wattage ratings that will support the maximum potential wattage of the fixture that are being dimmed. Do not size dimmers based on actual lamps installed in light fixtures, but on maximum lamp wattage ratings of light fixtures on that particular circuit.
- 3.5 SURFACE RACEWAYS:
- A. Provide all receptacles and special purpose outlets required in surface raceways. See Sections 16110 – Conduit Raceways, and 16135 – Electrical Boxes and Fittings.
- 3.6 OCCUPANCY SENSORS:
- A. Do not locate immediately adjacent to air diffusers. Coordinate exact placement with Division 15.
- 3.7 GROUNDING:
- A. Provide electrical continuous, tight, grounding connections for wiring devices.
- 3.8 TESTING:
- A. Prior to energizing circuitry, test wiring devices for electrical continuity and proper polarity connections. After energizing circuitry, test wiring devices to demonstrate compliance with requirements.
- 3.9 IDENTIFICATION:
- A. All devices shall be identified on the lower plate with panelboard name and circuit number.
 - B. In each outlet, tag each wire to identify the circuit it serves.
 - C. Identification labels shall be as follows:
 - Normal Power Black with White letters
 - Emergency Power Red with White Letters
 - UPS Orange with White Letters

END OF SECTION 16140

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16180 - OVERCURRENT PROTECTIVE DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to overcurrent protective devices.

1.2 DESCRIPTION OF WORK:

- A. Extent of overcurrent protective devices is indicated by drawings and schedules and is specified herein.
- B. Type of overcurrent protective devices in this section include the following:
 - 1. Molded Case Circuit Breakers

1.3 QUALITY ASSURANCE:

- A. STANDARDS: Refer to Section 16001 - Electrical General Provisions as applicable.
- B. SUBMITTALS:
 - 1. SHOP DRAWINGS: Submit manufacturer's data on overcurrent protective devices including specifications, time-current trip characteristics curves, mounting requirements, installation instructions, etc. Submit dimensioned drawings of overcurrent protective devices.
 - 2. Equipment Room Layouts: Submit dimensioned drawings of all equipment rooms indicating spatial relationships to other proximate equipment. Insure that all code required clearances are maintained.

PART 2 - PRODUCTS

2.1 GENERAL:

- A. Provide overcurrent protective devices and ancillary components of types, sizes, ratings, and electrical characteristics indicated. Provide enclosures in NEMA ratings as indicated and suitable for applications.

2.2 MOLDED CASE CIRCUIT BREAKERS:

A. MANUFACTURERS:

Subject to compliance with all requirements, provide molded case circuit breakers from one of the following:

- 1. General Electric
- 2. Square D

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

B. MOLDED CASE CIRCUIT BREAKERS:

1. Provide factory-assembled, molded case circuit breakers as integral components of lighting and appliance panelboards, power panelboards, switchboards, and for individual mounting as indicated. Provide thermal magnetic, molded case circuit breakers of amperages, voltages, types, and short circuit current ratings indicated. Provide bolt-on type breakers only. Construct with quick-break, quick-break mechanism with inverse-time delay and instantaneous trip protection for each pole. Provide breakers rated for ambient temperatures to suit respective applications. Provide mechanical screw type removable copper connector lugs of size to accommodate conductors specified.
2. Provide breakers that have interrupting ratings greater than or equal to the specified fault current. Provide fully-rated systems only. Series-rated systems are not acceptable, unless specifically noted otherwise.

PART 3 - EXECUTION

3.1 GENERAL:

- A. Install overcurrent protective devices in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 IDENTIFICATION:

- A. Provide 1/16" thick black plastic laminate labels with 1/4" high lettering on the exterior of each disconnect indicating name of disconnect or load served. Bolt labels to enclosure. Mark on interior cover the source of power by indicating the panel and circuit number.
- B. Provide red plastic laminate label for disconnects supplied by emergency power.

3.3 MOUNTING:

- A. Mount disconnects as indicated, but in no case higher than 6'-6" from finished floor to top of disconnect. Anchor enclosures firmly to walls and structural surfaces.
- B. Provide 4" high concrete pad under floor-standing disconnects.

END OF SECTION 16180

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16452 – GROUNDING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to grounding.

1.2 DESCRIPTION OF WORK:

- A. Extent of grounding work is indicated by drawings and schedules and is specified herein.
- B. Ground the complete electrical installation including the system neutral, metallic conduits and raceways, boxes, fittings, devices, cabinets, equipment, and separately derived systems in accordance with the NEC and all other applicable codes to provide a permanent, continuous, low impedance, grounding system.
- C. Provide grounding system such that the resistance from the service entrance ground bus, through the grounding electrode to earth is not greater than 5 ohms.

1.3 QUALITY ASSURANCE:

- A. STANDARDS: Refer to Section 16001 - Electrical General Provisions as applicable.
- B. TESTING: Submit results of ground resistance testing as specified in this section. Include name of testing agency with report. Include test results in operation and maintenance manuals.

PART 2 – PRODUCTS

2.1 GENERAL:

- A. Provide grounding equipment and accessories of types, sizes, ratings, and electrical characteristics indicated or as otherwise required to provide a complete system.

2.2 GROUNDING CONDUCTORS:

- A. Unless noted otherwise, provide grounding conductors with stranding and insulation types to match phase conductors. Provide conductors with green insulation if possible; otherwise wrap with green tape. Size ground conductors as indicated on drawings. Do not size ground conductors smaller than that allowable by NEC.

2.3 INSULATED GROUNDING BUSHINGS:

- A. Provide plated malleable iron body with 150 degree Centigrade molded plastic insulating throat, lay-in grounding lug with hardened stainless steel fasteners (OZ Gedney BLG or equivalent).

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2.4 CONNECTION TO PIPES:

- A. Provide heavy duty, cast bronze, ground clamp systems with silicon bronze bolts and nuts (OZ Gedney G Series - B or equivalent).

2.5 CONNECTIONS TO STRUCTURAL STEEL, GROUND RODS, OR SPLICES:

- A. Provide exothermic welds. (Cadweld or equivalent)

2.6 BONDING JUMPERS:

- A. Provide bonding jumpers with hot dip galvanized malleable or ductile iron clamps, hot dip galvanized steel U-bolts, and tinned copper braids (OZ Gedney BJ Series or equivalent).

2.7 GROUND BUS:

- A. Provide 1/4" x 4", copper ground bus complete with insulators and brackets in lengths and at mounting heights as indicated on drawings. Furnish complete with drilled holes and lugs to accommodate grounding conductors.

PART 3 - EXECUTION

3.1 GENERAL:

- A. Install grounding systems in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 CLEANING:

- A. Thoroughly clean all metal contact surfaces prior to installation of clamp-on connectors.

3.3 SEPARATELY DERIVED SYSTEMS:

- A. Ground each separately derived system in accordance with NEC Section 250.30 unless otherwise indicated on drawings.

3.4 EQUIPMENT BONDING AND GROUNDING:

- A. Provide an NEC sized conductor, whether indicated or not on the drawings, in raceways as follows:
 - 1. Non-metallic conduits and ducts.
 - 2. Distribution feeders.
 - 3. Motor and equipment branch circuits.
 - 4. Device and lighting branch circuits.
 - 5. Full length of all multi-outlet assemblies and other surface wireways.

3.5 ADDITIONAL GROUNDING INSTALLATION REQUIREMENTS:

- A. Provide grounding bushings on all service conduit and conduits installed in concentric/eccentric knock-outs or reducing washer at panelboards, cabinets, and gutters.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. Provide bonding jumpers across expansion and deflection couplings in conduit runs, across pipe connections at water meters, and across dielectric couplings in metallic cold water piping system. Connection to water piping system shall be made electrically continuous by connecting to the street side of the water main valve and/or installing additional bonding jumpers across the meter, valves or service unions that might be disconnected.
- C. Provide bonding wire in all flexible conduits.
- D. Isolated Ground Circuits: Circuits used for isolated ground outlets shall be run in separate raceways or shall have a separate green insulated ground conductor installed and tagged for identification at all outlet and junction boxes.

END OF SECTION 16452

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16510 - INTERIOR BUILDING LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to interior building lighting.

1.2 DESCRIPTION OF WORK:

- A. Extent of interior building lighting work is indicated by drawings and schedules and is specified herein.
- B. Type of lighting fixtures in this section include the following:
 - 1. Fluorescent
 - 2. Incandescent / Halogen

1.3 QUALITY ASSURANCE:

- A. STANDARDS: Refer to Section 16001 - Electrical General Provisions as applicable. Provide fluorescent-lamp ballasts which comply with Certified Ballast Manufacturer's Association standards and carry the CBM label.
- B. SHOP DRAWINGS: Submit manufacturer's data on interior building lighting fixtures. Submit dimensioned drawings of all lighting fixtures. Identify light fixtures by type and submit in alphabetical order.

PART 2 - PRODUCTS

2.1 GENERAL:

- A. Provide light fixtures of types as indicated on drawings or as approved by addenda. Provide light fixtures complete with, but not necessarily limited to, housings, lamps, lamp holders, reflectors, ballasts, starters, wiring, etc. Provide all light fixtures with safety latches where applicable.
- B. Provide all detachable fixture parts, luminous ceiling accessories, louvers, diffusers, lenses, and reflectors with locking catches, screws, safety chains, or safety cables.
- C. Provide all fixtures with damp or wet location labels as required by application.
- D. Provide all light fixtures and support accessories as required for a complete system.
- E. Consult architectural drawings for louvers (if any) to be provided by Division 16.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

2.2 FLUORESCENT LIGHT FIXTURES:

A. FLUORESCENT BALLASTS:

1. Electronic:
 - a. Manufacturers: Provide electronic ballasts from manufacturers specified as an integral part of light fixtures on the light fixture schedule. Where "generic" electronic ballasts are specified, provide products of one of the following for each fixture type:
 - 1) Advance Transformer
 - 2) Magnetek
 - 3) Motorola
 - 4) Osram Sylvania
 - b. Electronic Ballasts: Whether specified specifically or generically, provide electronic, fluorescent lamp ballasts for each type of fluorescent fixture capable of operating lamps indicated. Provide high power factor (97% or greater), Class P, sound-rated A, and internally thermally protected ballasts. Provide ballasts with input third harmonic content not exceeding 10% for 120V ballasts and less than 15% for 277V ballasts, average lamp current crest factor of 1.7, frequency of operation 20 KHz or greater, and non-PCB capacitors. Unless specifically noted otherwise, provide all interior light fixtures, with full light output electronic ballasts. Comply with all manufacturer's written recommendations for all lamp-ballast combinations.
 - c. Programmed Start Electronic Ballasts: Electronic ballasts shall be programmed start for maximum lamp life on shorter start cycles. Filament voltage shall be applied prior to the application of open circuit voltage to allow adequate heating of the filaments and then open circuit voltage is applied to start the lamps. Ballasts shall provide for a minimum lamp starting temperature of 0 Degrees F.
 - d. End-of-Life Circuitry: Ballasts for lamps of T5 and smaller including T5, T4, and T2 diameter shall contain end-of-life sensing circuitry to prevent lamp bulb, lamp base, or socket damage at lamp end-of-life.
2. Dimming:
 - a. Manufacturers: Subject to compliance with all requirements, provide products of one of the following for each fixture type:
 - 1) Lutron
 - 2) Dimming Ballasts:
 - b. Dimming ballasts shall be provided as part of a fluorescent dimming system where ballasts and controls are made by the same manufacturer. Refer to Fluorescent Lamp Dimmers Section 140 - Wiring Devices.
 - c. Ballasts shall be UL listed, Class P thermally protected and meet ANSI C62.41 (IEEE Publication 587, category A for surge protection.
 - d. Dimming shall be smooth and continuous without flicker down to 1% light levels for T-12, and T-8 lamps (5% for T-5 lamps).
 - e. Ballasts shall have a power factor greater than .95, ballast factor equal to .93, total harmonic distortion less than 10%, and lamp current crest factor less than or equal to 1.6.
 - f. Ballasts shall be inaudible in a 27dB ambient throughout the dimming range.
 - g. Ballasts shall be capable of striking lamps at any light level without first flashing to full light.
 - h. Ballasts shall comply with FCC Part 18 regulations and shall not interfere with other properly installed electrical equipment.
 - i. Ballasts shall have a minimum starting temperature of 10 Degrees C.
 - j. Ballasts shall be free of Polychlorinated Biphenyls (PCB's).
3. Ballast Fusing: All ballasts shall be externally and individually fused.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

B. FLUORESCENT LAMPS:

1. Manufacturers: Subject to compliance with all requirements, provide products of one of the following for each fixture type:
 - a. General Electric
 - b. Phillips
 - c. Osram Sylvania
2. Lamps: Provide fluorescent lamps in types, wattages, and sizes as indicated on fixture schedule. Unless specifically noted otherwise, equip interior light fixtures with full light output, energy-conserving, fluorescent lamps.
3. T-8 Lamps: Where T-8 lamps are specified, provide General Electric "Trimline", Sylvania "Octron", or Phillips only with initial lumens outputs of 2950 minimum.
4. Provide TCLP-compliant lamps where available from the manufacturer.

- C. DIFFUSERS: Where acrylic diffusers are specified, provide 100 percent virgin acrylic compound with minimum thickness of .125 inches.

2.3 INCANDESCENT / HALOGEN LIGHT FIXTURES

- A. Manufacturers: Subject to compliance with all requirements, provide products of one of the following for each fixture type:
1. General Electric
 2. Phillips
 3. Osram Sylvania
- B. Incandescent Lamps: Provide incandescent lamps in types, wattages, and sizes as indicated on the light fixture schedule.
- C. Halogen Lamps: Provide halogen lamps with increased LPW (IR technology) or improved optics in types, wattages, and sizes as indicated on the light fixture schedule.

PART 3 - EXECUTION

3.1 GENERAL:

- A. Install interior light fixtures in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 SUPPORT REQUIREMENTS:

A. RECESSED LIGHT FIXTURES:

1. Lay-in Ceilings: Support all light fixtures in lay-in ceilings independent from the ceiling system. Support each recessed light fixture from the building structure with #12 gauge steel wire attached to each corner. Provide clips to securely fasten lay-in light fixtures to Tee-Bars. Provide suspension bars for downlight fixtures in lay-in ceilings.
2. Gypsum Board, Plaster, or Similar Ceilings: Support all light fixtures in hard ceilings independent from the ceiling system. Support each recessed light fixture from the building structure with #12 gauge steel wire attached to each corner. Provide backing supports and all mounting accessories as required.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

3. Fire Ratings: Provide gypsum board protection for each light fixture recessed in fire-rated ceiling as required to maintain fire rating of penetrated ceiling.
 - B. SURFACE MOUNTED LIGHT FIXTURES: Support all surface mounted fixtures from a 4" square octagonal outlet box connected to a standard 3/8" stud or box hangar where applicable. Include backing and supports as required to support weight of light fixture.
 - C. PENDANT AND STEM MOUNTED LIGHT FIXTURES: Provide pendants, rigid conduit stems, and flexible ball joint hangers for all pendant and stem hung fixtures.
- 3.3 PROTECTION AND CLEANING:
- A. Protect installed and non-installed fixtures from damage during construction period.
 - B. Thoroughly clean all interior light fixtures. Do not mar or scar reflectors or diffusers. Repair all nicks and scratches to appearance of original finish. Remove protective plastic coverings on light fixtures at completion of project.
- 3.4 WIRING METHODS:
- A. Route a minimum of 36" of 3/8" flexible conduit to each lay-in light fixture directly from an outlet box. Unless specified otherwise, flexible conduit shall not exceed 72" in length. Do not loop flexible conduit from fixture to fixture.
 - B. Grounding: Provide equipment grounding connections for each lighting fixture.
- 3.5 COORDINATION:
- A. Refer to architectural reflected ceiling drawings for exact location and quantities of light fixtures, and ceiling types. Where conflicts occur between the architectural and electrical drawings, or where fixtures types do not coordinate with ceiling systems, notify architect/engineer prior to bid. After bid and award of contract, provide all light fixtures as required to meet the intent of the construction documents. Coordinate fixture layouts and installations with ceiling installer prior to submitting shop drawings and during construction. Fluorescent light fixtures shall be not less than 1/2" from combustible materials.
- 3.6 SPARE PARTS:
- A. LAMPS: Provide 15% spare lamps, but in no case less than one, of each type, wattage, and size used for the project.
 - B. ACRYLIC DIFFUSERS: Provide a spare acrylic diffusers and/or glass for each light fixture type and one for each additional unit for each ten fixtures. The quantity of any single type need not exceed 10.
 - C. ELECTRONIC BALLASTS: Provide 2% spare electronic ballasts.
- 3.7 WARRANTY:
- A. LAMPS: Warranty incandescent and fluorescent lamps for a period of two months from substantial completion.
 - B. ELECTRONIC BALLASTS: Warranty electronic ballasts for parts and labor for complete replacement for a period of five years. Warranty shall include an allowance for nominal replacement labor and replacement of defective product.

END OF SECTION 16510

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16532 - FLUORESCENT EMERGENCY BALLASTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 sections making reference to fluorescent emergency ballasts.

1.2 DESCRIPTION OF WORK:

- A. Extent of fluorescent emergency ballasts work is indicated by drawings and schedules and is specified herein.
- B. Type of fluorescent emergency ballasts include the following:
 - 1. Fluorescent Emergency Ballasts
 - 2. Compact Fluorescent Emergency Ballasts

1.3 QUALITY ASSURANCE:

- A. STANDARDS: Refer to Section 16001 - Electrical General Provisions as applicable.
- B. SHOP DRAWINGS: Submit manufacturer's data on fluorescent emergency ballasts.

PART 2 – PRODUCTS

2.1 FLUORESCENT EMERGENCY BALLASTS:

- A. Provide fluorescent emergency ballasts in accordance with the following:
 - 1. Shall operate one or two lamps at approximately 1100 to 1200 lumens initially and not less than 1050 lumens after 90 minutes.
 - 2. Battery shall be long life nickel cadmium type. Charger shall be capable of full recharge in 24 hours.
 - 3. Unit shall be complete with charging solid-state indicator light, double-pole test switch, and installation hardware.
 - 4. Unit shall be rated for dual voltage (120/277 VAC).
 - 5. Subject to all requirements, provide fluorescent emergency ballasts from one of the following manufacturers:
 - a. Bodine
 - b. Chloride
 - c. Lithonia
 - d. Iota
 - e. Emergi-Lite

2.2 COMPACT FLUORESCENT EMERGENCY BALLASTS:

- A. Provide compact fluorescent emergency ballasts in accordance with the following:
1. Shall operate one quad or triple-tube lamp at approximately 350 -750 lumens initially depending on wattage of lamp used for a minimum of 90 minutes.
 2. Battery shall be long life nickel cadmium type. Charger shall be capable of full recharge in 24 hours.
 3. Unit shall be complete with charging solid-state indicator light, double-pole test switch, and installation hardware.
 4. Unit shall be rated for dual voltage (120/277 VAC).
 5. Subject to all requirements, provide fluorescent emergency ballasts from one of the following manufacturers:
 - a. Bodine
 - b. Chloride
 - c. Lithonia
 - d. Iota
 - e. Emergi-Lite

PART 3 - EXECUTION

3.1 GENERAL:

- A. Install fluorescent battery ballasts in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 METHODS:

A. Installation:

1. Fluorescent Emergency Ballasts: Install fluorescent emergency lighting pack in ballast channel with charging indicator light and test switch mounted on fixture end, or visible and accessible through lens.
2. Compact Fluorescent Emergency Ballasts: Install compact fluorescent emergency light packs in ceiling adjacent to downlight. Install test/monitor plate close to the fixture in the ceiling.

B. Wire so unit can be tested with lights on.

C. Unless noted otherwise on drawings, wire so lamps in normal mode are switched off with other lighting in area. Connect emergency lighting unit to unswitched conductor of normal lighting circuit.

3.3 WARRANTY:

- A. Fluorescent Emergency Ballasts: Warranty fluorescent emergency ballasts lamps for a period of five (5) years (Not pre-rata).
- B. Compact Fluorescent Emergency Ballasts: Warranty compact fluorescent emergency ballasts lamps for a period of two (2) years (Not pre-rata).

END OF SECTION 16532

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 16740 - TELEPHONE AND DATA SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division-1 Specification Sections, apply to work of this section.
- B. This section is a Division 16 General Provisions section, and is part of each Division 16 section making reference to telephone and data systems.

1.2 DESCRIPTION OF WORK:

- A. Extent of telephone and data systems is indicated by drawings and schedules and is specified herein. Telephone and data systems includes the following:
 - 1. Outlet Boxes and Raceways

1.3 QUALITY ASSURANCE:

- A. STANDARDS: Refer to Section 16001 - Electrical General Provisions as applicable.

1.4 SHOP DRAWINGS: Not required.

PART 2 – PRODUCTS

2.1 OUTLET BOXES AND RACEWAYS:

- A. Provide outlet boxes and raceways in accordance with the following sections.
 - 1. Section 16110 - Conduit Raceways.
 - 2. Section 16135 - Electrical Boxes & Fittings
 - 3. Section 16072 – Electrical Support and Seismic Restraints

PART 3 - EXECUTION

3.1 GENERAL:

- A. Install telephone/data systems in accordance with manufacturer's written instructions, applicable requirements of NEC, NEMA standards, and NECA's "Standards of Installation", and in compliance with recognized industry practices to ensure that products fulfill requirements.

3.2 RACEWAYS:

- A. Unless otherwise noted, extend 3/4" conduit from each telephone/data outlet to telephone terminal

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- backboard, cabinet, or cable tray.
- B. Minimum trade size is 3/4". Install a 200 lb. polypropylene pull cord in each empty conduit run.
- C. Where raceway systems only are specified, provide blank coverplates for all unused telephone and data outlets.

END OF SECTION 16740

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

SECTION 211000 -WET PIPE FIRE-SUPPRESSION SPRINKLERS & PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes fire-suppression piping and equipment for the following building systems:
 - 1. Remodel Project: Wet-pipe, fire-suppression sprinklers, including piping, valves, specialties, and automatic sprinklers for areas indicated on architectural drawings. Relocate and replace sprinklers and piping as required for sprinkler coverage, matching existing heads. All relocated heads are to be replaced, not reused.
- B. Related Sections include the following:
 - 1. Division 26 Section "Fire Alarm Systems" for alarm devices not in this Section.

1.3 DEFINITIONS

- A. Working Plans: Documents, including drawings, calculations, and material specifications prepared according to NFPA 13 for obtaining approval from authorities having jurisdiction.
- B. Authority having Jurisdiction: The building official, Engineer and the insurance underwriter where applicable.

1.4 SYSTEM PERFORMANCE REQUIREMENTS

- A. Design sprinkler piping according to the following and obtain approval from authorities having jurisdiction. For projects governed by the state or local Fire Marshal's office, obtain review and approval from the Engineer prior to the Fire Marshal:
 - 1. Maximum Protection Area per Sprinkler:
 - a. Shell space 100 sq. ft. (No exception, install with 1" bushing.)
 - b. Office Space: 225 sq. ft..
 - c. Storage Areas: 130 sq. ft..
 - d. Mechanical Equipment Rooms: 130 sq. ft..
 - e. Electrical Equipment Rooms: 130 sq. ft..
 - f. Other Areas: According to NFPA 13 recommendations, unless otherwise indicated.
 - g. Extended coverage: Per listed coverage.
- B. Components and Installation: Capable of producing piping systems with 175-psig minimum working-pressure rating, unless otherwise indicated.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1.5 SUBMITTALS

- A. Product Data: For the following:
(All products to be domestic manufactured)
 - 1. Pipe and fitting materials and methods of joining for sprinkler piping.
 - 2. Pipe hangers and supports.
 - 3. Sprinklers, escutcheons, and guards. Include sprinkler flow characteristics, mounting, finish, and other pertinent data.
- B. Approved Sprinkler Piping Drawings: Working plans, prepared according to NFPA 13, that have been approved by authorities having jurisdiction. Include hydraulic calculations, unless noted otherwise. For designs governed by the local or state Fire Marshal's office, drawings are to be approved by the Engineer first.
- C. Field Test Reports and Certificates: Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13 and NFPA 14. Include "Contractor's Material and Test Certificate for Aboveground Piping" and "Contractor's Material and Test Certificate for Underground Piping."
- D. Maintenance Data: For each type of standpipe and sprinkler specialty to include in maintenance manuals specified in Division 1.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who has designed and installed fire-suppression piping similar to that indicated for this Project and obtained design approval and inspection approval from authorities having jurisdiction. The Engineer requires evidence to support the ability of the contractor to perform work in the scope and volume as specified. A contractor who cannot show such experience, may be found not suitable to perform the work. All Fire Sprinklers Contractors shall be pre-approved by Engineer.
- B. Engineering Responsibility: Preparation of working plans using AutoCad compatible drawing program, calculations, and field test reports by a qualified professional engineer or Engineering Technician NICET Level III. Base calculations on results of data provided in section 1.4.A.1.
- C. Manufacturer Qualifications: Firms whose equipment, specialties, and accessories are listed by product name and manufacturer in UL's "Fire Protection Equipment Directory" or FM's "Fire Protection Approval Guide" and that comply with other requirements indicated.
- D. Standpipe and Sprinkler Components: Listing/approval stamp, label, or other marking by a testing agency acceptable to authorities having jurisdiction.
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction.
- F. NFPA Standards: Equipment, specialties, accessories, installation, and testing complying with the following:
 - 1. NFPA 13-02, "Installation of Sprinkler Systems."
 - 2. NFPA 14-02, "Standpipe and Hose Systems."

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

3. NFPA 70-02, "National Electric Code."
4. NFPA 72-02, "National Fire Alarm Code."

G. International Conference of Building Code Officials codes and standards complying with the following:

1. IBC 2006, "International Building Code."
2. IFC 2006, "International Fire Code."

1.7 EXTRA MATERIALS

A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Sprinkler Cabinets: A supply of spare sprinklers (never less than 6) shall be supplied and located in a cabinet where the temperature does not exceed 100 deg F. These sprinklers shall correspond to the types and temperature ratings of the sprinklers installed on the project. Special sprinkler head wrenches shall be included to correspond to the types of heads provided.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Sprinklers:
 - a. Reliable Automatic Sprinkler Co., Inc.
 - b. Viking Corp.
 - c. Victaulic Co. of America
 - d. Tyco Corp.
2. Press-Seal Fittings for Steel Piping: (not allowed)

2.2 PIPING MATERIALS

A. Refer to Part 3 "Piping Applications" Article for applications of pipe, tube, fitting, and joining materials.

2.3 SPECIALTY VALVES

A. Ball Drip Valves: UL 1726, automatic drain valve, NPS 3/4, ball check device with threaded ends.

2.4 SPRINKLERS

A. Automatic Sprinklers: With heat-responsive element complying with the following:

1. UL 199, for applications except residential.
2. UL 1626, for residential applications.
3. UL 1767, for early suppression, fast-response applications.
4. NFPA #13, 1996 ed.

B. Sprinkler Types and Categories: Nominal 1/2-inch orifice for "Ordinary" temperature classification rating, unless otherwise indicated or required by application.

C. Sprinkler types, features, and options include the following:

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

1. Concealed ceiling sprinklers.
2. Extended-coverage sprinklers.
3. Pendent sprinklers.
4. Pendent, dry-type sprinklers.
5. Quick-response sprinklers.
6. Recessed sprinklers, including escutcheon.
7. Sidewall sprinklers.
8. Sidewall, dry-type sprinklers.
9. Upright sprinklers.

D. Sprinkler Finishes: Bronze and white.

E. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.

1. Ceiling Mounting: white steel, one piece, flat.
2. Ceiling Mounting: white steel, two piece, with 1-inch vertical adjustment.
3. Sidewall Mounting: white steel, one piece, flat.

F. Sprinkler Guards: Wire-cage type, including fastening device for attaching to sprinkler.

2.5 SPECIALTY SPRINKLER FITTINGS

- A. Specialty Fittings: UL listed and FM approved; made of steel, ductile iron, or other materials compatible with piping.
- B. Locking-Lug Fittings: (not allowed).
- C. Mechanical-T Fittings: (not allowed).
- D. Mechanical-Cross Fittings: (not allowed).
- E. Drop-Nipple Fittings: UL 1474, with threaded inlet, threaded outlet, and seals; adjustable.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in for piping to verify actual locations of piping connections before installation.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 COORDINATION

- A. All work of this contractor will be coordinated with other trades to insure minimal changes to the sprinkler system from the designs. Careful coordination of mechanical and electrical ducts, pipe and conduit shall be required.

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- B. The ceiling cavity must be carefully reviewed and coordinated with all trades. In the event of conflict, the installation of the mechanical equipment and piping shall be in the following order: plumbing waste, rainwater, and soil lines; supply, return, and exhaust ductwork, water piping, fire protection piping; and pneumatic control piping.
- C. All piping shall be run concealed where possible. All lines will be run as high as possible so as to not interfere with future changes to ceiling heights or other mechanical equipment. This contractor will be responsible for all sleeves, core drills, and sealing of penetrations in walls, floors, and structural members to facilitate the installation of the system, however, no holes in structural members will be allowed unless approved by the structural engineer.

3.3 PIPING APPLICATIONS

- A. Flanges, unions, and transition and special fittings with pressure ratings the same as or higher than system's pressure rating may be used in aboveground applications, unless otherwise indicated.
- B. Sprinkler Main Piping: Use the following:
 - 1. NPS 8 and Smaller: Plain-end, Type K hard copper tube; copper fittings; and brazed joints.

3.4 PIPING INSTALLATION

- A. Locations and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of piping. Install piping as indicated, as far as practical.
 - 1. Deviations from approved working plans for piping require written approval from authorities having jurisdiction. File written approval with Architect before deviating from approved working plans.
- B. Install unions adjacent to each valve in pipes NPS 2 and smaller. Unions are not required on flanged devices or in piping installations using grooved joints.
- C. Install "Inspector's Test Connections" in sprinkler piping, complete with shutoff valve, sized and located according to NFPA 13.
- D. Install sprinkler piping with drains for complete system drainage.
- E. Hangers and Supports: Comply with NFPA 13 for hanger materials. Install according to NFPA 13 for sprinkler piping and to NFPA 14 for standpipes.
 - 1. No powder driven studs allowed.
 - 2. Wrap-around braces are to be provided at end of branch lines.

3.5 SPECIALTY SPRINKLER FITTING INSTALLATION

- A. Install specialty sprinkler fittings according to manufacturer's written instructions.

3.6 SPRINKLER APPLICATIONS

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. General: Sprinkler heads shall be of the latest design closed spray type for 155 deg F unless specified otherwise or required by code. Heads in Light Hazard Occupancies shall be quick response type. Heads shall be a minimum orifice size of 1/2". Orifices larger than 1/2" may be used as required by density and spacing demands when specified. Use sprinklers according to the following applications:
1. Rooms without Ceilings: Upright and/or pendent sprinklers. Provide mechanical guards on all heads at or below 7'-0" height above the floor or where damage from room occupant use may occur.
 2. Rooms with Ceilings in MRI area : Non-ferrous Concealed sprinklers.
 3. Wall Mounting: Sidewall sprinklers with recessed escutcheon.
 4. Spaces Subject to Freezing: Upright; pendent, dry-type; and sidewall, dry-type sprinklers.
 5. Provide freeze proof type automatic sprinkler heads serving unconditioned spaces, areas subject to freezing and in other areas requiring their use.
 6. Heads located within the air streams of unit heaters or other heat-emitting equipment shall be selected for proper temperature rating.
 7. Sprinkler Finishes: Use sprinklers with the following finishes:
 - a. Upright, Pendent, and Sidewall Sprinklers: Chrome.
 - b. Concealed Sprinklers: Rough brass, with white cover plate.
 - c. Recessed Sprinklers: White with white escutcheon.
- B. Sprinklers: Use the following:
1. All sprinklers shall be listed, quick response type.

3.7 SPRINKLER INSTALLATION

- A. Every effort shall be required to insure that the heads form a symmetrical pattern in the ceiling with the ceiling grid, lights, diffusers and grilles. Offsets shall be made in piping to accommodate ductwork in the ceiling. Heads should be symmetrical and all piping run parallel or perpendicular to building lines.
1. In no case shall sprinkler heads be installed closer than approved distances from ceiling obstructions and HVAC ductwork.
 2. Sprinkler heads shall not conflict with tile grids.
 3. Locate sprinklers in center of tile, in waiting rooms, corridors and bridge to Moran Building.
- B. Where layout of sprinkler heads is shown on reflected ceiling plans the locations shall be followed unless approval is obtained from the Architect or such locations shown do not meet the requirements of NFPA-13. In either case, approval of the Architect shall be obtained in writing before sprinkler head locations are changed. If the installation of additional heads are needed to conform to NFPA 13 requirements in areas where heads are shown on reflected ceiling plans, they shall be included in the contract price.
- C. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing. Use dry-type sprinklers with water supply from heated space.

3.8 LABELING AND IDENTIFICATION

- A. Install labeling and pipe markers on equipment and piping according to requirements in NFPA 13 and NFPA 14."

3.9 FIELD QUALITY CONTROL

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

- A. Flush, test, and inspect sprinkler piping according to NFPA 13, "System Acceptance" Chapter.
- B. Replace piping system components that do not pass test procedures and retest to demonstrate compliance. Repeat procedure until satisfactory results are obtained.
- C. Report test results promptly and in writing to Architect and authorities having jurisdiction.
- D. Whether the underground serving the sprinkler system is done by this contractor or another, this contractor will be responsible to assure and have in his possession a certificate that the underground has been flushed and tested by the contractor who installed it in accordance with NFPA-24 prior to connection of the underground piping to the overhead sprinkler system.

3.10 CLEANING

- A. Clean dirt and debris from sprinklers.
- B. Remove and replace sprinklers having paint other than factory finish.

3.11 PROTECTION

- A. Protect sprinklers from damage until Substantial Completion.

3.12 COMMISSIONING

- A. Verify that specialty valves, trim, fittings, controls, and accessories are installed and operate correctly.
- B. Verify that specified tests of piping are complete and that "Material Test Certificates" are complete.
- C. Verify that damaged sprinklers and sprinklers with paint or coating not specified are replaced with new, correct type.
- D. Verify that sprinklers are correct types, have correct finishes and temperature ratings, and have guards as required for each application.
- E. Verify that fire department connections have threads compatible with local fire department equipment.
- F. Fill wet-pipe sprinkler piping with water.
- G. Coordinate with fire alarm tests. Operate as required.

3.13 DEMONSTRATION & TESTS

- A. Demonstrate equipment, specialties, and accessories. Review operating and maintenance information.
- B. All tests will be conducted as required by the local authority having jurisdiction, and in no case less than those required by NFPA standards. As a minimum, piping in the sprinkler system shall be tested at a water pressure at 200 psi for a period of not less two hours, or at 50 psi in excess of the normal pressure when the normal pressure is above 150 psi. Bracing shall be in place, and air shall be removed from the

Department of Human Services
Moab Regional Center Upgrades
Division of Facilities Construction Management

system through the hydrants and drain valves before the test pressure is applied. No apparent leaks will be permitted on interior or underground piping.

- C. The local jurisdiction having authority and the State Fire Marshal's office (where required) shall be notified at least three working days in advance of all tests and flushing. This includes any flushing of undergrounds, hydrostatic testing, or flow testing that may be required.
- D. This contractor shall make all the required tests to the sprinkler system as required by code. He shall be responsible to assure that the Contractor Test Certificates for the overhead and underground work are completed and delivered to the owner's insurance underwriter to assure proper insurance credit.
- E. All tests requiring the witnessing by local authorities will be the responsibility of this contractor. If tests are not run or do not have the proper witness, then they will be run later and all damage caused by the system, or caused in uncovering the system for such test, will be borne by this contractor.

3.14 WARRANTY, O & M's, AS-BUILTS

- A. This contractor shall warranty the sprinkler system and all its components for one year from the date of acceptance by the owner. Any costs incurred to extend any warranties of materials to assure this time frame shall be borne by this contractor.
- B. Provide Operation and Maintenance Manuals with correct as-built included and copies of warranty and test certificate. 6 sets to be provided in red 3-ring binders.
- C. Electronic copy of AutoCad as-builts drawings and O & M Manual shall also be provided on CD, with each O&M Manual.

3.15 FIELD QUALITY CONTROL

- A. Flush, test and inspect sprinkler piping according to NFPA 13, "System Acceptance" Chapter.
- B. Replace piping system components that do not pass test procedures and retest to demonstrate compliance. Repeat procedure until satisfactory results are obtained.
- C. Report test results promptly and in writing to Architect and authorities having jurisdiction.

END OF SECTION 211000