

CODE ANALYSIS

APPLICABLE CODES

Year	Year
International Building Code 2006	National Electrical Code 2005
International Mechanical Code 2006	Uniform Code for Building Conservation
International Fuel Gas Code 2006	ADA Accessibility Guidelines ICC/ANSI 117.1 2003
International Plumbing Code 2006	
International Fire Code 2006	
International Energy Conservation Code 2006	

A. Occupancy and Group: UNLIMITED - COVERED MALL BUILDING

Change in Use: Yes ☒ No ☐ Mixed Occupancy: Yes ☒ No ☐

Special Use and Occupancy (e.g. High Rise, Covered Mall): COVERED MALL BUILDING

B. Seismic Design Category: D Design Wind Speed: 90 mph

C. Type of Construction (circle one):

II B

D. Fire Resistance Rating Requirements for the Exterior Walls based on the fire separation distance (in hours):

North: EXISTING South: EXISTING East: EXISTING West: EXISTING

E. Mixed Occupancies: ☒ Nonseparated Uses: 0

F. Sprinklers:

Required: ☒ Provided: ☒

Type of Sprinkler System (IBC 903.3.1) NFPA 13

G. Number of Stories: 3 Building Height: 34'

H. Actual Area per Floor (square feet): ADDITION 1800 SF

I. Tabular Area: (table 503): N/A - UNLIMITED - COVERED MALL BUILDING

J. Area Modifications:

a) $A_a = \left\{ A_t + \left[A_t \times I_f \right] + \left[A_t \times I_s \right] \right\} \quad I_f = \left[F/P - 0.25 \right] W / 30$

b) Sum of the Ratio Calculations for Mixed Occupancies:

$$\frac{\text{Actual Area}}{\text{Allowable Area}} \leq 1$$

c) Total Allowable Area for:

- One Story:
- Two Story: A_a(2)
- Three Story: A_a(3)

d) Unlimited Area Building: Yes ☒ No ☐ Code Section: 402

K. Fire Resistance Rating Requirements for Building Elements (hours).

Element	Hours	Assembly Listing	Element	Hours	Assembly Listing
Exterior Bearing Walls	0		Floors - Ceiling Floors	0	
Interior Bearing Walls	0		Roofs - Ceiling Roofs	0	
Exterior Non-Bearing Walls	0		Exterior Doors and Windows	0	
Structural Frame	0		Shaft Enclosures	1 Hr.	
Partitions - Permanent	N/A		Fire Walls	N/A	
Fire Barriers	N/A		Fire Partitions	N/A	
			Smoke Partitions	N/A	

L. Design Occupant Load: EXIST. BLDG: 620 ADDITION: 26 (24, STUDIO + 2, STORAGE)

Exit Width Required: 160" EXIST. 3.5' ADDED Exit Width Provided: 192"

M. Minimum Number of Required Plumbing Facilities:

- Water Closets - Required (m) 18 (f) 18 Provided (m) 20 (f) 20
- Urinals - Required (m) (f) Provided (m) (f)
- Lavatories - Required (m) 9 (f) 9 Provided (m) 9 (f) 9
- Bath Tubs or Showers: 0
- Drinking Fountains: 3 Service Sinks: 2

FOOTNOTES:

- In case of conflict with the U.S. Department of Justice Federal Registers Parts I through V - ADA Guidelines and specific reference to the International Building Code Accessibility Chapters, the more restrictive requirement shall govern.
- Additional Code Information shall be provided at the discretion of the Building Official for Complex Buildings. Including, but not limited to:
 - High Rise Requirements.
 - Atriums.
 - Performance Based Criteria.
 - Means or Egress Analysis.
 - Fire Assembly Locator Sheet.
 - Exterior and Interior Accessibility Route.
 - Fire Stopping, Including Tested Design Number.

PROJECT TEAM

OWNER:
DFCM
Mike Ambre
Project Manager
4110 State Office Bldg.
Salt Lake City, Utah 84114
phone (801) 537-9210

USER:
UVSC
James L. Michaelis
Associate Vice President
Facilities Planning
800 West University Parkway
Orem, Utah 84058-5999
phone (801) 963-8776


ARCHITECT:
AXIS ARCHITECTS
Pierre O. Langue AIA
352 S. Denver St.
Salt Lake City, UT 84111
phone (801) 355-3003
fax (801) 355-0113

STRUCTURAL:
Bsumek Mu
Reinhardt Bsumek
345 South 400 East
Salt Lake City, Utah 84111
phone (801) 575-8223
fax (801) 532-3778


MECHANICAL:
Van Boerum & Frank
Wade Bennion
330 South 300 East
Salt Lake City, Utah 84111
phone (801) 530-3150
fax (801) 674-8617

ELECTRICAL:
BNA Consulting
Elaine Fawson
635 S. State Street
Salt Lake City, Utah 84111
phone (801) 355-3003
fax (801) 355-8578


VINCINITY MAP




OVERALL SITE PLAN



SYMBOL LEGEND



GRAPHIC SYMBOLS



DRAWING INDEX

GENERAL
GI101 GENERAL INFORMATION

ARCHITECTURAL

AD101 DEMOLITION PLAN
AE001 SITE PLAN
AE101 FLOOR PLAN
AE102 ROOF PLAN
AE111 REFLECTED CEILING PLAN
AE201 BUILDING ELEVATIONS
AE301 BUILDING SECTIONS
AE601 DETAILS

STRUCTURAL

SE001 STRUCTURAL GENERAL NOTES
SE101 FOOTING AND ROOF FRAMING PLAN
SE301 STRUCTURAL SECTIONS
SE501 STRUCTURAL DETAILS

MECHANICAL

ME001 MECHANICAL SYMBOLS, NOTES AND INDEX
ME501 MECHANICAL SCHEDULES
ME601 MECHANICAL SCHEDULE
MH101 MECHANICAL PLAN
PD101 PLUMBING DEMO PLAN
PP101 PLUMBING PLAN

ELECTRICAL

EG001 ELECTRICAL SYMBOLS, SCHEDULES, NOTES
EX101 LIGHTING PLAN AND POWER PLAN

NOTE: THE SHEETS LISTED ABOVE REPRESENT A FULL SET OF CONSTRUCTION DOCUMENTS AND INCLUDE A DETAIL BOOK AND A PROJECT MANUAL AND SHALL NOT BE SEPERATED. ANY CONTRACTOR, SUBCONTRACTOR, VENDOR OR ANY OTHER PERSON PARTICIPATING IN OR BIDDING ON THIS PROJECT SHALL BE RESPONSIBLE FOR REVIEWING ALL THE CONSTRUCTION DOCUMENTS INCLUDING BUT NOT LIMITED TO DRAWINGS, DETAILS, PROJECT MANUAL, SPECIFICATIONS AND ANY AND ALL ADDENDA ISSUED.

UTAH VALLEY STATE COLLEGE
STUDENT CENTER ADDITION
Orem, Utah

DFCM PROJECT # 08217790

CONSTRUCTION DOCUMENTS
JUNE 2, 2008



ENGINEERING, FACILITIES PLANNING & CONSTRUCTION DEPARTMENT

State of Utah
Department of Administrative Services

Division of Facilities
Construction & Management
4110 State Office Building
Salt Lake City, Utah 84114
Phone: (801) 538 - 3018
Fax: (801) 538 - 3267

ALTERNATES

ALTERNATE 1: ADD WINDOW "C" AND "D" - SEE FLOOR PLAN BASE BID INCLUDES A PAINTED GYP. BOARD WALL

APPROVALS

Prime Agency _____ Date _____

DFCM _____ Date _____

APPROVAL DOES NOT RELIEVE A/E OF DESIGN LIABILITY


UVSC - STUDENT
CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS


Revision # Date



Axis Job # **0721**
Owner #
Date 6-2-2008
Drawn
Checked

GENERAL INFORMATION

GI101







Axis Architects

UVSC - STUDENT CENTER ADDITION

OREM, UTAH


CONSTRUCTION DOCUMENTS


Revision # Date



Axis Job # 0721
Owner #
Date 6-2-2008
Drawn
Checked

PLANS

AE101







Axis Architects

UVSC - STUDENT
CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS


Revision # Date

.
. .
. .
. .


Axis Job # 0721
Owner #
Date 6-2-2008
Drawn
Checked

ELEVATIONS


AE201



DOOR FRAME TYPES






DOOR TYPES



FINISH LEGEND

- WALL:
1. PAINT COLOR 1
 2. PAINT COLOR 2
 3. PAINT TO MATCH EXIST
- FLOOR:
- F1 CARPET
F2 SEALED CONC.
F3 WOOD
- BASE:
- B1 RUBBER BASE
B2 WOOD BASE
B3
1. MATERIALS IN SIMILAR LOCATIONS ARE NOT KEYNOTED AT EVERY OCCURRENCE.
2. PROVIDE CONCRETE MOISTURE SEALER. ALL AREAS TO RECEIVE A FLOWERING FINISH MATERIAL
- NORTH WALL FINISH
BASE FINISH
B1* ABOVE
FLOOR FINISH
SOUTH WALL FINISH

WINDOW TYPES - ALUMINUM STORE FRONT



NOTES

1. CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO FABRICATION
2. SEE DETAILS IN-SERIE FOR SIGNAGE
3. MATERIALS IN SIMILAR LOCATIONS ARE NOT KEYNOTED AT EVERY OCCURRENCE.
4. ALL EXISTING DOORS & FRAMES TO BE PREPPED, HOLES REPAIRED, AND PAINTED
5. REFER TO ADA REQUIREMENTS FOR MOUNTING HEIGHTS , ETC. FOR FIXTURES - COORD. W/ MECH. AND ELECTRICAL.

GLAZING SCHEDULE

- A. 1" INSULATED LOW-E GLASS - TINTED BRONZE TO MATCH
- B. 1" INSULATED SPANDREL PANEL - PRE-FINISHED ALUMINUM (BOTH SIDES) TO MATCH DOOR.
- C. 1/4" FLOAT GLASS
- D. 45 MIN RATED GLASS


NOTES

1. CONTRACTOR TO FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO FABRICATION
2. SEE DETAILS IN-SERIES IN DETAIL BOOK
3. FILL AND COMPACT ALL DISTURBED SOIL.
4. PATCH, REPAIR, PREP. AND PAINT ALL INTERIOR SURFACES OF EXISTING WALLS.
5. REMOVE GLUE FROM EXISTING CONCRETE FLOOR AND PATCH, PREP. AS NECESSARY FOR INSTALLATION OF NEW VCT.
6. PROVIDE INTERIOR HORIZONTAL LOUVER BLINDS ON ALL EXTERIOR WINDOWS.

WALL TYPES

- EXISTING WALL TO REMAIN
- 2x4 STUD WALL EXTEND TO STRUCTURE. WALL WITH GYP. BOARD ON BOTH SIDES WITH SCHEDULED FINISH. EXTEND GYP. BOARD 6" ABOVE CEILING - NO GYP. BOARD IN CHASES

- NOTE:
1. ALSO SEE NOTES ON FLOOR PLANS
 2. ADD INSULATION IN OFFICE AND RESTROOM PERIMETER WALLS.




A1 STACKABLE WALL PARTITION DOOR

SCALE: 1-1/2"=1'-0"

B3 WALL AT BEAM/ INFILL

SCALE: 3"=1'-0"




A2 WOOD FLOOR DETAIL

SCALE: 3"=1'-0"


C4 WALL SECTION DETAIL AT EXTERIOR

SCALE: 3"=1'-0"



A3 WRAPPED WINDOW AT VERT. SUPPORT

SCALE: 3"=1'-0"



Axis Architects

UVSC - STUDENT
CENTER ADDITION
OREM, UTAH

CONSTRUCTION DOCUMENTS



Revision # Date

.....

Axis Job # 0721
Owner #
Date 6-2-2008
Drawn
Checked

DETAILS

AE601



Axis Architects



UVSC - STUDENT
CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS

Revision # Date
.
.
.

Axis Job # 20034
Owner #
Date 5-30-2008
Drawn
Checked

FOOTING & FOUNDATION AND ROOF FRAMING
PLANS

SE101



Axis Architects

UVSC - STUDENT
CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS




Revision # Date

.....

Axis Job # 28034
Owner #
Date 5-30-2008
Drawn
Checked

SECTIONS

SE301



Axis Architects

UVSC - STUDENT
CENTER ADDITION

OREM, UTAH

CONSTRUCTION DOCUMENTS


Revision # Date

.....


Axis Job # 28034
Owner #
Date 5-30-2008
Drawn
Checked

TYPICAL DETAILS

SE501



Axis Architects



UVSC - STUDENT
CENTER ADDITION
OREM, UTAH

CONSTRUCTION DOCUMENTS

Revision # Date

Axis Job # 0721
Owner #
Date 5-30-2008
Drawn EL
Checked WB

MECHANICAL SYMBOLS

ME001

LEGEND OF MECHANICAL SYMBOLS AND ABBREVIATIONS

MECHANICAL

	POSITIVE PRESSURE DUCT – RISE
	POSITIVE PRESSURE DUCT – DROP
	NEGATIVE PRESSURE DUCT – RISE
	NEGATIVE PRESSURE DUCT – DROP
	ROUND DUCT – RISE
	ROUND DUCT – DROP
	UNDER FLOOR DUCT
	TURNING VANES
	FRESH AIR LOUVER
	RELIEF AIR OR EXHAUST AIR LOUVER
	CEILING SUPPLY DIFFUSER
	CEILING RETURN REGISTER
	CEILING EXHAUST REGISTER, (BALANCE TO MATCH SUPPLY IF RETURN CFM IS NOT SHOWN)
	SIDEWALL SUPPLY REGISTER
	SIDEWALL EXHAUST OR RETURN REGISTER
	CEILING SUPPLY DIFFUSER WITH FLEXIBLE DUCT
	CEILING AIR GRILLE WITH FLEXIBLE DUCT
	CEILING RETURN AIR GRILLE W/ SOUND BOOT
	LINEAR DIFFUSER WITH PLENUM AND FLEXIBLE DUCT CONNECTION. NO. OF SLOTS & SIZE OF SLOT ON TOP, ACTIVE LENGTH AND CFM ON BOTTOM
	FLEXIBLE DUCT CONNECTION
	FLEXIBLE DUCT
	FAN
	FLAT OVAL DUCT WITH NET INSIDE DIMENSIONS SHOWN IN INCHES.
	RECTANGULAR DUCT WITH NET INSIDE DIMENSIONS SHOWN IN INCHES.
	ROUND DUCT WITH NET INSIDE DIMENSIONS SHOWN IN INCHES.
	INCLINED RISE
	INCLINED DROP
	R/W=1. ROUND DUCT SIMILAR TO RECTANGULAR
	RECTANGULAR TO RECTANGULAR OR ROUND TO ROUND DUCT TRANSFORMATION MAXIMUM 15° INCLUDED ANGLE EXCEPT WHERE SHOWN OTHERWISE.
	RECTANGULAR TO ROUND DUCT TRANSFORMATION
	BRANCH DUCT SPLIT WITH 6" WIDTH AND MIN. R=10X OF BRANCH DUCT DOWNSTREAM. ELBOW TURNING VANE OPTIONAL.
	TAP ENTRY AREA EQUALS 150% OF BRANCH AREA
	HIGH EFFICIENCY FITTING
	MANUAL VOLUME DAMPER
	FIRE DAMPER IN DUCT, W/ ACCESS PANEL REQD.
	COMBINATION FIRE/SMOKE DAMPER W/ ACCESS PANEL
	SMOKE DAMPER W/ ACCESS PANEL
	BACK DRAFT DAMPER
	ATC DAMPER
	ACCESS PANEL IN DUCT OR PLENUM
	HEATING OR COOLING COIL IN DUCT
	SINGLE DUCT AIR TERMINAL BOX VARIABLE OR CONSTANT VOLUME. MIN. 1-1/2" TERMINAL INLET SIZE STRAIGHT DUCT AT TERMINAL INLET.
	4-WAY BLOW PATTERN
	3-WAY BLOW PATTERN
	2-WAY BLOW PATTERN
	2-WAY BLOW PATTERN
	1-WAY BLOW PATTERN
	DUCT SMOKE DETECTOR
	UNIT HEATER

PLUMBING

	FLOOR SINK
	FLOOR DRAIN
	FLOOR CLEAN-OUT OR CLEAN-OUT TO GRADE
	ROOF DRAIN
	DOWNSPOUT NOZZLE
	ARROW INDICATES DIRECTION OF FLOW IN PIPE
	CHECK VALVE
	PRESSURE REDUCING, EXTERNAL PRESSURE VALVE
	PRESSURE REDUCING, SELF CONTAINED VALVE
	ATC VALVE – 2 WAY
	ATC VALVE – 3 WAY
	SOLENOID VALVE
	GATE VALVE
	GATE VALVE – NON RISING STEM
	GLOBE VALVE
	TEMPERATURE AND PRESSURE TEST PORT
	PRESSURE SWITCH
	GAS COCK
	CALIBRATED BALANCING VALVE WITH CFM INDICATED
	REDUCED PRESSURE BACKFLOW PREVENTOR W/ DRAIN PAN
	BRANCH – BOTTOM CONNECTION
	BRANCH – TOP CONNECTION
	BRANCH – SIDE CONNECTION
	RISE OR DROP
	RISE – DOWN (ELBOW)
	RISE – DOWN (ELBOW)
	VENT THRU ROOF
	WATER HAMMER ARRESTOR
	INLINE PUMP
	INLINE PUMP
	CLEAN-OUT
	RELIEF VALVE
	ANGLE VALVE
	FLOW METER
	UNION
	BALANCING COCK
	SHUT-OFF COCK FOR USE WITH PRESSURE GAUGE
	FLEXIBLE EXPANSION JOINT
	THERMOMETER – TEMP RANGE AS INDICATED
	PRESSURE GAUGE WITH SHUT-OFF COCK
	PRESSURE GAUGE WITH PIGTAIL
	LATERAL STRAINER WITH BLOW-OFF VALVE, PROVIDE HOSE END WITH CAP WHERE DISCHARGE IS NOT PIPED TO DRAIN
	BALL VALVE (PIPE SIZES 2" AND SMALLER)
	BUTTERFLY VALVE (PIPE SIZES 2-1/2" AND LARGER)
	MOTOR OPERATED BUTTERFLY VALVE
	VALVE IN RISE
	AIR VENT-MANUAL
	AIR VENT-AUTO
	FLOW SWITCH
	REDUCER
	CONCENTRIC REDUCER
	ECCENTRIC REDUCER

PLUMBING CONT.

	THERMOSTATIC MIXING VALVE
	HOSE BIBB
	PIPE CAP
	SWITCH
	SENSOR
	THERMOSTAT
	NIGHT THERMOSTAT
	FILL PORT
	DRAIN PAN AND P-TRAP
	FIXTURE FROM LEVEL ABOVE
	FLOW METER ORIFICE
	FLANGE
	90° ELBOW
	STEAM TRAP, F&T=FLOAT & THERMOSTATIC ELBOW
	B=BUCKET, T=THERMOSTATIC
	LEADER INDICATES DOWNWARD SLOPE
	DEMOLITION
	ALIGNMENT GUIDE
	ANCHOR
	LUBRICATED PLUG COCK

SYMBOLS

	PLUMBING FIXTURES
	POINT OF CONNECTION
	SECTION TAG – TOP FIGURE IS SECTION NO. BOTTOM FIGURE IS SHEET NO.
	DETAIL TAG – TOP FIGURE IS DETAIL NO. BOTTOM FIGURE IS SHEET NO.
	EQUIPMENT IDENTIFICATION
	KEYED NOTE IDENTIFICATION

FIRE

	HOSE VALVE
	NRS GATE VALVE WITH SUPERVISION
	FLOW SWITCH
	FIRE RISER
	SPRINKLER HEAD
	FIRE SPRINKLER WATER

LINETYPES


	ACID VENT
	ACID WASTE
	BOILER BLOW DOWN
	BOILER FEED WATER
	BRINE
	CARBON DIOXIDE
	COMPRESSED AIR
	CHEMICAL FEED
	CHILLED WATER SUPPLY
	CHILLED WATER RETURN
	CONDENSER WATER SUPPLY
	CONDENSER WATER RETURN
	DOMESTIC COLD WATER (DCW)
	DOMESTIC HOT WATER (DHW)
	DOMESTIC HOT WATER RETURN (DHW)
	DEIONIZED WATER SUPPLY
	DEIONIZED WATER RETURN
	EXISTING PIPING
	EXISTING PIPING TO BE REMOVED
	GLYCOL HEAT RECOVERY PIPING
	GLYCOL PIPING SOLUTION
	FUEL OIL RETURN
	FUEL OIL SUPPLY
	FUEL OIL VENT
	NATURAL GAS
	HOT GAS
	HELICOPTER FUEL RETURN
	HELICOPTER FUEL SUPPLY
	HIGH PRESSURE DOMESTIC WATER
	HIGH PRESSURE CONDENSATE
	HIGH PRESSURE STEAM
	HEATING HOT WATER RETURN
	HEATING HOT WATER SUPPLY
	INSTRUMENT AIR
	INSTRUMENT AIR AT PRESSURE INDICATED
	LAB AIR
	LAB VACUUM
	LOW PRESSURE CONDENSATE
	LIQUIFIED PETROLEUM GAS
	LOW PRESSURE STEAM
	MEDICAL AIR
	MEDICAL AIR AT PRESSURE INDICATED
	MEDIUM PRESSURE CONDENSATE
	MEDIUM PRESSURE STEAM
	MAKE UP WATER
	MEDICAL VACUUM
	NITROGEN
	NITROUS OXIDE
	MEDICAL OXYGEN
	MEDICAL OXYGEN AT PRESSURE INDICATED
	PUMPED CONDENSATE

LINETYPES CONT.


	REVERSE OSMOSIS WATER SUPPLY
	REVERSE OSMOSIS WATER RETURN
	ROOF DRAIN
	ROOF DRAIN OVERFLOW
	REFRIGERANT LIQUID
	REFRIGERANT SUCTION
	SEWER (BELOW GRADE)
	SEWER (ABOVE GRADE)
	SOFT DOMESTIC WATER (SW)
	VACUUM
	VENT (SEWER)

MECHANICAL GENERAL NOTES


1. PROVIDE BALANCING DAMPER AT EACH BRANCH TAKE-OFF TO SERVE DIFFUSER OR GRILLE AS WELL AS WHERE INDICATED.
2. COORDINATE EXACT LOCATION OF DUCTS WITH STRUCTURAL MEMBERS, LIGHTS, REFLECTED CEILING, CABLE TRAY, PLUMBING, MECHANICAL PIPING, FIRE PROTECTION, ETC.
3. BRANCH DUCTWORK SHALL BE SIZED TO MATCH THE NECK SIZE OF THE DIFFUSER, REGISTER OR GRILLE IT SERVES UNLESS NOTED OTHERWISE, TYPICAL.
4. COORDINATION DRAWING SUBMITTALS ARE REQUIRED FOR THIS SHEET.
5. SEE ARCHITECTURAL PLANS FOR EXACT LOCATION OF ALL REGISTERS, DIFFUSERS AND GRILLES.
6. INSTALL ALL HARD ELBOWS AS SHOWN. HARD ELBOWS ARE REQUIRED FOR SOUND ATTENUATION.
7. INSTALL EQUIPMENT WITH CLEARANCE PER MANUFACTURERS RECOMMENDATIONS. MAINTAIN PROPER SPACE FOR COIL PULL, CONTROLS, AND MAINTENANCE ACCESS.
8. ALL BRANCH TAKE-OFFS TO HAVE A HIGH EFFICIENCY FITTING. SEE DETAIL.
9. INSTALL TURNING VANES IN ALL SQUARE LOW PRESSURE DUCTWORK.
10. DETAILS REFERENCE ALL SHEETS.
11. UNLESS OTHERWISE NOTED, ALL SUPPLY DIFFUSERS SHALL BE OF THE CD-1 TYPE, ALL RETURN GRILLES SHALL BE OF THE RG-1 TYPE AND ALL EXHAUST GRILLES SHALL BE OF THE EX-1 TYPE.




3 ROOFTOP UNIT CURB DETAIL
ME501 NO SCALE




5 RETURN AIR SOUND BOOT DETAIL
ME501 NO SCALE




6 GAS FIRED UNIT HEATER
ME501 NO SCALE




1 SLOT DIFFUSER DETAIL
ME501 NO SCALE



2 ROOF MOUNTED EXHAUST FAN DETAIL
ME501 NO SCALE




4 ROOFTOP UNIT DETAIL
ME501 NO SCALE



Axis Architects

352 SOUTH DENVER STREET(440 E.) SALT LAKE CITY UTAH 84111 P 355-3003 F 355-0113



UVSC - STUDENT
CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS

Revision # Date

Axis Job # 0721
Owner #
Date 5-30-2008
Drawn EL
Checked WB

MECHANICAL DETAILS

ME501



PACKAGED ROOFTOP UNIT SCHEDULE																												
ID	MANUFACTURER	MODEL NO.	AREA SERVED	SUPPLY FAN			HEATING NATURAL GAS					COOLING (3) EVAPORATOR						FILTER	ELECTRICAL					WEIGHT (LBS.) (5)	SOUND		NOTES	
				AIRFLOW RATE (CFM)	EXT. S.P. (IN. H2O)	OA (CFM)	EAT (°F)	LAT (°F)	MBH		OUTPUT (2) 2ND STG.	EAT		LAT		CAPACITY			SEER (6)	MCA	MOCP	SUPPLY FAN MOTOR (HP)	SINGLE POINT VOLT/PH/HZ		DISCH. (A-Wt. dB)	OUTDOOR (A-Wt. dB)		
									1ST STG.	2ND STG.		DB (°F)	WB (°F)	DB (°F)	WB (°F)	TOTAL (MBH)	SENS. (MBH)											
RTU-1	CARRIER	48PGL-06	RM. 103 NORTH	1,500	1.00	260	59.5	94.8	52.5	75.0	48.6	78.6	64.0	52.0	50.6	54.6	36.5	14.6	7	30.1	45	0.69	208-3-60	1,100	74.4	78.0	1, 3, 4	
RTU-2	CARRIER	48PGL-05	RM. 103 SOUTH	1,150	1.00	260	55.7	101.8	52.5	75.0	48.6	79.8	64.0	52.8	51.0	42.7	29.6	14.8	7	25.4	30	0.51	208-3-60	1,100	72.6	72.0	1, 3, 4	
<div>1. CAPACITIES AT 4,500 FT. ELEVATION.</div> <div>2. INPUT AT SEA LEVEL. OUTPUT AT 4,500 FT. ELEVATION</div> <div>3. CONDENSER ENTERING AIR DRY BULB TEMP. = 95F. R-410A REFRIGERANT.</div> <div>4. 100% ECONOMIZER, 100% MODULATING POWERED RELIEF; STAINLESS STEEL HEAT EXCHANGER; PROVIDE SPRING ISOLATION BASE WITH KIT TO ENCLOSE ENTIRE CURB WITH GYP. BD. FOR SOUND CONTROL.</div> <div>5. MANUFACTURE'S LIST WEIGHT INCLUDING SPECIFIED ACCESSORIES.</div> <div>6. SEER RATING DETERMINED PER ARI STANDARDS 210-94 AND 360-95.</div> <div>7. SOUND RATING DETERMINED PER ARI STANDARDS 270-2001 AND 370-2001.</div>																												

GAS UNIT HEATER SCHEDULE														
ID	MANUFACTURER AND MODEL NUMBER	LOCATION	TYPE	USE TYPE	VENT CONN./ COMB. AIR (IN) (2)	AIRFLOW RATE (CFM) (1)	INPUT HEATING LOAD (MBH) (1)	OUTPUT HEATING LOAD (MBH) (1)	ELECTRICAL				WEIGHT (LBS)	NOTES
									FAN MOTOR HP	FAN MOTOR RPM	MOC	VOLT/PH/HZ		
UH-1	REZNOR UDAS-45	STORAGE	NATURAL GAS	HEATING	4 / 4	629	45	30.6	1/30	1550	15	120/1/60	75	(1) (3)
<div>1. GAS HEATING INPUT AT SEA LEVEL, ALL OTHER CAPACITIES AT PROJECT ELEVATION = 4,500 FT.</div> <div>2. SEALED COMBUSTION.</div> <div>3. DIRECT DRIVE OPEN MOTOR WITH INTEGRAL OVERLOAD PROTECTION WITH BUILT IN DISCONNECT.</div>														

EXHAUST FAN SCHEDULE													
ID	MANUFACTURER AND MODEL NUMBER	AREA SERVED	AIR		FAN	ELECTRICAL				PHYSICAL		NOTES	
			MAXIMUM AIRFLOW RATE (CFM)	STATIC PRESSURE (IN. WATER)	FAN SPEED (RPM)	MOTOR SIZE (HP)	MOTOR BHP (HP)	MOTOR SPEED (RPM)	VOLT/PH/HZ	WEIGHT	SONES		
EF-1	LOREN COOK ACE-B 100	STORAGE RM. 102	700	0.25	1,472	1/6	0.09	1,750	120 / 1 / 60	100	8.4	1, 2, 3	
<div>1. ALL CAPACITIES AT 4,500 FEET ELEVATION.</div> <div>2. ROOF MOUNT EXHAUST FAN, COMPETE WITH FACTORY PRE-FAB CURB, BELT DRIVE MOTOR, GRAVITY BACKDRAFT DAMPER, BIRD SCREEN, AND INTEGRAL THERMAL OVERLOAD PROTECTION. DISCONNECT BY DIV. 16.</div> <div>3. CONTROL: BY ATC.</div>													

DRYER BOOSTER FAN SCHEDULE								
ID	MANUF. AND MODEL NO.	LOCATION	SERVICE	FAN		MOTOR		NOTES
				TOTAL AIR FLOW RATE (CFM)	TOT. STATIC PRESSURE DROP (IN H2O)	WATTS	VOLT/PH	
BF-1	ALDES	A-4HP	LOCKER RM.	120	0.1	80	112/1/60	1, 2, 3
<div>1. ALL CAPACITIES AT 4500 FT. ELEVATION.</div> <div>2. INLINE DRYER BOOSTER FAN: BACKWARD CURVED INLINE FAN, THERMAL OVERLOAD PROTECTION AND DISCONNECT SWITCH, AND MOUNTING BRACKET.</div> <div>3. PROVIDE DRYER OPERATION PRESSURE SENSOR WITH TIMER/SWITCH.</div>								

GRILLES, REGISTERS AND DIFFUSERS				
ID	MANUFACTURER	MODEL	MAX NC	DESCRIPTION
CD-1	EH PRICE	SDS 100	30	2 SLOT LINEAR CEILING DIFFUSER WITH FULLY ADJUSTABLE AIR PATTERN AND FLOW CONTROL VANES FOR ONE OR TWO WAY THROW PATTERN. UNITS SHALL HAVE 1" SLOTS AND INSULATED PLENUM WITH ROUND DUCT CONNECTION. FOR SURFACE OR LAY-IN MOUNTING AS REQ'D.
RG-1	EH PRICE	PDDR	30	PERFORATED FACE RETURN AIR UNIT, REMOVABLE FACE & CORE. FRAME SHALL BE FOR SURFACE OR LAY-IN MOUNTING AS REQUIRED BY CEILING TYPE. LAY-IN FRAMES SHALL BE 24"x24", 24"x12" OR 12" x 12" AS REQUIRED TO FIT CEILING TILE SPACE AVAILABLE. AIR QUANTITY SHALL MATCH EXHAUST AIR
EG-1	EH PRICE	PDDR	30	PERFORATED FACE EXHAUST AIR UNIT, REMOVABLE FACE & CORE. FRAME SHALL BE FOR SURFACE OR LAY-IN MOUNTING AS REQUIRED BY CEILING TYPE. LAY-IN FRAMES SHALL BE 24" x 24", 24" x 12" OR 12"x12" AS REQUIRED TO CEILING TILE SPACE AVAILABLE.
SWR-1	EH PRICE	535	30	SIDEWALL RETURN AIR GRILLE. HORIZONTAL STATIONARY 45 DEGREE DEFLECTION VANES ON 1/2 INCH CENTER.




UVSC - STUDENT
CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS


Revision # Date	
Axis Job #	0721
Owner #	
Date	5-30-2008
Drawn	EL
Checked	WB
MECHANICAL SCHEDULES	

ME601


Axis Architects

352 SOUTH DENVER STREET(440 E.) SALT LAKE CITY UTAH 84111 P 355-3003 F 355-0113





Axis Architects




Revision # Date


Axis Job # 0721
Owner #
Date 5-30-2008
Drawn EL
Checked WB

MECHANICAL PLAN

MH101


352 SOUTH DENVER STREET(440 E.) SALT LAKE CITY UTAH 84111 P 355-3003 F 355-0113





Axis Architects

352 SOUTH DENVER STREET(440 E.) SALT LAKE CITY UTAH 84111 P 355-3003 F 355-0113




UVSC - STUDENT CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS

Revision #	Date


Axis Job # **0721**
Owner #
Date **5-30-2008**
Drawn **EL**
Checked **WB**

PLUMBING DEMOLITION PLAN

PD101



A1 DANCE & STORAGE PLUMBING PLAN
SCALE: 1/8"=1'-0"
PROJECT NORTH




A4 DANCE & STORAGE PLUMBING PLAN
SCALE: 1/8"=1'-0"
PROJECT NORTH

- # KEYED NOTES**
- EXISTING CATCH BASIN TO REMAIN.
 - EXISTING STORM DRAIN DRAIN MANHOLE TO REMAIN.
 - EXISTING SANITARY SEWER MANHOLE TO REMAIN.
 - EXISTING PIPING TO REMAIN.
 - EXISTING WASHER AND RELATED PIPING TO REMAIN.
 - (SPSIG) TO 4 OZ. GAS PRESSURE REGULATOR 225 CFH, VENT TO OUTSIDE.
 - MECHANICAL EQUIPMENT. SEE MECHANICAL DRAWINGS.
 - EXISTING GREASE SEPARATOR TO REMAIN.
 - EXISTING SINK AND RELATED PIPING TO REMAIN.
 - PROVIDE FIRE SPINKLER COVERAGE IN NEW ADDITION. CONNECT TO EXISTING FIRE SPINKLER MAIN. PROVIDE QUICK RESPONSE SPINKLER HEADS THAT MATCH EXISTING CONTRACTOR TO FIELD VERIFY EXISTING SYSTEM.
 - PROVIDE DRY PENDENT SPINKLER HEAD IN WALK-IN REFRIGERATOR.


PLUMBING FIXTURE SCHEDULE						
ID	FIXTURE	CW (IN)	HW (IN)	W (IN)	V (IN)	NOTES
DSN-1	DOWNSPOUT NOZZLE					SEE PLANS
RD-1	ROOF DRAIN					SEE PLANS
RDO-1	ROOF DRAIN OVERFLOW					SEE PLANS

1. ALL UNDER GROUND WASTE AND VENT SHALL BE 2" OR GREATER PER DRAWINGS.



Axis Architects

352 SOUTH DENVER STREET(440 E.) SALT LAKE CITY UTAH 84111 P 355-3003 F 355-0113



UVSC - STUDENT CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS

Revision # Date

Axis Job # 0721
Owner #
Date 5-30-2008
Drawn EL
Checked WB

PLUMBING PLAN



PP101

GENERAL NOTES

- CONSULT ARCHITECTURAL REFLECTED CEILING PLANS FOR EXACT LOCATION OF ALL LIGHTING FIXTURES.
- VERIFY ALL EQUIPMENT DIMENSIONS AND LOCATIONS BEFORE BEGINNING ROUGH IN. CONSULT ALL APPLICABLE CONTRACT DRAWINGS AND SHOP DRAWINGS TO INSURE NEC CODE CLEARANCES REQUIRED AROUND ALL ELECTRICAL EQUIPMENT.
- CONTRACTOR SHALL VERIFY ALL ELECTRICAL LOADS (VOLTAGE, PHASE, CONNECTION REQUIREMENTS, ETC.) OF EQUIPMENT FURNISHED UNDER DIVISION 15 WITH APPROVED MECHANICAL SHOP DRAWINGS BEFORE BEGINNING ROUGH IN.
- SEE SECTION 16510 OF THE SPECIFICATION REQUIRED COORDINATION MEETINGS WITH MECHANICAL AND CEILING CONTRACTORS.
- SEE APPLICABLE SHOP DRAWINGS FOR ROUGH IN LOCATION OF ALL EQUIPMENT, WIRING DEVICES, ETC. WHERE APPLICABLE MOUNT ALL WIRING DEVICES ABOVE BACK SPLASH EXCEPT THOSE SERVING UNDER COUNTER EQUIPMENT.
- SEE SPECIFICATION FOR ENERGY SAVING LAMP AND BALLAST REQUIREMENTS.
- FINISHES OF ALL LIGHT FIXTURES SHALL BE AS SELECTED BY ARCHITECT.
- THE ELECTRICAL CONTRACTOR SHALL NOTIFY AND COOPERATE WITH THE MECHANICAL CONTRACTOR SUCH THAT NO PIPING, DUCTS, OR EQUIPMENT FOREIGN TO THE OPERATION OF THE ELECTRICAL EQUIPMENT SHALL BE PERMITTED TO BE INSTALLED IN, ENTER OR PASS THRU ELECTRICAL ROOMS OR SPACES, OR ABOVE OR BELOW ELECTRICAL EQUIPMENT IN OTHER AREAS.
- ELECTRICAL BOXES SHALL NOT BE LOCATED IN MASONRY COLUMNS IN BRICK WALLS OR IN GROUTED CELLS ADJACENT TO OPENINGS. COORDINATE LOCATION OF BOXES WITH MASONRY CONTRACTOR.
- ALL PENETRATIONS OF FIRE RATED FLOORS, WALLS, AND CEILINGS SHALL BE SEALED WITH APPROVED MATERIAL TO MAINTAIN FIRE RATING OF SURFACE PENETRATED.
- CIRCUITS EXTENDING OVER 70' FOR 120 VOLT AND 165' FOR 277 VOLT 20 AMP CIRCUITS SHALL BE RUN WITH MINIMUM #10 CONDUCTORS.

DEMOLITION NOTES

- COORDINATE ALL NEW ELECTRICAL EQUIPMENT REQUIREMENTS AND MAKE CONNECTION TO EXISTING SYSTEMS. THIS INCLUDES LIGHTING, POWER, SIGNAL, RACEWAY AND OTHER SYSTEMS INCLUDED UNDER DIVISION 16.
- RELOCATE, REWIRE AND/OR RECONNECT EXISTING ELECTRICAL DEVICES AND/OR EQUIPMENT THAT FOR ANY REASON OBSTRUCTS CONSTRUCTION.
- CONCEAL ALL RACEWAY AND WIRING IN EXISTING WALLS, CEILINGS, FLOORS, ETC. EXCEPT WHERE THE USE OF SURFACE METAL RACEWAYS (E.G. WIRE MOLD) IS INDICATED ON DRAWINGS OR IN SPEC.
- LEAVE ALL EXISTING EQUIPMENT, IN PORTIONS OF THE BUILDING NOT BEING REMODELED, IN WORKING CONDITION. RESTORE ALL INTERRUPTED BRANCH CIRCUITS, FEEDERS, ETC. TO WORKING CONDITION.
- EXISTING RACEWAYS MAY BE REUSED (IN PLACE) WHERE POSSIBLE, AND WHERE IN COMPLIANCE WITH THE SPECIFICATIONS AND THE INTENT OF THE CONTRACT DOCUMENTS. INSURE INTEGRITY OF EXISTING RACEWAY BEFORE REUSE.
- REMOVE ALL RACEWAYS, CONDUCTORS, BOXES, DEVICES, EQUIPMENT, ETC. THAT ARE NOT TO BE REUSED.
- REMOVE EXISTING LIGHT FIXTURES WHICH ARE NOT TO BE REUSED, PLACE IN CARTON, LABEL APPROPRIATELY, AND RETURN TO OWNER, OR PROPERLY DISPOSE OF FIXTURES THAT THE OWNER CHOOSES NOT TO KEEP.
- DO NOT PENETRATE STRUCTURAL ELEMENTS OF FLOORS, WALLS, CEILINGS, ROOFS, ETC.
- DISCONNECT AND RECONNECT ANY/ALL FIXTURES, DEVICES, EQUIPMENT, ETC. REQUIRED FOR PROPER COMPLETION OF THE WORK.



FIXTURE SCHEDULE

TYPE	DESCRIPTION	CATALOG NUMBER	VOLTS	LAMPS
A	2 X 4 LAY-IN; 24 AMP; A12.125 ACRYLIC LENS CAM LATCHES	LITHONIA 2SP9 G 232 A12125 277 EB	277	(2) F32 T8 835
B	2 X 2 LAY-IN INDIRECT; 24 LAMPS	LITHONIA 2AV G 217 SBL 277 EB	277	(2) F17 8 835
XI	DECAST EXIT LIGHT	LITHONIA LES W G 1120277	277	INCLUDE

EQUIPMENT SCHEDULE

UNIT #	FUNCTION	LOAD	VOLT	PHASE	FULL LOAD	AMPS	CONDUIT SIZE	WIRES				OCPD		REF. NOTES		REMARKS
								NO. SETS	NO.	SIZE	EQUIP. WDG (")	TYPE	AMPS	STARTER	DISCONNECT	
BF-1	BOOSTER FAN	80 VA	120	1	0.67	3/4"	1	2	12	12	CB	15	4A			
EF-1	EXHAUST FAN	16 HP	120	1	4.40	3/4"	1	2	12	12	CB	15	4A			
RTU-1	ROOFTOP UNIT	30.1 MCA	208	3	24.08	3/4"	1	3	8	10	CB	45	2A			
RTU-2	ROOFTOP UNIT	25.4 MCA	208	3	20.32	3/4"	1	3	10	10	CB	30	2A			
UH-1	UNIT HEATER	120 HP	120	1	2.00	3/4"	1	2	12	12	CB	15	4A			

NOTES:

- NON-FUSED DISCONNECT SWITCH
- FUSED DISCONNECT SWITCH
- BREAKER IN ENCLOSURE
- MANUAL STARTER WITH THERMAL OVERLOAD
- MAGNETIC STARTER
- MAGNETIC STARTER/NON-FUSED DISCONNECT COMBINATION
- MAGNETIC STARTER/FUSED DISCONNECT COMBINATION
- MAGNETIC STARTER/BREAKER COMBINATION
- VARIABLE FREQUENCY DRIVE
- REDUCED VOLTAGE STARTER
- DIRECT CONNECTION
- RECEPTACLE/SPECIAL PURPOSE OUTLET/ETC.
- TWO-SPEED STARTER, COORDINATE WITH MOTOR TYPE

- FURNISHED, INSTALLED, AND CONNECTED UNDER DIVISION 16
- FURNISHED AND INSTALLED UNDER ANOTHER DIVISION REQUIRING CONNECTION UNDER DIVISION 16.
- FURNISHED UNDER ANOTHER DIVISION BUT INSTALLED AND CONNECTED UNDER DIVISION 16.
- FURNISHED, INSTALLED AND CONNECTED UNDER ANOTHER DIVISION.

CB = CIRCUIT BREAKER - THERMAL MAGNETIC
CHW = CHILLER W/LOW WATTS

NOTE 1: PER 250.122(A), EQUIPMENT GROUND IS NOT REQUIRED TO BE LARGER THAN PHASE CONDUCTOR.

ELECTRICAL SYMBOL SCHEDULE

- SEE FIXTURE SCHEDULE FOR TYPE, MOUNTING AND WATTAGE.
- HEIGHT MEASURED TO CENTER LINE OF THE BOX FROM THE FINISH FLOOR.
- REFER TO DRAWINGS FOR DIRECTIONAL ARROWS.
- SUBSCRIPT KEYS SWITCH TO FIXTURES CONTROLLED.
- NEMA TYPE 'ND' NON-FUSED UNNOTED 'F' (FUSED). USE 'HD' 480 V.
- HEIGHT TO BE THE LOWER OF EITHER 80" A.F.F. OR 6" BELOW CEILING.
- PROVIDE H.O.A. AND S.S. PUSHBUTTONS AS REQUIRED.

- DOUBLE ARROWS DENOTE A DOUBLE FACE UNIT.
 - COORDINATE WITH MILLWORK SHOP DRAWINGS AND ELEVATIONS FOR HEIGHT.
 - SUBSCRIPT DENOTES NEMA CONFIGURATION.
 - HEIGHT MEASURED TO BOTTOM OF THE BOX FROM FINISH FLOOR.
- * TYPICAL SYMBOL SCHEDULE. SOME SYMBOLS MAY NOT BE USED IN THIS SET OF DRAWINGS.




STANDARD MOUNTING HEIGHT UNLESS OTHERWISE NOTED ON PLANS			
SYMBOL	DESCRIPTION	MOUNTING HEIGHT	NOTES
→	ONE CIRCUIT, TWO WIRE HOME RUN TO PANEL		
→→	2 CIRCUIT, 3 WIRE, COMMON NEUTRAL HOME RUN		
→→→	3 CIRCUIT, 4 WIRE, COMMON NEUTRAL HOME RUN		
→→→→	CONDUIT RUN CONCEALED IN WALL OR CEILING		
-----	CONDUIT RUN CONCEALED IN FLOOR OR GROUND		
○	CONDUIT UP		
●	CONDUIT DOWN		
—○	CONDUIT STUB LOCATION	CAP CONDUIT	
≡	CABLE TRAY	AS NOTED	
○	CEILING LIGHT FIXTURE	CEILING	1.
⊙	WALL LIGHT FIXTURE	AS NOTED	1.
⊠	RECESSED DOWNLIGHT FIXTURE	CEILING	1.
⬢	FLUORESCENT LIGHT FIXTURE	AS NOTED	1
⬢⬢	FLUORESCENT EGRESS LIGHT FIXTURE	AS NOTED	UNSWITCHED
●	AREA LIGHT POLE AND FIXTURE	CONCRETE BASE	SEE DIAGRAM
⬢	FLOOD OR TRACK FIXTURE	AS NOTED	
⊗	CEILING MOUNTED EXIT LIGHT	CEILING	1.3.8.
⊙	WALL MOUNTED EXIT LIGHT	AS NOTED	1.3.8.
\$	SINGLE POLE SWITCH	+4'-0"	2.
\$ ^a	SINGLE POLE SWITCH	+4'-0"	4. 2.
\$ ³	THREE-WAY SWITCH	+4'-0"	2.
\$ ⁴	FOUR-WAY SWITCH	+4'-0"	2.
\$ ^K	KEY OPERATED SWITCH	+4'-0"	2.
\$ ^P	SWITCH WITH PILOT LIGHT	+4'-0"	2.
\$ ^D	VARIABLE INTENSITY SWITCH	+4'-0"	2.
\$ TM	TIMER SWITCH	+4'-0"	2.
\$	MOMENTARY CONTACT SWITCH, CENTER POSITION OFF	+4'-0"	2.
⊙	OCCUPANCY SENSOR	CEILING	
⊙	OCCUPANCY SENSOR	+4'-0"	2.
⊙	POWER PACK	CEILING	SEE DIAGRAM, SPEC.
⊙	AUTOMATIC RELAY PACK	CEILING	SEE DIAGRAM, SPEC.
⊙	LOW VOLTAGE TRANSFORMER		
⊙	DUPLEX RECEPTACLE	UPPER OUTLET SWITCH CONTROLLED	+16" OR AS NOTED 9. 11.
⊙	SIMPLEX RECEPTACLE	+16" OR AS NOTED	9. 11.
⊙	DUPLEX RECEPTACLE	+16" OR AS NOTED	9. 11.
⊙ _A	DUPLEX RECEPTACLE		9.
⊙ _W	ELECTRIC WATER COOLER RECEPTACLE		SEE DIAGRAM
⊙ _{WP}	WEATHERPROOF RECEPTACLE	+24" OR AS NOTED	2. 9.
⊙ _{IG}	ISOLATED GROUND RECEPTACLE	+16" OR AS NOTED	9. 11.
⊙	GROUND FAULT INTERRUPTER DUPLEX RECEPTACLE	+16" OR AS NOTED	9. 11.
⊙	DUPLEX RECEPTACLE EMERGENCY POWER (RED)	+16" OR AS NOTED	9. 11.
⊙	FOURPLEX RECEPTACLE	+16" OR AS NOTED	9. 11.
⊙	FOURPLEX RECEPTACLE EMERGENCY POWER (RED)	+16" OR AS NOTED	9. 11.
⊙	FLOOR OUTLET WITH 20A DEVICE	FLOOR	
⊙	MULTIPLE SERVICE FLOOR BOX	FLOOR	
⊙	SPECIAL PURPOSE OUTLET	+16" OR AS NOTED	10. WITH CAP. 11.
⊙	CORD DROP		SEE DIAGRAM
⊙	PLUGMOLD	+46" OR AS NOTED	
⊙	TELEVISION OUTLET	+16" OR AS NOTED	11.
⊙	DATA OUTLET	+16" OR AS NOTED	9. 11.
⊙	TELEPHONE OUTLET	+16" OR AS NOTED	9. 11.
⊙	TELEPHONE/DATA OUTLET	+16" OR AS NOTED	9. 11.
⊙	TELEPHONE OUTLET	FLOOR	
⊙	CALL SWITCH	+4'-0"	2.
⊙	CLOCK OUTLET	+7'-6"	8.
⊙	CLOCK/SPEAKER COMBINATION	+7'-6"	

STANDARD MOUNTING HEIGHT UNLESS OTHERWISE NOTED ON PLANS			
SYMBOL	DESCRIPTION	MOUNTING HEIGHT	NOTES
⊙	JUNCTION BOX ('F' IN FLOOR)	AS NOTED	
⊙	MOTOR OUTLET	TO SUIT EQUIP.	
⊙	PHOTO-ELECTRIC CONTROL	AS NOTED	TORK 2000A
⊙	TIME CLOCK	+5'-0"	2.
⊙	PUSHBUTTON	+4'-0"	2.
⊙	NON-FUSED DISCONNECT SWITCH	+5'-0"	5.
⊙	FUSED DISCONNECT SWITCH	+5'-0"	5.
⊙	MANUAL STARTER THERMAL OVERLOAD SWITCH WITH PILOT LIGHT	+4'-0"	2.
⊙	MAGNETIC STARTER	+5'-0"	7.
⊙	MAGNETIC STARTER / DISCONNECT COMBINATION	+5'-0"	
⊙	VARIABLE FREQUENCY DRIVE	+6'-6"	
⊙	PANEL BOARD	TOP AT +6'-0"	
⊙	MAIN DISTRIBUTION PANEL		
⊙	TELEPHONE TERMINAL BOARD		
⊙	BELL	+7'-6"	
⊙	CHIME	+7'-6"	
⊙	FIRE ALARM MANUAL STATION	+4'-0"	2.
⊙	FIRE ALARM SIGNAL HORN/STROBE PROJECTORS	+6'-8"	6.
⊙	FIRE ALARM SIGNAL HORN/STROBE	+6'-8"	6.
⊙	FIRE ALARM SIGNAL SPEAKER/STROBE	+6'-8"	6.
⊙ _S	SMOKE DETECTOR	CEILING	
⊙ _D	DUCT SMOKE DETECTOR		MTD. IN DUCT
⊙ _H	HEAT DETECTOR	CEILING	
⊙	FIRE/SMOKE DAMPER		
⊙	DOOR HOLDER	AS NOTED	
⊙ _S	FLOW SWITCH		
⊙ _S	TAMPER SWITCH		
⊙ _W	WATER FLOOD INDICATOR		
⊙	O.S. & Y. VALVE		SEE DIAGRAM
⊙	FIRE ALARM RELAY		
⊙	FIRE ALARM CONTROL MODULE		
⊙	FIRE ALARM MONITOR MODULE		
⊙	FIRE ALARM STROBE	+6'-8"	6.
⊙ _D	DURESS PUSHBUTTON	+4'-0"	
⊙ ₁	SECURITY SYSTEM DOOR SWITCH	DOOR JAMB	
⊙ ₂	SECURITY SYSTEM OVERHEAD DOOR SWITCH	CEILING	MOUNT AS PER. MAN
⊙	MAGNETIC SHEAR LOCK		
⊙	SECURITY SYSTEM KEYED ACCESS SWITCH	+4'-0"	2.
⊙	INFRARED SENSOR	AS NOTED	
⊙	SECURITY MOTION DETECTOR		MOUNT AS PER. MAN
⊙	GLASS BREAK DETECTOR	CEILING	
⊙	ELECTRIC DOOR STRIKE		
⊙	ACCESS CONTROL CARD READER	+4'-0"	2.
⊙	CLOSED CIRCUIT TELEVISION CAMERA	AS NOTED	
⊙	DOOR POSITION INDICATING SWITCH		
⊙ _#	SOUND SYSTEM SPEAKER	+8'-0" OR AS NOTED	
⊙ _{IC}	INTERCOM SPEAKER	AS NOTED	
⊙ _V	VOLUME CONTROL	+4'-0"	2.
⊙ _M	MICROPHONE OUTLET	+16"	11.
⊙ _M	MICROPHONE FLOOR OUTLET	FLOOR	
⊙ _M	MICROPHONE CEILING OUTLET	CEILING	
⊙	SOUND EQUIPMENT CABINET		CIRCUIT TO 120V
842	ARCHITECTURAL ROOM NUMBER		
A	LIGHT FIXTURE (LETTER DESIGNATES TYPE)		
EQ 34	EQUIPMENT NUMBER		

INDEX OF ELECTRICAL DRAWINGS

EG001 SYMBOLS, SCHEDULES AND NOTES

EX101 ELECTRICAL PLAN



UVCS - STUDENT
CENTER ADDITION
OREM, UTAH

CONSTRUCTION DOCUMENTS



Revision # Date

Axis Job # 0721
BNA Job #
Owner #
Date 05-23-2008
Drawn BNA
Checked

SYMBOLS, SCHEDULES
AND NOTES


EG001

By: jwehner; Jun 02, 2008 - 5:24pm
F:\2008\111A.DRW\111A-EX101.dwg



- SHEET KEYNOTES
- 1 CIRCUIT TO NEW 20 AMP 1 POLE CIRCUIT BREAKERS IN EXISTING PANEL INDICATED.
 - 2 PANEL H3 IS LOCATED ON LEVEL 2 BETWEEN GRIDS G1 AND G2 AT GRID 6.5.
 - 3 CIRCUIT EXIT LIGHTS TO EXISTING HALLWAY EMERGENCY EXIT LIGHT CIRCUIT.
 - 4 CONNECT NEW HORN/STROBE INTO EXISTING HALLWAY INDICATING LOOP.
 - 5 PROVIDE A 1" CONDUIT TO THE COMMUNICATIONS CABLETRAY. PROVIDE PULL CORD.
 - 6 CIRCUIT TO A NEW 3 POLE CIRCUIT BREAKER IN EXISTING PANEL INDICATED. SEE EQUIPMENT SCHEDULE FOR SIZES.

635 South State Street
Salt Lake City, Utah 84111
P: 801.535.2305
www.bnaconsulting.com



Axis Architects

UVCS - STUDENT
CENTER ADDITION
OREM, UTAH
CONSTRUCTION DOCUMENTS

Revision # Date

Axis Job # 0721
BNA Job #
Owner #
Date 05-23-2008
Drawn BNA
Checked

ELECTRICAL PLAN

EX101